



**LEGEND**

EXISTING		PROPOSED
-----	KERBING (SEMI-MOUNTABLE)	—————
-----	KERBING (FLUSH)	-----
-----	KERBING (MOUNTABLE)	-----
-----	KERBING (BARRIER)	-----
-----	KERBING (SM-SPECIAL)	-----
-----	FOOTPATH (CONCRETE)	-----
-----	KERB RAMP	-----
-----	GRAB RAIL	-----

**NOTES:**

- CADASTRAL INFORMATION APPROXIMATE ONLY.
- KERBING TO BE CONSTRUCTED IN ACCORDANCE WITH CITY OF WANNEROO DRG. No TS 05-1 TO TS 05-3
- ALL DISTURBANCES TO EXISTING VERGE RETICULATION AND TURFING TO BE REINSTATED.
- TACTILE PAVING TO BE CONSTRUCTED IN ACCORDANCE WITH CITY OF WANNEROO DRG. No TS 09-07-3.
- NO TREE TO BE REMOVED.
- FOR REPORT ON TREE REFER TRIM No.15/84063.

**CITY OF WANNEROO**  
**INFRASTRUCTURE**

**AMERY ROAD**  
 CADOUX LOOP TO EXISTING PATHWAY  
 CONSTRUCTION SHARED PATH  
 HOCKING

**CONSTRUCTION PLAN**  
 SHEET 1 OF 1

DRAWING No. SHEET REVISION ORIGINAL DRG. SIZE  
**3102 - 1 - 0** A1

No.	REVISION	BY	DATE	AUTH	No.	REVISION	BY	DATE	AUTH	SCALE:	2.5	0	2.5	5.0	7.5	10.0	12.5	SURVEYED:	NEARMAP	2/2015	DRAWN:	D. NGUYEN	5/2015	AUTHORISED:	FILE No.	19451					
0	ISSUED FOR CONSULTATION	DN	5/2015							1:250	SCALE IN METRES						DATUM:	LOCAL	GRD:	LOCAL	DESIGNED:	D. NGUYEN	3/2015	CHECKED:	COORDINATOR DESIGN	2/2015	APPROVED:	MANAGER INFRASTRUCTURE PROJECTS	2/2015	PROJECT No.	PR - 2502