

Landscape Vegetation Survey for Atlantis Childcare Centre

10 Harbour Elbow, BANKSIA GROVE





Site – 10 Harbour Elbow, Banksia Grove - Aerial photo & Cadastral



Table of Contents

Brief

Approach

Site - Existing Trees Species

Landscape – LC – 01- Development & Bushfire Response – Tree Survey

Landscape - LC- 02 - Development & Bushfire Response - Tree Removal Plan

Landscape — LC-03 - Development & Bushfire Response — Landscape Concept Plan

Landscape – LC-04 – Development – Fencing Plan

TPZ & SRZ definitions

Summary

Example of tree protection fencing

Contractor Specification for tree protection

Tree Survey Photos



Brief

The Client "Atlantis Childcare Centre" commissioned eScape landscape architecture to consult, inspect and complete a report to meet council's requirements for a landscape plan & tree survey to be completed as part of the planning approval submissions which forms part of the resubmission to council for the proposed childcare facility at the site address.

The site located in Banksia Grove in the City Of Wanneroo, Adjacent Neaves road and Old Yanchep Road. The block is 5003m2 with an existing house, shed, and established gardens currently on the block. The client proposes to use the property for a new childcare centre.

The objective of the survey was to assess the existing native remanent vegetation based on the preliminary works plan and provide a basis for a suitable landscape plan outlining the retention and removal of trees and vegetation. Key to this plan is the orientation and location of the building and the carpark, egress to and from the building, situated play spaces, and suitable buffering from adjacent properties. The survey is to establish the trees species, size, condition and location.

Approach

This eScape landscape architecture obtained a preliminary works plan from the client along with a feature survey, positioning the trees accurately on the site along with the proposed carpark location and proposed building outline. A visual site assessment of the trees was then undertaken to determine the species, size of canopy, health and suitability for retention. A Landscape Vegetation Study and a Tree Removal Plan was then completed to help facilitate the landscaping concept masterplan for submission to council along with the other consultant's reports.



Site - Existing Tree Species

The site has a number of well-established native trees generally in good to fair condition. A number of dead trees are present marked on the *Landscape Vegetation Study* and some species marked for removal due to their unsuitability on the *Landscape Tree Removal Plan* i.e. Acacia species. The botanical name and common name, condition and notes are referred to in the schedule below and on the tree survey plan.

| BLOCK | CODE | SPECIES | NOTES - SITE ASSESSMENT |
|-------|----------------|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 0 | BANKSIA | CANOLE BANKSIA Banksia attenuata | Generally good condition, requiring clean up and crown lift, some mildew on leaves requiring treatment 2 x Banksia Menziesii marked "BANKSA MEN" suggest trees to fall in non irrigated areas if possible due to susceptibility to irrigation |
| 0 | SHEOAK | COMMON SHEOAK Allocasuarina fraseriana | Generally good condition, requiring clean up and crown lift and removal of dead wood |
| | JARRAH | JARRAH Eucolyptus marginata | Generally good condition, no die back present, 5 x large multi trunk sentinet frees (habitat specimens, * Marked Feature Jarrah), small trees retained for shade in key areas and suitable for shade tree adjacent play spaces |
| (3) | ACACIA | GOLDEN WREATHED WATTLE Acacia saligna | Poor condition, paisonous species suitable for removal. |
| 0 | MARRI | MARRI REDGUM Eucalyptus calophylla | Generally good condition, suitable for shade tree adjacent playspaces |
| 0 | OLIVE | OLIVE SPECIES UNKNOWN | Remnant orchard species suitable for transplant to kitchen garden/ chicken coop etc |
| | FRUIT | MIXED FRUIT TREES REFER TO NOTES | Remnant orchard species suitable for transplant to kitchen garden/ chicken coop etc |
| | GRASS TREE | GRASS TREE Xanthorrhoea preissii | Various small - medium single headed grass trees, suitable for transplant into more suitable areas where removal is required. Suitable for transplant in garden areas away from kids eye level. |
| × | MACRO ZAMIA | MACROZAMIA Macrozamia riedlei | Various medium macrozamia sporatically dotted through verge and tree lines. Suitable for transplant in garden areas away from kids eye level. |

Tree Health

Good — The tree demonstrates good or exceptional growth for the species. The tree exhibits a full canopy of foliage. Minor pest or diseases problems. Foliage colour, size and density should be typical of a healthy specimen.

Fair - The tree demonstrates adequate growth for the species. The tree exhibits an adequate canopy of foliage. There may be some dead wood present in the crown, some grazing by insects, animals and foliage colour and size atypical for a healthy specimen of that species.


Poor - The tree is not growing to its full capacity, extension growth of the laterals may be minimal. The tree exhibits a thinning or sparse canopy of foliage. Large amounts of dead wood present in the crown, significant grazing by insects indicating the stress of the tree declining.

Very Poor – The tree appears to be in a state of decline and the canopy maybe very thin and sparse. Significant volume of deadwood may be present in the canopy and pest and disease problems causing a severe decline.

Dead - The tree is dead




Landscape – LC – 01- Development & Bushfire Response – Tree Survey





Landscape - LC- 02 - Development & Bushfire Response - Tree Removal Plan





Landscape — LC-03 - Development & Bushfire Response — Landscape Concept Plan





Landscape – LC-04 – Development – Fencing Plan



CONSTRUCTION PTY LTD. THEY SHALL NOT BE COPIED OR LENT WITHOUT PRIOR CONSENT OF ESCAPE LANDSCAPE ARCHITECTURAL DESIGN & CONSTRUCTION PTY LTD.

2: CONTRACTORS TO CHECK ALL MEASUREMENTS ON SITE PRIOR TO COMMENCMENT OF WORKS.

3: CONTRACTORS TO CONFIRM DESIGN CHANGES & DISCREPANCIES WITH THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF WORKS.

1: THIS DRAWING AND THE CONCEPTS WITHIN WILL REMAIN THE PROPERTY OF ESCAPE LANDSCAPE ARCHITECTURAL DESIGN &

NOTES:

| | 6 CRESSALL ROAD BALCATTA, WA 6021 |
|------------------------|----------------------------------------|
| landscape architecture | PH: 9201 2772 www.e-scapedesign.com |
| e Scape | |

| DRAWN | C. ABBOTT | 1 | ATLANTIS CHILDCARE CENTRE | |
|---------------------|------------|--------------------------------------|---------------------------------|-------|
| SCALE | 1:200 @ A1 | | 10 HARBOUR ELBOW, BANKSIA GROVE | |
| DATE | 19.03.2019 | LANDSCAPE - DEVELOPMENT FENCING PLAN | | |
| CLIENT | B. HINDLE | | | |
| LANDSCAPE ARCHITECT | | SIZE A1 | DRAWING NO. | REV C |



TPZ – Tree Protection Zone

As per the Australian Standards AS 4970-2009 *Protection of Trees on Development Sites* the tree protection zone (TPZ) is the principal means of protecting the trees on sites where development is to occur. The TPZ is a combination of the root zone and crown area requiring protection. It is isolated from construction disturbance, so that the trees remain viable.


The radius of the TPZ is calculated for each tree by multiplying the (DBH) diameter taken at breast height, DBH x 12. Eg, DBH is $0.5m \times 12 = 6m$ radius (TPZ = 6m measured from centre of the trunk at ground.)

If the proposed encroachment is greater than 10% into the TPZ or SRZ the project landscape architect or suitably qualified arborist must assess the tree to ensure its viability or review the proposed encroachment and suggest alternatives. Refer to the TPZ calculation for AS4970-2009 below fig 02. *An example is shown on the Landscape Tree Removal Plan on the large stands of trees.*

SRZ – Structural Root Zone


This consultant advises that a structural root zone area of a tree is required for tree stability. Using Australian Standards AS 4970-2009 *Protection of Trees on Development sites* the structural root zone area can be calculated when major encroachment into a TPZ is proposed.

If the proposed encroachment is greater than 10% into the TPZ or SRZ the project landscape architect or suitably qualified arborist must assess the tree to ensure its viability or review the proposed encroachment and suggest alternatives. Refer to the SRZ calculation for AS4970-2009 below fig 01.





AS 4978—2009 14



NOTE: Refer to Clause 3.2 for calculation of TPZ.

FIGURE 2 INDICATIVE TREE PROTECTION ZONE

Standards Australia

www.standards.org.au



Summary

This consultant's inspection included approx. 93 trees within the project's site boundaries and verges (Greenvale Place & Harbour Elbow) revealed that they are generally in good/fair condition.

The Tree audit identified out of the 93 specimens;

80 x Trees were native and endemic to the area.

13 x Fruiting trees and exotics, some suitable for transplanting.

51 x Native tree species were marked for retention being in suitable location, condition and species.

32 x approx Native understorey feature transplants were identified for re transplant on the site.

Therefore a total of 74% Native tree species were retained to provide visual amenity, shade and structure to the nature play spaces across the site.

Where trees are being retained it is crucial that designers, contractors and sub-contractors are advised of the potential damage to roots and lower branches from building infrastructure in close proximity to trees. Machinery and vehicles can damage lower canopies, compact and damage tree roots, stock piling of building materials, sand, spoil etc. around trees within TPZ is prohibited. It is recommended that contractors and sub-contractors are notified that works within the TPZ (or canopy drip line) may affect the trees health and if roots over 50mm require pruning they notify a suitable qualified landscape architect or arborist.

It is recommended that all works which are to be carried out within driplines of trees are hand dug using shovels to avoid damage to shallow roots, and common sense relocation of service onsite with appreciation of the trees health taken. All machinery is to be limited inside the TPZ radius and a spotter used if unavoidable.

It is recommended that the following occurs;

- Tree Protection Fencing is erected around each tree or groups of trees to prevent damage to canopies and root zones AS 4970-2007. Refer to Fig. 3.
- Soil levels around the trees out to the TPZ are not raised or lowered.
- Footpaths are installed slightly above natural grade where possible to reduce potential root disturbance.
- Irrigation, Power, Water mainlines, Comms are to be hand dug within the TPZ.
- Banksia's where practicable to fall into non irrigated areas to avoid future issues associated with this species in reticulated zones.


Watering trees is required where site works disturbance has occurred in summer to minimise stress to the trees.

The retained trees are recommended to have dead wood and crossing limbs removed and selectively pruned to avoid the level of risk the trees pose to people and property. It is advised that all remedial tree surgery works be carried out by a competent arborist to the relevant Australian Standards – Pruning of amenity trees 4373-2007. The future management, maintenance and condition of the trees have a considerable bearing on their location, safety to persons/users and property being the



main priority. Therefore each tree is recommended for annual inspection to assess the level of risk to the public/users is deemed acceptable.

Example of Tree Protection fencing from AS 4970-2007



LEGEND:

- 1 Chain wire mesh panels with shade cloth (if required) attached, held in place with concrete feet.
- 2 Alternative plywood or wooden paling fence panels. This fencing material also prevents building materials or soil entering the TPZ.
- 3 Mulch installation across surface of TPZ (at the discretion of the project arborist). No excavation, construction activity, grade changes, surface treatment or storage of materials of any kind is permitted within the TPZ.
 - 4 Bracing is permissible within the TPZ. Installation of supports should avoid damaging roots.

FIGURE 3 PROTECTIVE FENCING FROM AS 4970-2009



Contractor Specification for Tree protection during development works

- To reduce the effects that a building development can have upon the health of retained trees, suitable forms of protection are required together with the steps necessary to limit deterioration of those species left standing on the development site.
- This consultant confirms that there is clear evidence that mature trees are more sensitive to contractor pressure than young and semi-mature specimens, where the younger trees are able to compensate and adapt to new ground conditions by producing new roots. However, although younger trees can exhibit a remarkable tolerance to the adverse effects of building operations and site alterations, this is conditional upon the location and extent of works carried out within the root zone of the tree and therefore the extent of primary root removal.
- As with predominantly most trees they store vast amounts of carbohydrate in their root system, subsequently when major roots are severed the tree is unable to replenish its depleted energy levels, which gradually results in the decline of the canopy and often the death of the tree, with such symptoms often not evident until some years later. Therefore there must be clear recommendations to alleviate detrimental tree damage from the commencement through to the completion of the development, with the recommendations enforced and clearly understood by all contractor staff.
- All trees identified for retention shall be clearly marked and a Tree Protection Zone (TPZ) confirmed prior to the commencement of the development. As per Australian Standard AS 4970-2009 Protection of trees on development sites. The tree protection zone is the principal means of protecting trees on development sites. The TPZ is a combination of the root area and crown area requiring protection. It is an area isolated from construction disturbance, so that the tree remains viable.
- All heavy machinery shall keep outside the tree protection zone, with any roots damaged or torn roots with a diameter of 30mm or more cleanly severed to initiate occlusion and the contractor is to inform the works supervisor of the damage.
- No root pruning shall be carried out to construct boundary walls or to lay services closer than 1.5m from the base of the tree, with the encroaching roots bridged or under-bored for a distance of 1.5m each side of the trunk, with sufficient distance allowed when bridging for the roots to expand.
- Proposed excavations 1.5m to 2.5m away from the base of the trunk with the exposed roots having a diameter less than 30mm diameter shall be cleanly severed to initiate occlusion.
 Roots above 30mm diameter are not to be cut without authorisation from a qualified Arborist.
- No building materials are to be stored or disposed of within the tree protection zone, with
 provisions implemented so that building chemicals do not come into contact with the root
 rhizosphere or the roots themselves.
- Excavated soil shall not be stored or built up around the trunk of the tree. Soil levels will not be changed around the base of trees, either raised or lowered.
- The laying of surface material (Paving or Asphalt Paths & Roadways) within the root plate spread of the tree shall take into consideration the cultural requirements of the tree,



particularly in relation to moisture and oxygen levels, with the retention of a suitable open surface area.

- Any compaction within the root plate zone of the protected tree to lay paving shall be carried out using a plate compactor only.
- Supplementary watering to all retained trees will be required over summer months
 where works are occurring and due to the disturbance of soil and opening up of the site.
 Watering the trees is required to minimise stress on the trees while recommended to water
 deeply a minimum of once per week for a total of 1000 litres per tree for mature trees and 600
 litres for trees less than 8m in height. It is recommended that the water truck or temporary
 watering system, have a wetting agent in the tank to assist to get the water through to sandy
 layer to the trees root system.
- Established trees of good vigour and structure represent an asset to any development site.
 Trees are living organisms that require certain environmental conditions in order to maintain their value as an asset. Damage must be avoided or minimized during the development process and procedures to ensure the protection of trees must be in place at all stages.