

PART TWO

Explanatory Section

Amendment No. 5

Lots 1 + 102 Yanchep Beach Road, Yanchep (Jindowie West)

Agreed Structure Plan No. 40



Title: Lots 1 + 102 Yanchep Beach Road, Yanchep (Jindowie West)
Part Two - Explanatory Section

Prepared for: Department of Communities

CLE Reference: 2122Rep162A

Date: 31 July 2020

Status: Final

Review date: 31 July 2020

Prepared by: CLE Town Planning + Design

Project team: Town Planning + Design - CLE Town Planning + Design
Engineering - Development Engineering Consultants
Hydrology - Development Engineering Consultants
Environmental - Coffey Environments
Bushfire - Entire Fire Management
Acoustic - Lloyd George Acoustics
Landscape Design - EPCAD

This report is for the exclusive use of the Client, pursuant to Agreement between the Client and CLE Town Planning + Design. CLE accepts no liability or responsibility whatsoever in respect of any use of or reliance upon any information contained within this report by anyone who is not party to the Agreement and/or has come into possession of the Report through parties other than the Client or CLE.

CLE is not accountable for any information which may be contained within the Report which has been supplied by others and reproduced by CLE in this report.

Copyright and any other Intellectual Property arising from this report and the provision of the services in accordance with the Agreement belongs exclusively to CLE unless otherwise agreed and may not be reproduced or disclosed to any other person other than the Client without the express written authority of CLE.

Any reproduction by the Client is to reference CLE as the original author.

Plans and figures contained in this report have been prepared for general information purposes only and may inadvertently use uncontrolled data from external sources. CLE does not guarantee the accuracy of the plans and they should not be used for any detailed site design. The content of this report including all plans remains the property of CLE.

CONTENTS

- 1.0 BACKGROUND
 - 1.1 Purpose and Scope
 - 1.2 Lot Details
 - 1.3 Planning Context
- 2.0 PROPOSED AMENDMENT
 - 2.1 Removal of the 'Mixed Use' zone
 - 2.2 Proposed Residential Zone
 - 2.3 R-MD Codes
 - 2.4 Planning and Development (Local Planning Schemes) Regulations 2015
 - 2.5 Substantiality
- 3.0 PLANNING CONSIDERATIONS
 - 3.1 Dwelling Yield
 - 3.2 Employment
 - 3.3 Access
 - 3.4 Transport Noise Management
 - 3.5 Bushfire Hazard Management
- 4.0 CONCLUSION

FIGURES

- Figure 1 Location Plan (CLE Ref. 2125-233-01)
- Figure 2 Site Plan (CLE Ref. 2125-234-01)
- Figure 3 MRS Map (CLE Ref. 2125-235-01)
- Figure 4 City of Wanneroo DPS 2 Map (CLE Ref. 2125-236-01)
- Figure 5 Existing Structure Plan Maps (CLE Ref. 2125-238, 239 and 240)
- Figure 6 Proposed Structure Plan Maps (CLE Ref. 2125-241, 242 and 243A)

APPENDICES

- Appendix 1 Certificate of Title
- Appendix 2 Existing, approved ASP 40 (Part 1)
- Appendix 3 Proposed new Part 1 for ASP 40
- Appendix 4 PTA Advice on South Yanchep Station
- Appendix 5 Transportation Noise Assessment (Lloyd George Acoustics, April 2020)
- Appendix 6 Bushfire Management Plan (Entire Fire Management, March 2020)



1.0 BACKGROUND

1.1 Purpose and Scope

The purpose of this amendment is to modify Agreed Structure Plan No. 40 ('ASP 40') in response to the deletion of the South Yanchep station from plans for the Joondalup railway extension. Specifically, it is proposed that a portion of Lot 9038 Avon Road be rezoned from 'Mixed Use' to 'Residential' with density codings of R40 and R60, and that a Neighbourhood Connector road previously intended to connect the station with the Yanchep District Centre be realigned.

In addition to the proposed rezoning and road reconfiguration, this amendment proposes to insert reference to the R-MD Codes in place of Tables 1A and 1B and bring the format of Part 1 of ASP 40 into consistency with the *Planning and Development (Local Planning Schemes) Regulations 2015*.

1.2 Lot Details

This amendment relates to a portion of Lot 9038 Avon Road, Yanchep ('the amendment area', refer to Figures 1 and 2). It appears on Deposited Plan 67829 and Certificate of Title vol. 2926, folio 205. The amendment area is in the ownership of our Client, the Department of Communities. The Certificate of Title appears at Appendix 1.





Figure 1 - Location Plan
Source: Nearmap



LEGEND
— Amendment Area

Figure 2 - Site Plan
Source: Nearmap

1.3 Planning Context

The amendment area is zoned 'Urban' under the Metropolitan Region Scheme and 'Urban Development' under the City of Wanneroo ('City') District Planning Scheme No. 2 ('DPS 2'). Land in all directions is also zoned 'Urban' under the MRS apart from the Yanchep Secondary College site to the south-west, which is reserved for 'Public Purposes-High School'. Abutting the amendment to the east is land reserved for 'Railways' in the MRS, and Yanchep Beach Road to the north is reserved for 'Other Regional Roads' (refer to Figures 3 and 4).

The amendment area is covered by the Yanchep-Two Rocks District Structure Plan ('the DSP', 2010), the provisions of which have guided subsequent, more detailed structure planning. The applicable Local Structure Plan is Agreed Structure Plan No. 40 ('ASP 40', refer Appendix 2), which is the subject of this amendment. ASP 40 was adopted by the City of Wanneroo in November 2007 and has been amended five times since. ASP 40 fulfils the requirement of DPS 2 (Section 3.14) for subdivision and development in the 'Urban Development' zone to be guided by a structure plan adopted in accordance with the *Planning and Development (Local Planning Schemes) Regulations 2015*.

The amendment area has frontage to Avon Road to the north, Kakadu Road to the west and Morwell Street to the south. Plan 1 of ASP 40 indicates that the amendment area is for 'Residential / Mixed Use' purposes, whilst Plans 2A and 2B clarify that the 'Mixed Use' zone is the applicable zone under DPS 2. To capitalise on the then-planned railway station south of Yanchep Beach Road, the R60, R80/R100 and R160 density codes apply (refer to Figures 5 (a), (b) and (c)).

The amendment area is part of the Jindowie estate being developed by the Department of Communities. The portion of the amendment area coded R60 has been developed, whilst the portion coded R80/R100 and R160 remains vacant.




Figure 3 - Metropolitan Region Scheme Map
Source: WAPC




Figure 4 - City of Wanneroo DSP 2 Map
Source: WAPC




Figure 5 - Existing Structure Plan Maps (b)




Figure 5 - Existing Structure Plan Maps (c)

2.0 PROPOSED AMENDMENT

2.1 Removal of 'Mixed Use' zone

When ASP 40 was approved in 2007, it was anticipated that a station on the extended Joondalup railway would be provided south of Yanchep Beach Road. This would be located between the planned Yanchep and Eglinton stations and be known as 'South Yanchep'. Planning for the Joondalup railway extension, which now forms part of the State Government's Metronet initiative, no longer includes South Yanchep station (refer Appendix 4: PTA Advice on South Yanchep Station). As such, it is necessary to review the planning initiatives that were included as a response to the station, including:

- The 'Mixed Use' zone and the associated R80/100 and R160 density codes; and
- The Activity Corridor linking the Yanchep District Centre and former South Yanchep station site, centred on a Neighbourhood Connector road.

The 'Mixed Use' zone is not specifically addressed in Part 1 of the structure plan report, but DPS 2 (Section 3.5.1) provides the following definition:

"The Mixed Use zone is intended to accommodate a mixture of residential development with small-scale businesses in a primarily residential-scale environment. The predominant uses will be residential, office, consulting, dining and limited retail uses occupying the street frontage of lots".

In the absence of the South Yanchep station, the justification for a mixed-use activity corridor diminishes to the extent that a more residential-focused zoning is more appropriate. The range of commercial activities contemplated in the 'Mixed Use' zone is wholly reliant on foot traffic and a high residential population in close proximity, neither of which will eventuate without the South Yanchep station.

The proposed 'Residential' zone will encourage development whilst facilitating a variety of commercial uses, including childcare centres, consulting rooms, corner stores and home businesses, should market demand be sufficient in future.

2.2 Proposed Residential Zone

Residential development is permissible in the existing 'Mixed Use' zone, but it is more appropriate for ASP 40 to be amended before any further medium-density development is progressed. This ensures that appropriate controls on land use, density and built form are in place. The proposed ASP 40 plans appear as Figures 6(a), (b) and (c).

ASP 40 currently specifies that the R60, R80/100 and R160 density codes apply to any residential component of the amendment area. This reflects the amendment area's proximity to the formerly-planned site of the South Yanchep station. In the absence of the station, replacement of the R80/100 and R160 density codes with the R40 or R60 code is appropriate. This acknowledges the diminished opportunity for a transit-oriented development whilst still facilitating appropriate densities in the walkable catchment of the Yanchep District Centre.

The objectives of State Planning Policy 4.2: Activity Centres for Perth and Peel for residential yield within the walkable catchment of the Yanchep District Centre can be achieved through this coding. Assuming application of Table 2.1 in State Planning Policy 7.3: Residential Design Codes, vol. 2, the R60 code would enable multiple dwellings of up to 3 storeys and 2 storeys for R40. Through State Planning Policy 7.3: Residential Design Codes, vol. 1, grouped or single lots to an average of 150sqm and a minimum of 120sqm would be permitted on land coded R60 and 220sqm and 180sqm respectively for R40.

The following assessment has been made of the proposed structure plan for the purposes of informing a potential dwelling yield:

Table 1: Potential lot yield at R40 and R60, using a conservative average lot size

Planning Instrument	Metric	Min dwellings per hectare	Area (ha)	Minimum yield required	Potential yield (dph)*
LN	Site hectare (NDA)	22	7.2	158	240
SPP 4.2	Gross Urban hectare	20	9.9	198	240

* Assumes subdivision to an average of 300sqm, consistent with previous patterns of subdivision.

The amendment area is closer to the Yanchep District Centre than existing subdivided land. As such, it is envisaged that the average lot size within the amendment area will be less than that observed among existing lots. This would increase yield beyond 240. Even if that does not eventuate, Table 1 demonstrates that the proposed R40 and R60 density codes will enable achievement of the yield targets in SPP 4.2 and LN. Delivery of these lots, and the associated population growth, will assist in catalysing completion of the Yanchep District Centre to the west, commencement of the Local Centre shown in ASP 76 to the east, and progression of the Yanchep City Centre to the north.

2.3 R-MD Codes

In its current form, ASP 76 contains estate-specific variations to the Residential Design Codes ('R-Codes') to guide medium-density residential development (refer to Tables 1A and 1B of Part 1 of ASP 40). Since ASP 40 was approved, the WAPC has adopted Planning Bulletin 112: *Medium-density single house development standards – Development Zones* (the 'R-MD Codes'), being a set of standard variations to the Residential Design Codes for medium-density housing.

To ensure consistency with other estates and standard house designs prepared by builders in accordance with the R-MD Codes, it is desirable to delete Tables 1A and 1B from ASP 40 and replace them with reference to the R-MD Codes. Reference to the R-MD Codes in a structure plan is not, in itself, statutorily effective, however, a head of power for the reference exists in the form of the City's Local Planning Policy 4.19: *Medium-Density Housing Standards (R-MD)*, enabling its implementation.

Replacement of Tables 1A and 1B with reference to the R-MD Codes will necessitate associated changes to the text in Part 1 of the ASP 76 report, particularly in Section 9. Table 1C, containing R-Codes variations for land coded R80 and R100, will also be deleted, with R-Codes variations to be implemented through a Local Development Plan or development application.




Figure 6 - Proposed Structure Plan Maps (a)




Figure 6 - Proposed Structure Plan Maps (b)




Figure 6 - Proposed Structure Plan Maps (c)

2.4 Planning and Development (Local Planning Schemes) Regulations 2015

In 2015, the *Planning and Development (Local Planning Schemes) Regulations 2015* came into effect and made changes to the format and effect of statutory structure plans. The opportunity is being taken to update ASP 40 to reflect the new Structure Plan Framework, which is part of the suite of Regulations documents.

2.5 Substantiality

With reference to the criteria listed in the Structure Plan Framework, we are of the view that this proposal constitutes a minor structure plan amendment. It responds to the contemporary planning framework and does not:

- Materially alter the purpose and intent of the structure plan;
- Change the intended lot/dwelling yield by more than ten per cent;
- Adversely impact upon the amenity of adjoining landowners;
- Restrict the use and development of adjoining land;
- Impact on infrastructure provision or the environment.

Consistent with the Planning and Development (Local Planning Schemes) Regulations 2015, minor structure plan amendments need not be advertised.

3.0 PLANNING CONSIDERATIONS

3.1 Employment

3.1.1 [Yanchep-Two Rocks District Structure Plan](#)

The DSP contains an employment self-sufficiency target of 75%, which is envisaged to be achieved through the development of activity centres, employment precincts, corridors, industrial areas, education establishments and home-based businesses. There is no employment target specific to the 'Mixed Use' zone in ASP 40.

The DSP contains land use classifications named 'Mixed Use Corridors' and 'Mixed Use / Employment'. These are not the same as the 'Mixed Use' zone in DPS 2; they are significant, strategically-located employment nodes designated around the Yanchep City Centre and transit corridors. The Amendment area is identified for 'Residential' purposes in the DSP, and no 'Mixed Use' component is distinguished. A target of 48,469 dwellings is stated in Table 1 of the DSP, with 2680 "home-based businesses" envisaged (representing 5% of the total). Some of these are anticipated to be operative from homes within the Amendment area.

Achievement of the employment self-sufficiency target can only be achieved once development of commercial, employment-generating land has been catalysed. This occurs through local population growth, which depends on residential development such as that facilitated by this amendment. Progression of residential development within Jindowie will support the emergence of the Yanchep District Centre and Yanchep Secondary Centre (where 42% of the DSP target is envisaged to be accommodated) and maximise the likelihood of the small-scale commercial activities mentioned above being progressed.

3.1.2 [Permissibility in the 'Mixed Use' zone](#)

The objectives of the 'Mixed Use' zone in DPS 2 include facilitation of "small-scale businesses in a primarily residential-scale environment", with the predominant uses being "residential, office, consulting, dining and limited retail". The proposed 'Residential' zone still facilitates a variety of commercial uses, including childcare centres, consulting rooms, corner stores and home businesses. This range is, by definition, narrower than that permissible in the 'Mixed Use' zone, but it does facilitate local-scale commercial activity in the event that local market demand is sufficient. The following land uses that might realistically have eventuated within the Amendment area are permissible in the 'Mixed Use' zone but not in the 'Residential' zone:

Use class	Residential	Mixed Use
Bakery	X	D
Beauty Parlour	X	P
Convenience Store	X	D
Hairdresser	X	P
Lunch Bar	X	P
Office	X	P
Pharmacy	X	D
Restaurant	X	D

In the absence of the South Yanchep station and the associated foot traffic and higher residential density, it is unlikely that any of the above land uses would eventuate within the Amendment area. The Yanchep District Centre is immediately west and will (and should) be the focal point for local commercial floorspace. On balance, it is very likely that the net effect on employment will be minimal. Replacement of the 'Residential / Mixed Use' zone with the 'Residential' zone is therefore a sensible response to the removal of the South Yanchep station from planning for the Joondalup railway extension. This has fundamentally altered the considerations relevant to land use within the amendment area.

3.2 Access

Access to the Amendment area is currently, and will continue to be, from Marmion Avenue (reserved for 'Primary Regional Roads' in the MRS) and Yanchep Beach Road (reserved for 'Other Regional Roads' in the MRS and a 'District Distributor' using Main Roads' classification system). Constructed, gazetted Neighbourhood Connector roads (Peony Boulevard, Morwell Street, Blackwood Meander and Kakadu Road) provide access into the Amendment area from Marmion Avenue and Yanchep Beach Road.

The majority of the Amendment area has already been developed and therefore has an established street network. This is structured around two constructed, operating Neighbourhood Connector roads:

- Kakadu Drive, which connects to Yanchep Beach Road to the north; and
- Morwell Street / Blackwood Meander, which loops eastward from Marmion Avenue north of Yanchep Secondary College and returns to Marmion Avenue south of the College.

Morwell Street east of its intersection with Kakadu Drive was not envisaged as a Neighbourhood Connector road in the original version of ASP 40. The northern section of the loop described above was proposed to be in a more northerly location, meeting the Joondalup railway extension at the previously-proposed South Yanchep station. This northern section was to have formed the spine of a local-level activity corridor comprising land zoned 'Residential / Mixed Use'. Deletion of the South Yanchep station from planning for Joondalup railway extension has diminished the locational justification for this corridor and as a consequence, it has remained undeveloped, and Morwell Street east of Kakadu Drive completes the aforementioned loop.

The rezoning and reduction in density proposed by this Amendment would obviate the need for the Neighbourhood Connector that previously formed the northern section of the loop. As such, a downgrade to Access Street standard is proposed, with an associated upgrade of Morwell Street east of Kakadu Drive to Neighbourhood Connector status. All other new streets within the Amendment area are proposed to be Access Streets.

3.3 Transport Noise Management

The Amendment area is in close proximity to Yanchep Beach Road and the planned Joondalup railway extension corridor, both of which are triggers for consideration of State Planning Policy 5.4 – *Road and Rail Transport Noise* ('SPP 5.4'). In accordance with SPP 5.4, a Transportation Noise Assessment (Lloyd George Acoustics, April 2020; refer Appendix 5) has been prepared to support this Amendment. This concludes that noise mitigation measures will be required to ensure compliance with SPP 5.4 for lots adjacent to the above-mentioned corridors, including:

- Noise barriers (preferably a wall) along both corridors;
- Implementation of 'Quiet House' construction standards;
- Inclusion of notifications on the Certificates of Title for noise-affected lots.

The noise mitigation treatment required for each individual noise-affected lots will be confirmed at the subdivision stage in accordance with SPP 5.4. The Transportation Noise Assessment provided with this Amendment provides assurance that, consistent with previous assessments, an acceptable level of acoustic amenity can be achieved for residential development within the Amendment area.

3.4 Bushfire Hazard Management

The south-western and eastern parts of the amendment area are identified as being bushfire-prone in the map database maintained by the Department of Fire and Emergency Services. In accordance with the requirements of State Planning Policy 3.7: Planning in Bushfire-Prone Areas ('SPP 3.7'), a Bushfire Management Plan incorporating a Bushfire Attack Level ('BAL') Contour Plan (Entire Fire Management, March 2020; refer Appendix 6) is included with this amendment request.

The BMP confirms that the primary bushfire hazards affecting the application area are temporary. They include:

- 'Forest' vegetation within the MRS 'Railways' reserve that forms the eastern edge of the amendment area. This will be cleared in the next 12 months or so to facilitate the extension of the Joondalup railway to Yanchep.
- 'Scrub', 'Shrubland' and 'Grassland' on various sites around the amendment area, all of which will be cleared or managed to a low-threat state as part of future development in accordance with ASP 40.

These factors translate to temporary BAL ratings for very limited areas around the periphery of the amendment area. This confirms that the bushfire hazards affecting the application area can be managed in accordance with SPP 3.7. The BAL ratings for each individual lot will be updated through preparation of a new BAL Compliance Report pursuant to a condition of subdivision approval, which, depending on the progress of development on neighbouring land, may enable some of the BAL ratings to be deleted entirely.

4.0 CONCLUSION

This amendment proposes to respond to the deletion of South Yanchep station from planning for the extension of the Joondalup railway. The station had justified inclusion of a 'Mixed Use' zone westward to the Yanchep District Centre and associated residential density codes of R80/ R100 and R160. Without it, that justification is no longer present. Transit-oriented development, which is characterised by a mix of uses and a relatively high population density, is, by definition, dependent on proximity to a high-frequency, cross-metropolitan transit station. South Yanchep station would have performed such a role, but is no longer available. As such, it is proposed that the 'Mixed Use' area be rezoned to 'Residential' with density codings of R40 and R60, which will support development of nearby activity centres (particularly the Yanchep District Centre) and ensure that the planning framework reflects the characteristics of the site.



APPENDICES

- Appendix 1 Certificate of Title
- Appendix 2 Existing, approved ASP 40 (Part 1)
- Appendix 3 Proposed new Part 1 for ASP 40
- Appendix 4 PTA Advice on South Yanchep Station
- Appendix 5 Transportation Noise Assessment (Lloyd George Acoustics, April 2020)
- Appendix 6 Bushfire Management Plan (Entire Fire Management, March 2020)

APPENDIX 1

Certificate of Title

1

WESTERN



AUSTRALIA

REGISTER NUMBER 9038/DP67829	
DUPLICATE EDITION N/A	DATE DUPLICATE ISSUED N/A

RECORD OF CERTIFICATE OF TITLE
UNDER THE TRANSFER OF LAND ACT 1893

VOLUME **2926** FOLIO **205**

The person described in the first schedule is the registered proprietor of an estate in fee simple in the land described below subject to the reservations, conditions and depth limit contained in the original grant (if a grant issued) and to the limitations, interests, encumbrances and notifications shown in the second schedule.



REGISTRAR OF TITLES

LAND DESCRIPTION:

LOT 9038 ON DEPOSITED PLAN 67829

REGISTERED PROPRIETOR:
(FIRST SCHEDULE)

HOUSING AUTHORITY OF 99 PLAIN STREET, EAST PERTH

(AF N605641) REGISTERED 25/5/2017

LIMITATIONS, INTERESTS, ENCUMBRANCES AND NOTIFICATIONS:
(SECOND SCHEDULE)

- *EXCEPT AND RESERVING METALS, MINERALS, GEMS AND MINERAL OIL SPECIFIED IN TRANSFER 1466/1928.
- *EASEMENT BURDEN CREATED UNDER SECTION 167 P. & D. ACT FOR WATER PURPOSES TO WATER CORPORATION - SEE DEPOSITED PLAN 67829 AS CREATED ON DEPOSITED PLAN 67846.

Warning: A current search of the sketch of the land should be obtained where detail of position, dimensions or area of the lot is required.
* Any entries preceded by an asterisk may not appear on the current edition of the duplicate certificate of title.
Lot as described in the land description may be a lot or location.

-----END OF CERTIFICATE OF TITLE-----

STATEMENTS:

The statements set out below are not intended to be nor should they be relied on as substitutes for inspection of the land and the relevant documents or for local government, legal, surveying or other professional advice.

SKETCH OF LAND: DP67829
 PREVIOUS TITLE: 2906-93
 PROPERTY STREET ADDRESS: NO STREET ADDRESS INFORMATION AVAILABLE.
 LOCAL GOVERNMENT AUTHORITY: CITY OF WANNEROO
 RESPONSIBLE AGENCY: DEPARTMENT OF COMMUNITIES (SSHC)

NOTE 1: DUPLICATE CERTIFICATE OF TITLE NOT ISSUED AS REQUESTED BY DEALING M325597
 NOTE 2: N604629 DEPOSITED PLAN 67829 LODGED

APPENDIX 2

Existing, approved ASP 40 (Part 1)

2

**LOT 1 & LOT 102 YANCHEP BEACH ROAD,
YANCHEP
AGREED STRUCTURE PLAN
(AS AMENDED OCTOBER 2019)**

**Structure Plan No. 40
Agreed: 5 November 2007**

**This Structure Plan was prepared under the provisions of Part 9 of City of Wanneroo District
Planning Scheme No. 2**

Record of Amendments made to the Agreed Structure Plan

Lot 1 & Lot 102 Yanchep Beach Road, Yanchep

Amendment No.	Description of Amendment	Finally Endorsed Council	Finally Endorsed WAPC
1.	<ul style="list-style-type: none"> i) Introduce Special Design Provisions and R Code Variations ii) Re Code various Apartment sites to R100 iii) Minor changes to Zoning Plan to reflect approved subdivision iv) Clarify wording related to the land subject to the Retail Floorspace allocation. 	26 March 2009	10 September 2009
2.	<ul style="list-style-type: none"> i) Modification to Residential Density Code Plan (Plan 3) to Re Code various Apartment sites to R160 and replace R100 coding of smaller adhoc sites with an R60 coding. 	6 April 2010	2 March 2011
3.	<ul style="list-style-type: none"> i) Inserting a new paragraph into section 6.0 outlining the statutory operation of the R80/R100 split code; ii) Amending Clause 9.6.3 to include reference to State Planning Policy 4.2; iii) Inclusion of Table 1C into Part 1 to include additional Acceptable Development provisions for single and grouped housing on R80/R100 coded lots; iv) Modifying the LSP Statutory Plan (Plan 1) and Zoning Plan (Plan 2) to reflect a modified subdivision layout; and v) Modifying the Residential Density Code Plan (Plan 3) to Re code various lots from R60 to R80/R100 and to reflect a modified subdivision layout. 	28 May 2013	

4.	Modifying the Local Structure Plan Map (Plan 1) by reclassifying No. 2 Kakadu Road, Yanchep from 'Business' to 'District Centre'; and Modifying the Zoning Plan (Plan 2) by rezoning No. 2 Kakadu Road, Yanchep from 'Business Zone' to 'Commercial'.		1 November 2019
----	--	--	-----------------

This structure plan is prepared under the provisions of the City of Wanneroo District Planning Scheme No. 2.

IT IS CERTIFIED THAT THIS STRUCTURE PLAN WAS APPROVED BY RESOLUTION OF THE WESTERN AUSTRALIAN PLANNING COMMISSION ON:

5 November 2007

In accordance with Schedule 2, Part 4, Clause 28 (2) and refer to Part 1, 2. (b) of the *Planning and Development (Local Planning Schemes) Regulations 2015*.

Date of Expiry: 19 October 2025

OVERVIEW

PARTS OF THE STRUCTURE PLAN

This Structure Plan comprises two separate parts;

- PART 1 – STATUTORY SECTION
- PART 2 – EXPLANATORY REPORT

Clause 9.8 of the City of Wanneroo District Planning Scheme No. 2 (hereinafter called “the Scheme”) provides, amongst other things, that a provision, standard or requirements of a Structure Plan approved under Part 9 of the Scheme, shall be given the same force and effect as if it was a provision, standard or requirement of the Scheme. It is hereby provided that such force and effect shall only be given to Part 1 of this Structure Plan. Part 2 of this Structure Plan is for explanatory purposes only, providing a descriptive analysis of the Structure Plan initiatives.

Clause 9.8.3 (f) of the Scheme states that where, in the event of there being any inconsistency or conflict between any provision, requirement of standard of the Scheme and any provision requirement or standard of an agreed Structure Plan, the provision, requirement or standard of the Scheme shall prevail.

PART 1

STATUTORY PLANNING SECTION

LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP

LOCAL STRUCTURE PLAN

As provided for under the provisions of the Scheme, this part of the Lot 1 and Lot 102 Structure Plan has the same force and effect as a provision, standard or requirement of the Scheme.

1.0 STRUCTURE PLAN AREA

This Structure Plan shall apply to Lot 1 and Lot 102 Yanchep Beach Road, Yanchep being the land contained within the inner edge of the broken black line shown on the Zoning Map (Plan No.2).

2.0 STRUCTURE PLAN CONTENT

This Structure Plan comprises the:

- a) Statutory section (Part 1);
- b) Explanatory section (Part 2);

3.0 INTERPRETATION

The words and expressions used in this Structure Plan shall have the respective meanings given to them in the Scheme.

4.0 OPERATION DATE

In accordance with sub-clause 9.8.1 of the Scheme, this Structure Plan shall come into operation when it is certified by the Commission pursuant to sub-clause 9.6.3 or adopted, signed and sealed by the Council under sub-clause 9.6.5 of the Scheme.

5.0 RELATIONSHIP WITH THE SCHEME

In accordance with clause 9.8 of the Scheme:

- a) The provisions, standards and requirements specified under Part 1 of this Structure Plan shall have the same force and effect as if it were a provision, standard or requirement of the Scheme. Part 2 of this Structure Plan is for explanatory purposes only in order to provide a descriptive analysis of the Structure Plan.
- b) In the event of there being any inconsistencies or conflict between the provisions, standards or requirements of the Scheme and the provisions, standards or requirements of this Structure Plan, then the provisions, standards or requirements of the Scheme shall prevail.

6.0 ZONES, RESERVES AND RESIDENTIAL DENSITY CODES

The Zoning Plan (Plan No.2) and Residential Density Code Plan (Plan No.3) delineate and depict the zones, reserves and residential density codes applicable to the structure plan area according to the legend thereon.

The zones, reserves and residential density codes designated under this structure plan apply to the land within it as if the zones, reserves and residential density code were incorporated in the Scheme.

All provisions, standards and requirements applicable to the zones, reserves and residential density codes in the Scheme shall apply, unless specific provision is made to the contrary in this Structure Plan.

Single and grouped dwelling development within the R80/R100 split coding is subject to the Residential Design Codes provisions for the R80 code and the variations set out in Table 1C. Multiple dwelling development within the R80/R100 split coding is subject to the Residential Design Code provisions for the R100 code and the variations set out in Table 1C.

7.0 STRUCTURE PLAN MAP

The Structure Plan Map (Plan No.1) outlines the planned pattern of subdivision or development for the Structure Plan area. All subdivision and development should be carried out in accordance with the principles outlined on the Structure Plan Map.

8.0 GENERAL PROVISIONS

8.1 Retail Floorspace

The Western Australian Planning Commission's Section 5AA Statement of Planning Policy No.9 – Metropolitan Centre's Policy Statement for the Perth Metropolitan Region (now SPP 4.2) designates the location of the Yanchep South District Centre in the Structure Plan area. The SPP states that the, "Shopping Floor space should generally be confined to 15,000m² unless consistent with a Commission endorsed Local Planning Strategy or Centre Plan"

Notwithstanding the SPP designation of the Centre as 'District', this Structure Plan allocates a retail net lettable area of 11,000m², with any additional retail net lettable area for this District Centre being justified in the context of overall retail modelling for the District and an amendment to the Structure Plan.

9.0 SPECIAL PROVISIONS

9.1 Environmental Management Plan

The actions as set out in the Lot 102 Yanchep Beach Road Environmental Assessment and Management Plan as specified in Schedule 12 – Environmental Conditions of the City of Wanneroo District Planning Scheme No. 2 are to be undertaken and submitted for assessment at the time of lodging a subdivision and / or development application within the Structure Plan area.

9.2 Limitation of Dwelling Units in the Yanchep-Two Rocks District

In accordance with the Western Australian Planning Commission Policy adopted on 26 October 2004 residential lot creation in the Plan Area is limited to a maximum of 200 lots until such time as Marmion Avenue is extended.

9.3 Romeo Road to Yanchep Railway Alignment Study

A Romeo Road to Yanchep Railway Alignment Study is currently being undertaken by the Western Australian Planning Commission. Following finalisation of this Study and where applicable, modifications to the Structure Plan may be required to reflect the final railway alignment.

9.4 Unexploded Ordnance

The Structure Plan area has previously been utilised as an artillery range and may contain unexploded ordnance. No subdivision or development shall be commenced prior to the Structure Plan area being cleared to the satisfaction of the Fire and Emergency Services and the City of Wanneroo of unexploded ordnance.

9.5 Employment Strategy

9.5.1

The Developer shall implement the recommendations of the Lot 102 Yanchep Beach Road Structure Plan Employment Strategy as prepared by Shrapnel Urban Planning and dated January 2006 at the subdivision and/or development stage.

9.6 Local Housing Strategy

9.6.1

The subdivider shall demonstrate, as part of any subdivision and / or development proposal, the manner in which the Key Strategy Actions identified in the Local Housing Strategy are to be addressed, to ensure adequate housing choice is available to meet the changing social and economic needs of the community. These housing types should include, but not be limited to studio apartments, group dwellings, aged persons, and mixed uses.

9.6.2

Designs and layouts shall create a street network and movement patterns that focus on the rail station and town centre and creates links that would extend the railway stations walkable catchment. At least 60% of the 800m radius catchment should be within an actual 800m walk to the railway station and town centre.

9.6.3

The City shall require the subdivider/developer to outline how any Plan will achieve the average dwelling yield targets included in the Local Housing Strategy and State Planning Policy 4.2 Activity Centres for Perth and Peel.

9.7 Residential Design Code Variations

9.7.1 Residential Design Code Variations

The following Tables 1A, 1B and 1C set out those variations to the R Codes which are deemed to constitute Acceptable Development within the Structure Plan area and where neighbour consultation and planning approval is not required.

TABLE 1 A – R40

VARIATIONS TO THE 'ACCEPTABLE DEVELOPMENT' REQUIREMENTS OF THE R CODES FOR R40:

Item	Relevant R Code Clauses	Variation												
Front Setback	6.2.1 A1.1 (i) & 6.2.2 A2 (i)	<p>For lots with rear access, the front setbacks shall be:</p> <table border="1" data-bbox="816 457 1461 604"> <thead> <tr> <th></th> <th>Minimum</th> <th>Maximum</th> <th>Average</th> </tr> </thead> <tbody> <tr> <td>Dwelling</td> <td>1.5m</td> <td>Not applicable</td> <td>3.0m</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Minimum	Maximum	Average	Dwelling	1.5m	Not applicable	3.0m				
	Minimum	Maximum	Average											
Dwelling	1.5m	Not applicable	3.0m											
Boundary Walls	6.3.2 A2 6.3.2 A2 (iii)	<p>In determining the acceptable length of any boundary wall pursuant to Clause 6.3.2 A2 (ii) of the Codes, the front setback shall mean the setback of the building itself on that boundary.</p> <p>For lots with laneway access, walls on boundary are permitted to both side boundaries of a lot (excluding secondary street boundaries other than to laneways) within the following limits:</p> <table border="1" data-bbox="816 951 1461 1062"> <thead> <tr> <th></th> <th>Max. Height</th> <th>Max. Length</th> </tr> </thead> <tbody> <tr> <td>Single Storey</td> <td>3.5m*</td> <td>No limit</td> </tr> <tr> <td>Two Storey & Above</td> <td>6.5m*</td> <td>12 m</td> </tr> </tbody> </table> <p>* For dwellings with a pitched roof, the height of walls on side boundaries may be increased to the top of the ridgeline where this runs parallel to the front boundary and will abut a similarly configured wall or secondary street.</p>		Max. Height	Max. Length	Single Storey	3.5m*	No limit	Two Storey & Above	6.5m*	12 m			
	Max. Height	Max. Length												
Single Storey	3.5m*	No limit												
Two Storey & Above	6.5m*	12 m												
Private Open Space	6.4.1 A1 & 6.4.2 A2 – Table 1	<p>Minimum open space to be provided will be reduced to a minimum of 30% of the site subject to the provision of;</p> <ul style="list-style-type: none"> i) A minimum 2m setback to major openings to habitable rooms located on the northernmost or easternmost boundaries; ii) Any boundary wall (if proposed) to be built on the southernmost or westernmost side boundary (except where that boundary is to a secondary street other than to a laneway) or as otherwise depicted on an adopted Detailed Area Plan 												

Table 1A Continued:								
Private Open Space (continued)	6.4.1 A1 & 6.4.2 A2 – Table 1	<p>iii) Provision of an Outdoor Living Area designed in accordance with the RD Codes and directly accessible from an internal living area on the northernmost or easternmost boundary. Where the outdoor living area is not directly accessible from an internal living area, provision of an additional outdoor living area which complies with the following criteria:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 20%;">Min Area</th> <th style="width: 20%;">Min Dimension</th> <th style="width: 60%;">Other</th> </tr> </thead> <tbody> <tr> <td style="text-align: center; vertical-align: top;">20m²</td> <td style="text-align: center; vertical-align: top;">4m</td> <td style="vertical-align: top;"> <ul style="list-style-type: none"> – May be included under the roof of the main dwelling – Must be located on the northernmost or easternmost side boundary of the dwelling. </td> </tr> </tbody> </table> <p>Note: Courtyards are permitted within the secondary street setback area.</p>	Min Area	Min Dimension	Other	20m ²	4m	<ul style="list-style-type: none"> – May be included under the roof of the main dwelling – Must be located on the northernmost or easternmost side boundary of the dwelling.
Min Area	Min Dimension	Other						
20m ²	4m	<ul style="list-style-type: none"> – May be included under the roof of the main dwelling – Must be located on the northernmost or easternmost side boundary of the dwelling. 						
Design for Climate	6.9.1 A1	The overshadowing provisions (Cl 6.9.1 A1) do not apply.						
Additional Requirements		<p>In addition to the Acceptable Development standards, for those lots immediately adjacent Public Open Space the following provisions shall apply:</p> <p>i) must have a minimum of one habitable room with a major opening facing toward the Public Open Space area - where, for the purposes of this Clause, a “habitable room” means a room that is used for normal domestic activities and includes a living room, lounge room, sitting room, television room, kitchen, dining room, however, does not include a bedroom; and</p> <p>ii) visually permeable fencing to the public open space boundary to the specification and satisfaction of the City.</p>						

TABLE 1 B – R60			
VARIATIONS TO THE 'ACCEPTABLE DEVELOPMENT' REQUIREMENTS OF THE R CODES FOR R60:			
Item	Relevant R Code Clauses	Variation	
Front Setbacks	6.2.1 A1.1 (i) & 6.2.2 A2 (i)	Front Setbacks:	
		Minimum	Maximum
		Dwelling	2m
		4.0m	Not applicable
		Porch, balcony, veranda or the equivalent	1.5m
		3.0m	Not applicable
Boundary Walls	6.3.2 A2 6.3.2 A2 (iii)	In determining the acceptable length of any boundary wall pursuant to Clause 6.3.2 A2 (ii) of the Codes, the front setback shall mean the setback of the building itself on that boundary. Boundary Walls are permitted to both side boundaries of a lot (excluding secondary street boundaries other than to laneways) within the following limits:	
		Max. height	Max. length
		Single Storey	3.5m*
		No limit	12m
		Two Storey & Above	6.5m*
		Note: For dwelling with a pitched roof, the height of walls on side boundaries may be increased to the top of the ridgeline where this runs parallel to the front boundary and abuts a similarly configured wall or secondary street.	
Private Open Space	6.4.1 A1 – Table 1 6.4.2 A2	Minimum open space to be provided is 25%. An Outdoor Living Area is to be provided:	
		<ul style="list-style-type: none"> i) With a minimum useable space of 24m² and a minimum dimension of 4m; ii) Behind the primary street setback line (it is permitted within the secondary street setback area); iii) Located on the northernmost or easternmost boundary to maximise solar access; and 	
Access & Car-parking	6.5.1 A1	For any lots on the corner of a "lane to lane" or "lane to road" a minimum of one on site bay per dwelling is required and it must be covered.	

Table1B Continued:		
Privacy	6.8.1 A1 (i), (ii) & (iii)	The setback to the boundary of major openings to active habitable spaces or their equivalent which have a floor level more than 0.5m above natural ground level and are positioned so as to overlook any part of any other residential property behind the 3m street setback line which are specified in (i) of Clause 6.8.1 A1 is to be a minimum of 4.5m in all cases.
Design for Climate	6.9.1 A1	The overshadowing provisions (Cl 6.9.1 A1) do not apply.
Special Purpose Dwellings/Ancillary Accommodation	7.1.1 A1	Ancillary accommodation is permitted on lots less than 450m ² where abutting a laneway. Such ancillary accommodation does not require an additional car parking bay on site.
Additional Requirements		In addition to the Acceptable Development standards, for those lots immediately adjacent Public Open Space the following provisions shall apply: i) must have a minimum of one habitable room with a major opening facing toward the Public Open Space area - where, for the purposes of this Clause, a "habitable room" means a room that is used for normal domestic activities and includes a living room, lounge room, sitting room, television room, kitchen, dining room, however, does not include a bedroom; and ii) visually permeable fencing to the public open space boundary to the specification and satisfaction of the City.

TABLE 1C – R80/R100

VARIATIONS TO THE 'ACCEPTABLE DEVELOPMENT' REQUIREMENTS OF THE R CODES FOR R80/R100:

Item	Relevant R Code Clauses	Variation																
Minimum and Average Lot Sizes	6.1.1 A1.1 & A1.2 (i) & (ii)	Minimum Lot Size: 100m ² Average Lot Size: 120m ²																
Front Setbacks	6.2.1 A1.1 (i) & 6.2.2 A2 (i)	<p>Front Setbacks:</p> <table border="1" data-bbox="580 546 1353 949"> <thead> <tr> <th></th> <th>Minimum</th> <th>Maximum</th> <th>Average</th> </tr> </thead> <tbody> <tr> <td>Dwelling with laneway access (rear loaded)</td> <td>2m</td> <td>4.0m</td> <td>Not applicable</td> </tr> <tr> <td>Porch, balcony, veranda or the equivalent</td> <td>1.5m</td> <td>3.0m</td> <td>Not applicable</td> </tr> <tr> <td>Dwelling with street access (front loaded)</td> <td>2m</td> <td>5.0m</td> <td>Not applicable</td> </tr> </tbody> </table> <p>Where vehicle access is from a primary street and parking is provided in tandem, the minimum setback for a garage is 5 metres.</p> <p>Buildings are permitted up to the primary and secondary street boundary where abutting the 'Mixed Use Activity Corridor' as designated on the Local Structure Plan.</p>		Minimum	Maximum	Average	Dwelling with laneway access (rear loaded)	2m	4.0m	Not applicable	Porch, balcony, veranda or the equivalent	1.5m	3.0m	Not applicable	Dwelling with street access (front loaded)	2m	5.0m	Not applicable
	Minimum	Maximum	Average															
Dwelling with laneway access (rear loaded)	2m	4.0m	Not applicable															
Porch, balcony, veranda or the equivalent	1.5m	3.0m	Not applicable															
Dwelling with street access (front loaded)	2m	5.0m	Not applicable															
Boundary Walls	6.3.2 A2 6.3.2 A2 (iii)	<p>In determining the acceptable length of any boundary wall pursuant to Clause 6.3.2 A2 (ii) of the Codes, the front setback shall mean the setback of the building itself on that boundary.</p> <p>Boundary Walls are permitted to both side boundaries of a lot (excluding secondary street boundaries other than to laneways) within the following limits:</p> <table border="1" data-bbox="580 1453 1353 1601"> <thead> <tr> <th></th> <th>Max. height</th> <th>Max. length</th> </tr> </thead> <tbody> <tr> <td>Single Storey</td> <td>3.5m*</td> <td>No limit</td> </tr> <tr> <td>Two Storey & Above</td> <td>7m*</td> <td>17m maximum</td> </tr> </tbody> </table> <p>*Note: For dwelling with a pitched roof, the height of walls on side boundaries may be increased to the top of the ridgeline where this runs parallel to the front boundary and abuts a similarly configured wall or secondary street.</p>		Max. height	Max. length	Single Storey	3.5m*	No limit	Two Storey & Above	7m*	17m maximum							
	Max. height	Max. length																
Single Storey	3.5m*	No limit																
Two Storey & Above	7m*	17m maximum																
Private Open Space	6.4.1 A1 – Table 1 6.4.2 A2	<p>Minimum open space to be provided is 25%, except where a lot, strata lot or building fronts the designated activity corridor, in which case minimum open space is 20%.</p> <p>An Outdoor Living Area is to be provided:</p> <ul style="list-style-type: none"> i. With a minimum useable space of 16m² and a minimum 																

TABLE 1C – R80/R100

VARIATIONS TO THE 'ACCEPTABLE DEVELOPMENT' REQUIREMENTS OF THE R CODES FOR R80/R100:

Item	Relevant R Code Clauses	Variation								
		dimension of 4m; ii. Behind the primary street setback line (it is permitted within the secondary street setback area);								
Access & Car-parking	6.5.1 A1	Car parking may be reduced to one on site bay per dwelling where: <ul style="list-style-type: none"> • The dwelling has a single bedroom; or • The dwelling has two bedrooms, and has a Plot Ratio Area less than 125m², and vehicle access is provided via a rear lane. Note: 'Plot Ratio Area' is defined in the Residential Design Codes.								
Building Height	6.7.1 A1.1	Maximum building heights are as per the table below: <table border="1" data-bbox="580 815 1355 981" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th colspan="2" style="text-align: center;">Maximum Building Heights</th> </tr> </thead> <tbody> <tr> <td style="width: 60%;">Top of external wall (roof above)</td> <td style="text-align: center;">7 metres</td> </tr> <tr> <td>Top of external wall (concealed roof)</td> <td style="text-align: center;">7.5 metres</td> </tr> <tr> <td>Top of pitched roof</td> <td style="text-align: center;">10 metres</td> </tr> </tbody> </table>	Maximum Building Heights		Top of external wall (roof above)	7 metres	Top of external wall (concealed roof)	7.5 metres	Top of pitched roof	10 metres
Maximum Building Heights										
Top of external wall (roof above)	7 metres									
Top of external wall (concealed roof)	7.5 metres									
Top of pitched roof	10 metres									
Privacy	6.8.1 A1 (i), (ii) & (iii)	The setback to the boundary of major openings to active habitable spaces or their equivalent which have a floor level more than 0.5m above natural ground level and are positioned so as to overlook any part of any other residential property behind the 3m street setback line which are specified in (i) of Clause 6.8.1 A1 is to be a minimum of 4.5m in all cases.								
Design for Climate	6.9.1 A1	The overshadowing provisions (CI 6.9.1 A1) do not apply.								
Special Purpose Dwellings/Ancillary Accommodation	7.1.1 A1	Ancillary accommodation is permitted on lots less than 450m ² where abutting a laneway. Such ancillary accommodation does not require an additional car parking bay on site.								
Additional Requirements		In addition to the Acceptable Development standards, for those lots immediately adjacent Public Open Space the following provisions shall apply: must have a minimum of one habitable room with a major opening facing toward the Public Open Space area - where, for the purposes of this Clause, a "habitable room" means a room that is used for normal domestic activities and includes a living room, lounge room, sitting room, television room, kitchen, dining room or bedroom; and visually permeable fencing to the public open space boundary to the specification and satisfaction of the City.								
Design for Climate	6.9.1 A1	The overshadowing provisions (CI 6.9.1 A1) do not apply.								

9.8 Public Open Space

9.8.1 General

9.8.1.1

At the time of subdivision, the subdivider will cede free of cost to the Crown a minimum of 10% of the gross subdivisible area in accordance with the Western Australian Planning Commission's Policy D.C 2.3 'Public Open Space in Residential Areas' ('Policy DC 2.3') for public open space ('POS'). This POS requirement shall be provided in a mix of high quality areas.

9.8.1.2

The overall allocation, size and type of open spaces being provided shall be explained at a strategic level for the Structure Plan to ensure that comprehensive local open space planning is achieved on the broad scale.

9.8.1.3

The subdivider will require the Western Australian Planning Commission's approval for drainage credits towards public open space provision in accordance with Policy DC 2.3.

9.8.2 Southern Precinct

9.8.2.1


Provision of local and neighbourhood parks to support increased densities that are central to the catchment and provide for a high level of accessibility.

9.9 Interim Wastewater Transfer Pump Station

The Structure Plan depicts the general preferred location envelope for an Interim Wastewater Transfer Pump Station. A site of approximately 2000m² will be required with a buffer of 30m to residential land use. The final location shall be resolved at either the subdivision or development stage.

9.10 Ethnographic and Archaeological Study

At the time of subdivision the Local Government shall recommend to the Western Australian Planning Commission that an ethnographic and archaeological study be undertaken.



The issue of intersection spacing and design to Yanchep Beach Road to be further considered during the preparation of a Local Structure Plan for the Centre Zone land.

T Junction (North Side) Left In/Left Out

Driveway Access Point Left In/Left Out

Left In/Left Out only Intersection
Upon completion of traffic planning for Yanchep Beach Road a full four way intersection may be supported.

T Junction Full Movement

T Junctions Left In/Left Out

Existing T Junction Left In/Left Out

Driveway Access Left In/Left Out

Full Movement 4 Way Intersection with traffic lights

General Preferred Location for Interim Wastewater Transfer Pump Station. A Site of approx. 2000m² with a 30m buffer within this envelope is required. Final location resolved at the Subdivision/Development Stage.

T Junction Full Movement

T Junction Full Movement


Pedestrian Underpass

Future Railway Alignment








LEGEND

 Public Open Space


LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
STRUCTURE PLAN No. 40
PLAN No. 1 - LOCAL STRUCTURE PLAN








LEGEND

-  Structure Plan Boundary
-  Residential Zone
-  Commercial
-  Business Zone
-  Centre Zone & Private Clubs/Recreation
-  Public Purpose - High School Reservation
-  Other Regional Road Reserve

LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
 STRUCTURE PLAN No. 40
 PLAN No. 2 - ZONING PLAN



LEGEND

	Structure Plan Boundary
	R160
	R80 / R100
	R60
	R40

LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
STRUCTURE PLAN No. 40
 PLAN No. 3 - R-CODE PLAN

APPENDIX 3

Proposed new Part 1 for ASP 40

3

AGREED STRUCTURE PLAN NO. 40
LOTS 1 + 102 YANCHEP BEACH ROAD, YANCHEP (JINDOWIE WEST)

PART ONE | IMPLEMENTATION SECTION

Prepared by:



2 Abbotsford Street
West Leederville WA 6007
PO Box 796
Subiaco WA 6904
08 9382 1233
www.cleplan.com.au

2122Rep160
July 2020

Title: Agreed Structure Plan No. 40
Lots 1 + 102 Yanchep Beach Road, Yanchep (Jindowie West)
Part One | Implementation Section

Prepared for: Department of Communities

CLE Reference: 2122Rep160

Date: 31 July 2020

Status: Final

Review date: 31 July 2020

Prepared by: CLE Town Planning + Design

Project team: Town Planning + Design - CLE Town Planning + Design
Engineering - Development Engineering Consultants
Hydrology - Development Engineering Consultants
Environmental - Coffey Environments
Bushfire - Entire Fire Management
Acoustic - Lloyd George Acoustics
Landscape Design - EPCAD

This report is for the exclusive use of the Client, pursuant to Agreement between the Client and CLE Town Planning + Design. CLE accepts no liability or responsibility whatsoever in respect of any use of or reliance upon any information contained within this report by anyone who is not party to the Agreement and/or has come into possession of the Report through parties other than the Client or CLE.

CLE is not accountable for any information which may be contained within the Report which has been supplied by others and reproduced by CLE in this report.

Copyright and any other Intellectual Property arising from this report and the provision of the services in accordance with the Agreement belongs exclusively to CLE unless otherwise agreed and may not be reproduced or disclosed to any other person other than the Client without the express written authority of CLE.

Any reproduction by the Client is to reference CLE as the original author.

Plans and figures contained in this report have been prepared for general information purposes only and may inadvertently use uncontrolled data from external sources. CLE does not guarantee the accuracy of the plans and they should not be used for any detailed site design. The content of this report including all plans remains the property of CLE.

This amendment to Agreed Structure Plan 40 is prepared under the provisions of Part 4 of the *Planning and Development (Local Planning Schemes) Regulations 2015*.

IT IS CERTIFIED THAT AMENDMENT NO. 5 TO AGREED STRUCTURE PLAN 40 WAS ADOPTED BY RESOLUTION OF THE WESTERN AUSTRALIAN PLANNING COMMISSION ON

.....

Signed for and on behalf of the Western Australian Planning Commission:

.....

an officer of the Commission duly authorised by the Commission pursuant to section 16 of the *Planning and Development Act 2005* for that purpose, in the presence of:

..... Witness

..... Date

..... Date of expiry

Table of amendments

Amendment No.	Description of Amendment	Endorsed by City of Wanneroo	Endorsed by WAPC
1	(i) Introduce Special Design Provisions and R-Code Variations	26 March 2009	10 September 2009
	(ii) Re Code various Apartment sites to R100		
	(iii) Minor changes to Zoning Plan to reflect approved subdivision		
	(iv) Clarify wording related to the land subject to the Retail Floorspace allocation.		
2	(v) Modification to Residential Density Code Plan (Plan 3) to Re Code various Apartment sites to R160 and replace R100 coding of smaller adhoc sites with an R60 coding	6 April 2010	2 March 2011
3	(vi) Inserting a new paragraph into section 6.0 outlining the statutory operation of the R80/R100 split code;	28 May 2013	11 November 2011
	(vii) Amending Clause 9.6.3 to include reference to State Planning Policy 4.2;		
	(viii) Inclusion of Table 1C into Part 1 to include additional Acceptable Development provisions for single and grouped housing on R80/R100 coded lots;		
	(ix) Modifying the LSP Statutory Plan (Plan 1) and Zoning Plan (Plan 2) to reflect a modified subdivision layout; and		
	(x) Modifying the Residential Density Code Plan (Plan 3) to Re code various lots from R60 to R80/R100 and to reflect a modified subdivision layout.		
4	Modifying the Local Structure Plan Map (Plan 1) by reclassifying No. 2 Kakadu Road, Yanchep from 'Business' to 'District Centre'; and Modifying the Zoning Plan (Plan 2) by rezoning No. 2 Kakadu Road, Yanchep from 'Business Zone' to 'Commercial'.	8 October 2019	1 November 2019
5	Rezoning the 'Mixed Use' land between the Yanchep District Centre and the defunct South Yanchep station site to 'Residential' with density codes of R40 and R60 and deleting the Activity Corridor linking the two.	TBC	TBC

CONTENTS

- 1.0 Structure plan area
- 2.0 Structure plan content
- 3.0 Structure plan operation
- 4.0 Land use and subdivision
- 5.0 Local Development Plans
- 6.0 Additional information

PLANS

- Plan 1: Local Structure Plan (CLE Ref. 2125-241-01)
- Plan 2: Zoning Plan (CLE Ref. 2125-242-01)
- Plan 3: R-Code Plan (CLE Ref. 2125-243-01)

1.0 STRUCTURE PLAN AREA

This structure plan applies to the land within the line identified as the 'Structure Plan Boundary' on Plan 1: Lots 1 and 102 Yanchep Beach Road, Yanchep (Jindowie West) Local Structure Plan.

2.0 STRUCTURE PLAN CONTENT

This structure plan consists of:

- Part One – Implementation Section (this section);
- Part Two – Explanatory Report (report CLE Ref. 2125-36A-01);
- Appendices – technical reports supporting the structure plan.

Part One of the Local Structure Plan comprises the structure plan map and planning provisions. Part Two and all Appendices are a reference provided to guide the interpretation and implementation of Part One.

3.0 STRUCTURE PLAN OPERATION

This structure plan is prepared in accordance with Part 4 of Schedule 2 (Deemed Provisions) in the *Planning and Development (Local Planning Schemes) Regulations 2015* ('the Regulations'). It is a Local Structure Plan fulfilling the requirements of City of Wanneroo District Planning Scheme No. 2 for the applicable 'Urban Development' zone.

The Regulations require decision-makers to have due regard for the provisions of this structure plan, which takes effect on the date on which it is approved by the Western Australian Planning Commission ('WAPC').

Unless otherwise specified in this Part, all words and expressions used in this structure plan have the same meaning as the same words and expressions in the Regulations and City of Wanneroo District Planning Scheme No. 2.

4.0 LAND USE AND SUBDIVISION

4.1 Zones and reserves

Subdivision and development of land within the structure plan area should be in accordance with the structure plan (Plans 1, 2 and 3) and the corresponding zone or reserve under City of Wanneroo District Planning Scheme No. 2.

4.2 Residential densities

[4.2.1 Dwelling target](#)

It is the objective of this structure plan to provide a minimum of 20 dwellings per gross Urban-zoned hectare, consistent with State Planning Policy 4.2: *Activity Centres for Perth and Peel*, and 22 dwellings per hectare of Net Developable Area, consistent with *Liveable Neighbourhoods*.

[4.2.2 Residential density](#)

The residential densities applicable to the structure plan area are shown on Plan 3.

[4.2.4 Built form \(R40 and R60\)](#)

The R-Codes variations specified in Planning Bulletin 112: *Medium-density single house development standards – Development Zones* and duplicated in the City of Wanneroo Local Planning Policy 4.19: *Medium-Density Housing Standards* are applicable to all land coded R40 or R60.

[4.2.5 Built form \(R80/R100\)](#)

Consistent with Section 5 of this structure plan, Local Development Plan/s for land coded R80/R100 are to be prepared pursuant to condition/s of subdivision approval. The Local Development Plan/s may be used to specify R-Codes variations and any other matter contemplated in the Regulations.

4.3 District Centre

A District Centre developed generally in accordance with State Planning Policy 4.2: *Activity Centres for Perth and Peel* is permitted on the land zoned 'Commercial' on the Structure Plan Map.

4.4 Public open space

A minimum of 10 per cent of the gross subdivisible area, less deductions permitted under Liveable Neighbourhoods, is to be provided as public open space. This should be provided generally in the locations shown on the Structure Plan Map.

5.0 LOCAL DEVELOPMENT PLANS


At the subdivision stage, the WAPC may impose a condition/s of approval requiring Local Development Plan/s to be prepared, in accordance with Part 6 of the Regulations, for lots that:

- Are rear-loaded;
- Abut public open space;
- Are coded R80/R100;
- Are identified for a Commercial purpose;
- Are affected by road or rail transport noise and require noise mitigation measures at the development stage

6.0 ADDITIONAL INFORMATION

At the subdivision stage, as relevant, the WAPC may require and/or impose a condition/s of approval requiring the preparation and submission of the following technical reports:

Additional Information	Approval Stage	Consultation Required
Bushfire Management Plan (BAL Contour Plan)	Subdivision (pre-approval)	City of Wanneroo WAPC
Acoustic Assessment	Subdivision (pre-approval)	City of Wanneroo WAPC
Urban Water Management Plan	Subdivision (condition of approval)	City of Wanneroo WAPC



The issue of intersection spacing and design to Yanchep Beach Road to be further considered during the preparation of a Local Structure Plan for the Centre Zone land.

T Junction
Left In/Left Out

Driveway
Access Point
Left In/Left Out

Left In/Left Out only Intersection
Upon completion of traffic planning for Yanchep Beach Road a full four way intersection may be supported.

T Junction
Full Movement

T Junctions Left
In/Left Out

Existing T Junction
Left In/Left Out

Driveway Access
Left In/Left Out

Full Movement 4 Way
Intersection with
traffic lights

General Preferred Location for Interim
Wastewater Transfer Pump Station.
A Site of approx. 2000m² with a 30m
buffer within this envelope is required.
Final location resolved at the
Subdivision/Development Stage.

T Junction
Full Movement

T Junction
Full Movement


Future Railway
Alignment

LEGEND








 Public Open Space

LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
STRUCTURE PLAN No. 40
PLAN No. 1 - LOCAL STRUCTURE PLAN






LEGEND

-  Structure Plan Boundary
-  Residential Zone
-  Commercial
-  Business Zone
-  Centre Zone & Private Clubs/Recreation
-  Public Purpose - High School Reservation
-  Other Regional Road Reserve

LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
 STRUCTURE PLAN No. 40
 PLAN No. 2 - ZONING PLAN



LOT 1 & LOT 102 YANCHEP BEACH ROAD, YANCHEP
 STRUCTURE PLAN No. 40
 PLAN No. 3 - R-CODE PLAN

APPENDIX 4

PTA Advice on South Yanchep Station

4

Mark de Cruz

To: Alex Watson
Subject: RE: Jindowie Land Estate

From: Lam Sin Cho, Jade <Jade.LamSinCho@pta.wa.gov.au>
Sent: Thursday, 31 October 2019 8:04 AM
To: Stuart Sinclair <Stuart.Sinclair@housing.wa.gov.au>
Subject: Jindowie Land Estate

Hi Stuart

Thanks for your query regarding the provision for a future train station in Jindowie Land Estate (Australand) in Yanchep. The Yanchep Rail Extension will deliver three new stations, Alkimos, Eglinton and Yanchep. No future provision has been made for a station at Australand.

If you have any further queries please don't hesitate to contact me.

Regards

Jade Lam Sin Cho
Strategic Railway Network Planner | Infrastructure Planning & Land Services
Public Transport Authority of Western Australia
Level 4, Public Transport Centre, West Parade, Perth, 6000
PO Box 8125, Perth Business Centre, WA, 6849
Tel: (08) 9326 2473
Email: jade.lamsincho@pta.wa.gov.au | Web: www.pta.wa.gov.au

Please note that my working days are Monday, Tuesday, Thursday and Friday.



The Public Transport Authority of Western Australia cannot accept any liability for any loss or damage sustained as a result of software viruses. You must carry out such virus checking as is necessary before opening any attachment to this message. The information in this email and any files transmitted with it may be of a privileged and/or confidential nature and is intended solely for the addressee(s). If you are not an intended addressee please notify the sender immediately, and note that any disclosure, copying or distribution by you is prohibited and may be unlawful. The views expressed in this email are not necessarily the views of the Public Transport Authority.

The Department of Communities acknowledges the traditional owners of country throughout Western Australia and their connection to land, waters and community. We pay our respects to them and their cultures, and to their elders past and present.

The Department of Communities (Communities) formed on 1 July 2017 and is responsible for the delivery of child protection and family support, community grants, funding and initiatives, education and care regulation, disability services, housing and regional services reform. During the transition phase emails sent from the Housing Authority domain will be converted to the Communities email address. This message may contain privileged and confidential information and is intended for the exclusive use of the addressee(s). You must not disclose this communication to anyone without the prior consent of Communities. If you have received this email in error, please notify us by return mail, delete it from your system and destroy all copies. Communities has exercised care to avoid errors in the information contained in this email but does not warrant that it is error or omission free.

APPENDIX 5

**Transportation Noise Assessment (Lloyd George
Acoustics, April 2020)**

5



Lloyd George Acoustics

PO Box 717
Hillarys WA 6923
T: 9401 7770

www.lgacoustics.com.au

Transportation Noise Assessment

Lots 9038 & 9040 Yanchep Beach Road

Structure Plan

Reference: 19105224-01A

Prepared for:
Department of Communities



Report: 19105224-01A

Lloyd George Acoustics Pty Ltd

ABN: 79 125 812 544

PO Box 717
Hillarys WA 6923

www.lgacoustics.com.au

T: 9401 7770

Contacts	Daniel Lloyd	Terry George	Matt Moyle	Olivier Mallié	Ben Hillion	Rob Connolly
E:	daniel@lgacoustics.com.au	terry@lgacoustics.com.au	matt@lgacoustics.com.au	olivier@lgacoustics.com.au	ben@lgacoustics.com.au	rob@lgacoustics.com.au
M:	0439 032 844	0400 414 197	0412 611 330	0439 987 455	0457 095 555	0410 107 440

This report has been prepared in accordance with the scope of services described in the contract or agreement between Lloyd George Acoustics Pty Ltd and the Client. The report relies upon data, surveys, measurements and results taken at or under the particular times and conditions specified herein. Any findings, conclusions or recommendations only apply to the aforementioned circumstances and no greater reliance should be assumed or drawn by the Client. Furthermore, the report has been prepared solely for use by the Client, and Lloyd George Acoustics Pty Ltd accepts no responsibility for its use by other parties.

Date:	Rev	Description	Prepared By	Verified
30/01/2020	-	Issued to Client	Daniel Lloyd	Terry George
09/04/2020	A	Updated Structure Plan	Daniel Lloyd	Terry George

Table of Contents

1	INTRODUCTION	1
2	CRITERIA	3
3	METHODOLOGY	4
3.1	Site Measurements	4
3.2	Noise Modelling	5
3.2.1	Ground Topography	6
3.2.2	Traffic Data	6
3.2.3	Train Movements	7
3.2.4	Ground Attenuation	7
3.2.5	Parameter Conversion	7
4	RESULTS	8
4.1	Noise Measurements	8
4.2	Noise Modelling	8
5	ASSESSMENT	10

List of Tables

Table 2-1	Noise Targets for Noise-Sensitive Land-Use	4
Table 3-1	Sound Pressure Levels Used in the Noise Model	5
Table 3-2	Noise Relationship Between Different Road Surfaces	6
Table 3-3	Traffic Information Used in the Modelling	6
Table 3-4	Daily Rail Movements Assumed in the Modelling	7
Table 4-1	Measured Noise Levels	8

List of Figures

Figure 1-1 Structure Plan for Lot 9038	1
Figure 1-2 Concept Subdivision for Lot 9040	2
Figure 4-1 Predicted Future Noise Levels – Ground Floor Level	9
Figure 5-1 Proposed Noise Wall Design	11

Appendices

- A Acceptable Treatment Packages
- B Terminology

1 INTRODUCTION

The Department of Communities is developing a Structure Plan for residential development on Lots 9038 and 9040 Yanchep Beach Road, Yanchep. The land is defined by Yanchep Beach Road to the north and the future Passenger railway to the east of Lot 9038 and the west of Lot 9040.

Lloyd George Acoustics have been commissioned to undertake a transport noise assessment in accordance with the *State Planning Policy No. 5.4 Road and Rail Noise* and to prepare a report detailing the noise impacts associate with the surrounding roads and passenger railway.

The proposed structure plan is presented in *Figures 1-1 and 1-2*.

Appendix B contains a description of some of the terminology used throughout this report.




Figure 1-1 Structure Plan for Lot 9038



Figure 1-2 Concept Subdivision for Lot 9040

2 CRITERIA

The criteria relevant to this assessment is provided in *State Planning Policy No. 5.4 Road and Rail Noise* (hereafter referred to as SPP 5.4) produced by the Western Australian Planning Commission (WAPC). The objectives of SPP 5.4 are to:

- Protect the community from unreasonable levels of transport noise;
- Protect strategic and other significant freight transport corridors from incompatible urban encroachment;
- Ensure transport infrastructure and land-use can mutually exist within urban corridors;
- Ensure that noise impacts are addressed as early as possible in the planning process; and
- Encourage best practice noise mitigation design and construction standards

Table 2-1 sets out noise targets that are to be achieved by proposals under which SPP 5.4 applies. Where the targets are exceeded, an assessment is required to determine the likely level of transport noise and management/mitigation required.

Table 2-1 Noise Targets for Noise-Sensitive Land-Use

Outdoor Noise Target		Indoor Noise Target	
55 dB L _{Aeq} (Day)	50 dB L _{Aeq} (Night)	40 dB L _{Aeq} (Day) (Living and Work Areas)	35 dB L _{Aeq} (Night) (Bedrooms)

Notes:

- Day period is from 6am to 10pm and night period from 10pm to 6am.
- The outdoor noise target is to be measured at 1-metre from the most exposed, habitable¹ facade of the noise sensitive building.
- For all noise-sensitive land-use and/or development, indoor noise targets for other room usages may be reasonable drawn from Table 1 of Australian Standard/New Zealand Standard AS/NZS 2107:2016 Acoustics – Recommended design sound levels and reverberation times for building interiors (as amended) for each relevant time period.
- Outdoor targets are to be met at all outdoor areas as far as is reasonable and practicable to do so using the various noise mitigation measures outlined in the Guidelines.

The application of SPP 5.4 is to consider anticipated traffic volumes for the next 20 years from when the noise assessment is undertaken.

In the application of the noise targets, the objective is to achieve:

- indoor noise levels specified in *Table 2-1* in noise-sensitive areas (e.g. bedrooms and living rooms of houses and school classrooms); and
- a reasonable degree of acoustic amenity for outdoor living areas on each residential lot. For non-residential noise-sensitive developments, for example schools and childcare centres, the design of outdoor areas should take into consideration the noise target.

It is recognised that in some instances, it may not be reasonable and/or practicable to meet the outdoor noise targets. Where transport noise is above the noise targets, measures are expected to be implemented that balance reasonable and practicable considerations with the need to achieve acceptable noise protection outcomes.

3 METHODOLOGY

Noise measurements and modelling have been undertaken generally in accordance with the requirements of SPP 5.4 and associated Guidelines² as described in *Section 3.1* and *Section 3.2*.

3.1 Site Measurements

Noise monitoring was undertaken at one (1) location in order to:

- Quantify the existing noise levels;
- Determine the differences between different acoustic parameters (L_{Aeq}(Day) and L_{Aeq}(Night)); and
- Calibrate the noise model for existing conditions.

¹ A habitable room is defined in State Planning Policy 3.1 as a room used for normal domestic activities that includes a bedroom, living room, lounge room, music room, sitting room, television room, kitchen, dining room, sewing room, study, playroom, sunroom, gymnasium, fully enclosed swimming pool or patio.

² Road and Rail Noise Guidelines, September 2019

The measurements were taken over a two-hour period during peak times using a Rion NA28 hand-held sound level meter (S/N: 1270692) located 11 metres from the edge of Yanchep Road. The microphone was positioned 1.4 metres above ground. This instrument complies with the instrumentation requirements of *Australian Standard 2702-1984 Acoustics – Methods for the Measurement of Road Traffic Noise*. The meter was field calibrated before and after the measurement session and found to be accurate to within +/- 1 dB. Lloyd George Acoustics also holds current laboratory calibration certificate for the loggers.

The overall daytime and night-time noise levels were calculated by adjusting the hourly noise levels based on the measured hourly traffic volumes provided by Main Roads via their website.

3.2 Noise Modelling

The computer programme *SoundPLAN 8.1* was utilised incorporating the *Calculation of Road Traffic Noise* (CoRTN) algorithms for road noise and the Nordic Rail Prediction Method (Kilde Rep. 130) algorithm for train noise. Both algorithms have been modified to reflect Australian conditions.

The modifications included the following:

- Vehicles were separated into heavy (Austroads Class 3 upwards) and non-heavy (Austroads Classes 1 & 2) with non-heavy vehicles having a source height of 0.5 metres above road level and heavy vehicles having two sources, at heights of 1.5 metres and 3.6 metres above road level, to represent the engine and exhaust respectively. By splitting the noise source into three, allows for less barrier attenuation for high level sources where barriers are to be considered.
- Note that a -8.0 dB correction is applied to the exhaust and -0.8 dB to the engine (based on Transportation Noise Reference Book, Paul Nelson, 1987), so as to provide consistent results with the CoRTN algorithms for the no barrier scenario;
- Adjustments of -0.8 dB and -1.7 dB have been applied to the predicted levels for the ‘free-field’ and ‘at facade’ cases respectively, based on the findings of *An Evaluation of the U.K. DoE Traffic Noise Prediction*; Australian Road Research Board, Report 122 ARRB – NAASRA Planning Group (March 1983).
- Train modification to align with measured noise levels of passenger trains operating in the Perth region. Measured noise levels used are shown in *Table 3-1*.

Table 3-1 Sound Pressure Levels Used in the Noise Model

Description	dB(A) at One-Third Octave Frequencies (Hz)									Overall dB(A)
	31.5	63	125	250	500	1K	2K	4K	8K	
Train speed of 130 km/hr at a distance of 15m	30	51	59	62	73	79	79	77	69	87
	35	54	61	65	73	79	80	74	64	
	42	53	61	69	78	80	78	72	58	

Predictions are made at heights of 1.4 m above ground floor level for single storey houses. The noise is predicted at 1.0 metre from an assumed building facade resulting in a + 2.5 dB correction due to reflected noise.

Various input data are included in the modelling such as ground topography, road design, traffic volumes etc. These model inputs are discussed in the following sections.

3.2.1 Ground Topography

Topographical data for this project was provided by CLE Plan. As this project is only at “Structure Plan” stage, information on subdivision levels are preliminary only and therefore the modelling uses the preliminary earthworks topography.

The approximate location of future houses have also been included as these can provide barrier attenuation when located between a source and receiver, in much the same way as a hill or wall provides noise shielding. All buildings are assumed to be single storey with a height of 3.5 metres.

3.2.2 Traffic Data

Traffic data includes:

- Road Surface – The noise relationship between different road surface types is shown in *Table 3-2*.

Table 3-2 Noise Relationship Between Different Road Surfaces

Road Surfaces						
Chip Seal			Asphalt			
14mm	10mm	5mm	Dense Graded	Novachip	Stone Mastic	Open Graded
+3.5 dB	+2.5 dB	+1.5 dB	0.0 dB	-0.2 dB	-1.5 dB	-2.5 dB

The existing and future road surface on Yanchep Beach Road is assumed to be dense graded asphalt.

- Vehicle Speed – The existing and future posted speed is assumed to be 80km/hr.
- Traffic Volumes – 2016 and 2041 traffic volumes were provided by Main Roads WA (Clare Yu ref: 41352). *Table 3-3* provides the traffic volume input data in the model.

Table 3-3 Traffic Information Used in the Modelling

Parameter	2016			2041		
	Eastbound	Westbound	% Heavy	Eastbound	Westbound	% Heavy
24 Hour Volume	5,200	4,100	1	21,400	21,300	1

Note: 18 hour volumes used in the CoRTN algorithms are assumed to be 94% of 24-hour volumes

3.2.3 Train Movements

The number of train movements assumed in the model has been provided by PTA and are detailed in *Table 3-4*.

Table 3-4 Daily Rail Movements Assumed in the Modelling

Train Description	Train Movements	
	Day	Night
Northbound		
6 Car Sets	75	22
Southbound		
6 Car Sets	75	22

3.2.4 Ground Attenuation

The ground attenuation has been assumed to be 0.0 (0%) for the road, 0.75 (75%) throughout the subdivision, except for the public open space, which was set to 1.00 (100%). Note 0.0 represents hard reflective surfaces such as water and 1.00 represents absorptive surfaces such as grass.

3.2.5 Parameter Conversion

The CoRTN algorithms used in the *SoundPLAN* modelling package were originally developed to calculate the $L_{A10,18\text{hour}}$ traffic noise level. SPP 5.4 however uses $L_{Aeq(\text{Day})}$ and $L_{Aeq(\text{Night})}$. The relationship between the parameters varies depending on the composition of traffic on the road (volumes in each period and percentage heavy vehicles).

As noise monitoring was undertaken, the relationship between the parameters is based on the results of the monitoring – refer *Section 4.1*.

4 RESULTS

4.1 Noise Measurements

The results of the noise measurements are summarised in *Table 4-1*.

Table 4-1 Measured Noise Levels

Date	Average Weekday Noise Level, dB		
	Hourly (0600 & 0700)	L _{Aeq} (Day)	L _{Aeq} (Night)
2 December 2019	62.0	60.8	54.2


The average differences between the weekday L_{Aeq}(Day) and L_{Aeq}(Night) is 6.6 dB. This same difference has been assumed to exist in future years. As such, it is the daytime noise levels that will dictate compliance since these are at least 5 dB more than night-time levels.

This data is also used to calibrate the noise model. This is achieved by predicting the traffic noise level at the noise measurement location assuming the existing traffic volumes and comparing these results against the measured values. The results of the calibration showed that the model was over predicting by 2.1 dB and the results of the modelling have been adjusted accordingly.

4.2 Noise Modelling

The results of the noise modelling for future conditions is provided in *Figure 4-1* as an L_{Aeq}(Day) noise level contour plot. It can be seen that predicted noise levels at the nearest houses will be above the *target* and therefore noise control is to be considered.

Figure 4-1






Noise levels
L_{Aeq,Day} dB

<= 55	Exposure A
<= 56	
<= 57	Exposure B
<= 58	
<= 59	Exposure C
<= 60	
<= 61	Exposure D
<= 62	
<= 63	
<= 64	
<= 65	
<= 66	
> 66	


SPP 5.4 (Sep 2019)

Signs and symbols

-  Building
-  Road
-  Railway



Length Scale



Lots 9038 & 9040 Yanchep Beach Road
 Predicted Noise Level Contours - No Noise Mitigation

L_{Aeq}(Day) Noise Level Contours
 Ground Floor Level

SoundPlan v8.1
 CoRTN & Nordic Algorithms

7 January 2020



Lloyd George Acoustics
 PO Box 717
 HILLARYS WA 6923
 (08) 9401 7770

5 ASSESSMENT

The objectives of SPP 5.4 are to achieve:

- indoor noise levels specified in *Table 2-1* in noise-sensitive areas (e.g. bedrooms and living rooms of houses and school classrooms); and
- a reasonable degree of acoustic amenity for outdoor living areas on each residential lot.

Where the outdoor noise targets of *Table 2-1* are achieved, no further controls are necessary.

With reference to the predicted noise levels in *Section 4.2*, it is evident the outdoor noise target will be exceeded.

As this project is only at “Structure Plan” phase, the suggested noise mitigation measures are indicative only. They have been designed to achieve a reasonable degree of amenity and facade packages may also be required to achieve compliance with SPP 5.4.


Therefore our preliminary recommendations are:

- Construct noise barriers as shown in *Figure 5-1*. The noise barrier is to be solid, free of gaps and of minimum surface mass 15kg/m^2 . Alternatively, an earth bund could be constructed.
- Where lots are still above the outdoor noise target (refer *Figure 5-1*), the following Packages (refer *Appendix A*) are required:
 - Package A where noise levels are between 56 dB and 58 dB $L_{\text{Aeq(Day)}}$;
 - Package B where noise levels are between 59 dB and 62 dB $L_{\text{Aeq(Day)}}$;
 - Package C where noise levels are between 63 dB and 66 dB $L_{\text{Aeq(Day)}}$;

Alternative constructions from the deemed to satisfy packages may be acceptable if supported by a report undertaken by a suitably qualified acoustical consultant (member from of the Association of Australasian Acoustical Consultants (AAAC)), once the lots specific building plans are available.

- All affected lots are to have notifications on lot titles as per SPP 5.4 requirements – refer *Appendix A*.

Figure 5-1



Noise levels

$L_{Aeq,Day}$ dB

<= 55	Exposure A
<= 56	
<= 57	Exposure B
<= 58	
<= 59	Exposure C
<= 60	
<= 61	Exposure D
<= 62	
<= 63	
<= 64	
<= 65	
<= 66	
> 66	


SPP 5.4 (Sep 2019)

Signs and symbols

- Building
- Road
- Railway
- Wall



Length Scale



Lots 9038 & 9040 Yanchep Beach Road Predicted Noise Level Contours - With Noise Mitigation

$L_{Aeq(Day)}$ Noise Level Contours
Ground Floor Level

SoundPlan v8.1
CoRTN & Nordic Algorithms

7 January 2020



Lloyd George Acoustics
PO Box 717
HILLARYS WA 6923
(08) 9401 7770

Appendix A

ACCEPTABLE TREATMENT PACKAGES


The packages and information provided on the following pages are taken from *Road and Rail Noise Guidelines* (September 2019).

Where outdoor and indoor noise levels received by a noise-sensitive land-use and/or development exceed the policy's noise target, implementation of quiet house requirements is an acceptable solution.

The quiet house packages are not the only solution to achieving acceptable internal transport noise levels. A suitably qualified acoustical engineer or consultant may also determine more tailored acoustic design requirements for buildings in a transport noise corridor by carrying out acoustic design in accordance with relevant industry standards. This includes the need to meet the relevant design targets specified in AS/NZS 2107:2016 for road traffic noise.

With regards to the packages, the following definitions are provided:

- **Facing** the transport corridor (red): Any part of a building façade is 'facing' the transport corridor if any straight line drawn perpendicular (at a 90 degree angle) to its nearest road lane or railway line intersects that part of the façade without obstruction (ignoring any fence).
- **Side-on** to transport corridor (blue): Any part of a building façade that is not 'facing' is 'side-on' to the transport corridor if any straight line, at any angle, can be drawn from it to intersect the nearest road lane or railway line without obstruction (ignoring any fence).
- **Opposite** to transport corridor (green): Neither 'side on' nor 'facing', as defined above.



Quiet House Package A

56-58 dB $L_{Aeq}(\text{Day})$ & 51-53 dB $L_{Aeq}(\text{Night})$

Element	Orientation	Room	
		Bedroom	Indoor Living and Work Areas
External Windows	Facing	<ul style="list-style-type: none"> Up to 40% floor area ($R_w + C_{tr} \geq 28$): <ul style="list-style-type: none"> Sliding or double hung with minimum 10mm single or 6mm-12mm-10mm double insulated glazing; Sealed awning or casement windows with minimum 6mm glass. Up to 60% floor area ($R_w + C_{tr} \geq 31$): <ul style="list-style-type: none"> Sealed awning or casement windows with minimum 6mm glass. 	<ul style="list-style-type: none"> Up to 40% floor area ($R_w + C_{tr} \geq 25$): <ul style="list-style-type: none"> Sliding or double hung with minimum 6mm single or 6mm-12mm-6mm double insulated glazing; Up to 60% floor area ($R_w + C_{tr} \geq 28$); Up to 80% floor area ($R_w + C_{tr} \geq 31$).
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less or max % area increased by 20%.	
	Opposite	No specific requirements	
External Doors	Facing	<ul style="list-style-type: none"> Fully glazed hinged door with certified $R_w + C_{tr} \geq 28$ rated door and frame including seals and 6mm glass. 	<ul style="list-style-type: none"> Doors to achieve $R_w + C_{tr} \geq 25$: <ul style="list-style-type: none"> 35mm Solid timber core hinged door and frame system certified to $R_w 28$ including seals; Glazed sliding door with 10mm glass and weather seals.
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less.	
	Opposite	No specific requirements	
External Walls	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 45$: <ul style="list-style-type: none"> Two leaves of 90mm thick clay brick masonry with minimum 20mm cavity; Single leaf of 150mm brick masonry with 13mm cement render on each face. One row of 92mm studs at 600mm centres with: <ul style="list-style-type: none"> Resilient steel channels fixed to the outside of the studs; and 9.5mm hardboard or fibre cement sheeting or 11mm fibre cement weatherboards fixed to the outside; 75mm thick mineral wool insulation with a density of at least 11kgkg/m³; and 2 x 16mm fire-rated plasterboard to inside. 	
Roofs and Ceilings	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 35$: <ul style="list-style-type: none"> Concrete or terracotta tile or metal sheet roof with sarking and at least 10mm plasterboard. 	
Outdoor Living Areas	At least one outdoor living area located on the opposite side of the building from the transport corridor and/or at least one ground level outdoor living area screened using a solid continuous fence or other structure of minimum 2 metres height above ground level.		

Quiet House Package B

59-62 dB $L_{Aeq}(\text{Day})$ & 54-57 dB $L_{Aeq}(\text{Night})$

Element	Orientation	Room	
		Bedroom	Indoor Living and Work Areas
External Windows	Facing	<ul style="list-style-type: none"> Up to 40% floor area ($R_w + C_{tr} \geq 31$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 6mm glass or 6mm-12mm-6mm double insulated glazing. Up to 60% floor area ($R_w + C_{tr} \geq 34$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 10mm glass or 6mm-12mm-10mm double insulated glazing. 	<ul style="list-style-type: none"> Up to 40% floor area ($R_w + C_{tr} \geq 28$): <ul style="list-style-type: none"> Sliding or double hung with 6mm-12mm-10mm double insulated glazing; Sealed awning or casement windows with minimum 6mm glass. Up to 60% floor area ($R_w + C_{tr} \geq 31$); Up to 80% floor area ($R_w + C_{tr} \geq 34$).
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less or max % area increased by 20%.	
	Opposite	As above, except $R_w + C_{tr}$ values may be 6 dB less or max % area increased by 20%.	
External Doors	Facing	<ul style="list-style-type: none"> Fully glazed hinged door with certified $R_w + C_{tr} \geq 31$ rated door and frame including seals and 10mm glass. 	<ul style="list-style-type: none"> Doors to achieve $R_w + C_{tr} \geq 28$: <ul style="list-style-type: none"> 40mm Solid timber core hinged door and frame system certified to $R_w 32$ including seals; Fully glazed hinged door with certified $R_w + C_{tr} \geq 28$ rated door and frame including seals and 6mm glass.
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less or max % area increased by 20%.	
	Opposite	As above, except $R_w + C_{tr}$ values may be 6 dB less or max % area increased by 20%.	
External Walls	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 50$: <ul style="list-style-type: none"> Two leaves of 90mm thick clay brick masonry with minimum 50mm cavity between leaves and 50mm glasswool or polyester insulation (R2.0+). Resilient ties used where required to connect leaves. Two leaves of 110mm clay brick masonry with minimum 50mm cavity between leaves and 50mm glasswool or polyester insulation (R2.0+). Single leaf of 220mm brick masonry with 13mm cement render on each face. 150mm thick unlined concrete panel or 200mm thick concrete panel with one layer of 13mm plasterboard or 13mm cement render on each face. Single leaf of 90mm clay brick masonry with: <ul style="list-style-type: none"> A row of 70mm x 35mm timber studs or 64mm steel studs at 600mm centres; A cavity of 25mm between leaves; 50mm glasswool or polyester insulation (R2.0+) between studs; and One layer of 10mm plasterboard fixed to the inside face. 	
Roofs and Ceilings	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 35$: <ul style="list-style-type: none"> Concrete or terracotta tile or metal sheet roof with sarking and at least 10mm plasterboard ceiling with R3.0+ fibrous insulation. 	
Outdoor Living Areas		At least one outdoor living area located on the opposite side of the building from the transport corridor and/or at least one ground level outdoor living area screened using a solid continuous fence or other structure of minimum 2.4 metres height above ground level.	

Quiet House Package C

63-66 dB $L_{Aeq}(\text{Day})$ & 58-61 dB $L_{Aeq}(\text{Night})$

Element	Orientation	Room	
		Bedroom	Indoor Living and Work Areas
External Windows	Facing	<ul style="list-style-type: none"> Up to 20% floor area ($R_w + C_{tr} \geq 31$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 6mm glass or 6mm-12mm-6mm double insulated glazing. Up to 40% floor area ($R_w + C_{tr} \geq 34$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 10mm glass or 6mm-12mm-10mm double insulated glazing. 	<ul style="list-style-type: none"> Up to 40% floor area ($R_w + C_{tr} \geq 31$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 6mm glass or 6mm-12mm-6mm double insulated glazing. Up to 60% floor area ($R_w + C_{tr} \geq 34$): <ul style="list-style-type: none"> Fixed sash, awning or casement with minimum 10mm glass or 6mm-12mm-10mm double insulated glazing.
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less or max % area increased by 20%.	
	Opposite	As above, except $R_w + C_{tr}$ values may be 6 dB less or max % area increased by 20%.	
External Doors	Facing	<ul style="list-style-type: none"> Not recommended. 	<ul style="list-style-type: none"> Doors to achieve $R_w + C_{tr} \geq 30$: <ul style="list-style-type: none"> Fully glazed hinged door with certified $R_w + C_{tr} \geq 31$ rated door and frame including seals and 10mm glass; 40mm Solid timber core side hinged door, frame and seal system certified to $R_w 32$ including seals. Any glass inserts to be minimum 6mm.
	Side On	As above, except $R_w + C_{tr}$ values may be 3 dB less or max % area increased by 20%.	
	Opposite	As above, except $R_w + C_{tr}$ values may be 6 dB less or max % area increased by 20%.	
External Walls	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 50$: <ul style="list-style-type: none"> Two leaves of 90mm thick clay brick masonry with minimum 50mm cavity between leaves and 50mm glasswool or polyester insulation (R2.0+). Resilient ties used where required to connect leaves. Two leaves of 110mm clay brick masonry with minimum 50mm cavity between leaves and 50mm glasswool or polyester insulation (R2.0+). Single leaf of 220mm brick masonry with 13mm cement render on each face. 150mm thick unlined concrete panel or 200mm thick concrete panel with one layer of 13mm plasterboard or 13mm cement render on each face. Single leaf of 90mm clay brick masonry with: <ul style="list-style-type: none"> A row of 70mm x 35mm timber studs or 64mm steel studs at 600mm centres; A cavity of 25mm between leaves; 50mm glasswool or polyester insulation (R2.0+) between studs; and One layer of 10mm plasterboard fixed to the inside face. 	
Roofs and Ceilings	All	<ul style="list-style-type: none"> $R_w + C_{tr} \geq 40$: <ul style="list-style-type: none"> Concrete or terracotta tile roof with sarking, or metal sheet roof with foil backed R2.0+ fibrous insulation between steel sheeting and roof battens; R3.0+ insulation batts above ceiling; 2 x 10mm plasterboard ceiling or 1 x 13mm sound-rated plasterboard affixed using steel furring channel to ceiling rafters. 	
Outdoor Living Areas		At least one outdoor living area located on the opposite side of the building from the transport corridor and/or at least one ground level outdoor living area screened using a solid continuous fence or other structure of minimum 2.4 metres height above ground level.	

Mechanical Ventilation requirements

In implementing the acceptable treatment packages, the following mechanical ventilation / air-conditioning considerations are required:

- Acoustically rated openings and ductwork to provide a minimum sound reduction performance of R_w 40 dB into sensitive spaces;
- Evaporative systems require attenuated ceiling air vents to allow closed windows;
- Refrigerant based systems need to be designed to achieve National Construction Code fresh air ventilation requirements;
- Openings such as eaves, vents and air inlets must be acoustically treated, closed or relocated to building sides facing away from the corridor where practicable.

Notification

Notifications on title advise prospective purchasers of the potential for noise impacts from major transport corridors and help with managing expectations.

The Notification is to state as follows:

This lot is in the vicinity of a transport corridor and is affected, or may in the future be affected, by road and rail transport noise. Road and rail transport noise levels may rise or fall over time depending on the type and volume of traffic.

Appendix B

Terminology

The following is an explanation of the terminology used throughout this report.

Decibel (dB)

The decibel is the unit that describes the sound pressure and sound power levels of a noise source. It is a logarithmic scale referenced to the threshold of hearing.

A-Weighting

An A-weighted noise level has been filtered in such a way as to represent the way in which the human ear perceives sound. This weighting reflects the fact that the human ear is not as sensitive to lower frequencies as it is to higher frequencies. An A-weighted sound level is described as L_A dB.

L_1

An L_1 level is the noise level which is exceeded for 1 per cent of the measurement period and is considered to represent the average of the maximum noise levels measured.

L_{10}

An L_{10} level is the noise level which is exceeded for 10 per cent of the measurement period and is considered to represent the “intrusive” noise level.

L_{90}

An L_{90} level is the noise level which is exceeded for 90 per cent of the measurement period and is considered to represent the “background” noise level.

L_{eq}

The L_{eq} level represents the average noise energy during a measurement period.

$L_{A10,18hour}$

The $L_{A10,18hour}$ level is the arithmetic average of the hourly L_{A10} levels between 6.00 am and midnight. The *CoRTN* algorithms were developed to calculate this parameter.

$L_{Aeq,24hour}$

The $L_{Aeq,24hour}$ level is the logarithmic average of the hourly L_{Aeq} levels for a full day (from midnight to midnight).

$L_{Aeq,8hour} / L_{Aeq} (Night)$

The $L_{Aeq} (Night)$ level is the logarithmic average of the hourly L_{Aeq} levels from 10.00 pm to 6.00 am on the same day.

$L_{Aeq,16hour} / L_{Aeq} (Day)$

The $L_{Aeq} (Day)$ level is the logarithmic average of the hourly L_{Aeq} levels from 6.00 am to 10.00 pm on the same day. This value is typically 1-3 dB less than the $L_{A10,18hour}$.

Noise-sensitive land use and/or development

Land-uses or development occupied or designed for occupation or use for residential purposes (including dwellings, residential buildings or short-stay accommodation), caravan park, camping ground, educational establishment, child care premises, hospital, nursing home, corrective institution or place of worship.

About the Term 'Reasonable'

An assessment of reasonableness should demonstrate that efforts have been made to resolve conflicts without comprising on the need to protect noise-sensitive land-use activities. For example, have reasonable efforts been made to design, relocate or vegetate a proposed noise barrier to address community concerns about the noise barrier height? Whether a noise mitigation measure is reasonable might include consideration of:

- The noise reduction benefit provided;
- The number of people protected;
- The relative cost vs benefit of mitigation;
- Road conditions (speed and road surface) significantly differ from noise forecast table assumptions;
- Existing and future noise levels, including changes in noise levels;
- Aesthetic amenity and visual impacts;
- Compatibility with other planning policies;
- Differences between metropolitan and regional situations and whether noise modelling requirements reflect the true nature of transport movements;
- Ability and cost for mobilisation and retrieval of noise monitoring equipment in regional areas;
- Differences between Greenfield and infill development;
- Differences between freight routes and public transport routes and urban corridors;
- The impact on the operational capacity of freight routes;
- The benefits arising from the proposed development;
- Existing or planned strategies to mitigate the noise at source.

About the Term 'Practicable'

'Practicable' considerations for the purposes of the policy normally relate to the engineering aspects of the noise mitigation measures under evaluation. It is defined as "reasonably practicable having regard to, among other things, local conditions and circumstances (including costs) and to the current state of technical knowledge" (*Environmental Protection Act 1986*). These may include:

- Limitations of the different mitigation measures to reduce transport noise;
- Competing planning policies and strategies;
- Safety issues (such as impact on crash zones or restrictions on road vision);
- Topography and site constraints (such as space limitations);
- Engineering and drainage requirements;
- Access requirements (for driveways, pedestrian access and the like);
- Maintenance requirements;
- Bushfire resistance or BAL ratings;
- Suitability of the building for acoustic treatments.


R_w

This is the weighted sound reduction index and is similar to the previously used STC (Sound Transmission Class) value. It is a single number rating determined by moving a grading curve in integral steps against the laboratory measured transmission loss until the sum of the deficiencies at each one-third-octave band, between 100 Hz and 3.15 kHz, does not exceed 32 dB. The higher the R_w value, the better the acoustic performance.

C_{tr}

This is a spectrum adaptation term for airborne noise and provides a correction to the R_w value to suit source sounds with significant low frequency content such as road traffic or home theatre systems. A wall that provides a relatively high level of low frequency attenuation (i.e. masonry) may have a value in the order of -4 dB, whilst a wall with relatively poor attenuation at low frequencies (i.e. stud wall) may have a value in the order of -14 dB.


Chart of Noise Level Descriptors



Austrroads Vehicle Class

VEHICLE CLASSIFICATION SYSTEM	
AUSTRADS	
CLASS	LIGHT VEHICLES
1	SHORT Car, Van, Wagon, 4WD, Utility, Bicycle, Motorcycle
2	SHORT - TOWING Trailer, Caravan, Boat
HEAVY VEHICLES	
3	TWO AXLE TRUCK OR BUS *2 axles
4	THREE AXLE TRUCK OR BUS *3 axles, 2 axle groups
5	FOUR (or FIVE) AXLE TRUCK *4 (5) axles, 2 axle groups
6	THREE AXLE ARTICULATED *3 axles, 3 axle groups
7	FOUR AXLE ARTICULATED *4 axles, 3 or 4 axle groups
8	FIVE AXLE ARTICULATED *5 axles, 3+ axle groups
9	SIX AXLE ARTICULATED *6 axles, 3+ axle groups of 7+ axles, 3 axle groups
LONG VEHICLES AND ROAD TRAINS	
10	DOUBLE HEAVY TRUCK and TRAILER *7+ axles, 4 axle groups
11	DOUBLE ROAD TRAIN *7+ axles, 5 or 6 axle groups
12	TRIPLE ROAD TRAIN *7+ axles, 7+ axle groups

Typical Noise Levels



A P P E N D I X 6



**Bushfire Management Plan (Entire Fire Management
March 2020)**

6

AS 3959 Bushfire Contour & Bushfire Hazard Level Report

Site Details			
Address:	Jindowie		
Suburb:	Yanchep	Postcode:	6035
Local Government Area:	City of Wanneroo		
Description of Building Works:	Redevelopment		


Report Details			
Report Number:	2-2824	Report Revision:	1
Assessment Date:	19/03/2020	Report Date:	31/03/2020

BPAD Accredited Practitioner Details	
Name:	Gavin Fancote
Company Details:	Entire Fire Management
<p>I hereby certify that I have undertaken the assessment of the above-mentioned site and determined the Bushfire Attack Level stated above in accordance with the requirements of AS 3959 -2009 (Method 1)</p>	
<p>I hereby declare that I am a BPAD accredited bushfire practitioner.</p> 	
Accreditation No.	BPAD37922
Signature:	
<p><i>Authorised Practitioner Stamp</i></p>	
<p><i>Reliance on the assessment and determination of the Bushfire Attack Level contained in this report should not extend beyond a period of 12 months from the Assessment date. If the assessment was completed more than 12 months ago, it is recommended that the validity of the determination be confirmed with the Accredited Practitioner and where required an updated report issued.</i></p>	

Site Assessment & Site Plans

(Attached as page 2 of this report)

The assessment of this site / development was undertaken on the above-mentioned date by an Accredited BPAD Practitioner for determining the Bushfire Attack Level in accordance with AS 3959 - 2009 Simplified Procedure (Method 1).



Entire Empire Pty Ltd
 ABN: 63 468 728 651
 Office: (08) 9498 0056
 Address: 6 Potts Road
 Forrestdale Business Park
 Forrestdale WA 6112

Project Yindowie - Yanchep

Title Vegetation Classification

Size A3 **Scale** 1:3000 **Sheet** 2-2824 **Rev** 0

Name Gavin Fancote **Date** 20 Mar 2020

Legend

	Class A - Forest
	Class B - Woodland
	Class C - Shrubland
	Class D - Scrub
	Class G - Grassland

	Subject Property
	150m Exclusion Zone
	100m Exclusion Zone
	Photo Location
	Vegetation Plot Boundary

Excluded c2.2.3.2(f)

Notes

0 40 80 **Meters**



Plot 4
Class B - Woodland
Upslope 3°

Plot 2
Class B - Woodland
Upslope 7°

Plot 3
Class A - Forest
Upslope 3°

Plot 9
Class C - Shrubland
Flat

Plot 13
Class C - Shrubland
Upslope 2°

Plot 15
Class C - Shrubland
Flat

Plot 20
Class C - Scrub
Downslope 12°

Plot 21
Class A - Forest
Downslope 12°

Plot 22
Class D - Scrub
Upslope 3°

Plot 23
Class D - Scrub
Downslope 3°

Entire Empire Pty Ltd
 ABN: 63 468 728 651
 Office: (08) 9498 0056
 Address: 6 Potts Road
 Forrestdale Business Park
 Forrestdale WA 6112



Project Yindowie - Yanchep		Rev	0
Title	BAL Contour Assessment	Sheet	BAL C 2-2824
Size	A3	Scale	1:3000
Name	Gavin Fancote	Date	20 Mar 2020


Legend


- Property Boundary
- Proposed Building
- 100m Exclusion Zone
- 150m Assessment area
- Vegetation Plot Boundary

Indicative Bushfire Attack Levels:

- BAL-LOW
- BAL-12.5
- BAL-19
- BAL-29
- BAL-40
- BAL-FZ

Notes





Plot 3
Class A – Forest
Upslope 3°

Plot 2
Class B – Woodland
Upslope 7°

Plot 4
Class B – Woodland
Upslope 3°

Plot 5
Class G – Grassland
Upslope 3°

Plot 10
Class A – Forest
Flat

Plot 9
Class C – Shrubland
Flat

Plot 13
Class C – Shrubland
Upslope 2°

Plot 15
Class C – Shrubland
Flat

Plot 20
Class C – Scrub
Downslope 12°

Plot 21
Class A – Forest
Downslope 12°

Plot 22
Class D – Scrub
Upslope 3°

Plot 23
Class D – Scrub
Downslope 3°

Entire Empire Pty Ltd
 ABN: 63 468 728 651
 Office: (08) 9498 0056
 Address: 6 Potts Road
 Forrestdale Business Park
 Forrestdale WA 6112



Legend

- Subject Development
- Low Hazard Level
- Moderate Hazard Level
- Extreme Hazard Level


Project Yindowie – Yanchiep

Title Bushfire Hazard Level

Size A3 Scale 1:3000 Sheet BHL 2-2824 Rev 0

Name Gavin Fancote Date 20 Mar 2020

Notes



Vegetation Classification

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	1	Plot no:	1	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings and rocky outcrops.				



Photo ID:	2	Plot no:	2	
Vegetation Classification or Exclusion Clause				
Class B - Woodland				
Description				
Trees averaging height 10m-12m with 10%-30% foliage cover dominated by eucalypts with a prominent grassy understorey, includes small shrubs.				

Photo ID:	3	Plot no:	3	
Vegetation Classification or Exclusion Clause				
Class A - Forrest				
Description				
Trees averaging height 10m-12m; 30%-70% foliage cover Typically dominated by eucalypts. May include low trees or shrubs. Dense vegetation within Plot				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	4	Plot no:	4	
Vegetation Classification or Exclusion Clause				
Class B - Woodland				
Description				
Trees averaging height 10m-15m with 10%-30% foliage cover dominated by eucalypts with a prominent grassy understorey. Low Shrubs surrounding set in a small reserve.				



Photo ID:	5	Plot no:	5	
Vegetation Classification or Exclusion Clause				
Class G - Grassland				
Description				
Low lying sparse vegetation including situations with shrubs and isolated trees, if the overstorey foliage cover is less than 10%.				

Photo ID:	6	Plot no:	6	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings.				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	7	Plot no:	7	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings.				



Photo ID:	8	Plot no:	8	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings.				

Photo ID:	9	Plot no:	9	
Vegetation Classification or Exclusion Clause				
Class C - Shrubland				
Description				
Found in area affected by poor quality soil or shallow soils. Shrubs average height 1m not greater than 2m high.				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	10	Plot no:	10	
Vegetation Classification or Exclusion Clause				
Class A - Forrest				
Description				
Trees averaging height 10m-12m; 30%-70% foliage cover Typically dominated by eucalypts. May include low trees or shrubs. Dense vegetation within Plot.				



Photo ID:	11	Plot no:	11	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings and rocky outcrops. Plot is included within the development.				

Photo ID:	12	Plot no:	12	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings and rocky outcrops.				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	13	Plot no:	13	
Vegetation Classification or Exclusion Clause				
Class C - Shrubland				
Description				
Found in area affected by poor quality soil or shallow soils. Shrubs 1m-2m high.				



Photo ID:	14	Plot no:	14	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings and rocky outcrops. Plot is included within the development.				

Photo ID:	15	Plot no:	15	
Vegetation Classification or Exclusion Clause				
Class C - Shrubland				
Description				
Found in area affected by poor quality soil or shallow soils. Shrubs averaging height of 1m not greater 2m high.				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	16	Plot no:	16	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings and rocky outcrops.				



Photo ID:	17	Plot no:	17	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (f) Regarded as Low threat vegetation : managed grasslands in a minimum fuel condition. Including Public reserves, parklands, nature strips and windbreaks				

Photo ID:	18	Plot no:	18	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (f) Regarded as Low threat vegetation : managed grasslands in a minimum fuel condition. Including Public reserves, parklands, nature strips and windbreaks				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	19	Plot no:	19	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings.				



Photo ID:	20	Plot no:	20	
Vegetation Classification or Exclusion Clause				
Class D - Scrub				
Description				
Found in areas with poor soil fertility. Shrubs >2m high up to 6m				

Photo ID:	21	Plot no:	21	
Vegetation Classification or Exclusion Clause				
Class A - Forrest				
Description				
Trees averaging height 12-15m; 30%-70% foliage cover Typically dominated by eucalypts. May include low trees or shrubs. Dense vegetation within Plot.				

Vegetation Classification (continued)

All vegetation within 100m of the site / proposed development was classified in accordance with Clause 2.2.3 of AS 3959-2009. Each distinguishable vegetation plot with the potential to determine the Bushfire Attack Level is identified below.


Photo ID:	22	Plot no:	22	
Vegetation Classification or Exclusion Clause				
Class D - Scrub				
Description				
Found in areas with poor soil fertility. Shrubs >2m high up to 6m. Plot joins larger area of Scrub out of 100m radius.				



Photo ID:	23	Plot no:	23	
Vegetation Classification or Exclusion Clause				
Class D - Scrub				
Description				
Found in areas with poor soil fertility. Shrubs >2m high up to 6m				

Photo ID:	24	Plot no:	24	
Vegetation Classification or Exclusion Clause				
Excluded - Low Threat Vegetation				
Description				
2.2.3.2 (e) Non vegetated areas that are permanently cleared of vegetation, roads, buildings. Developed sporting complex, car parks, tennis courts, maintained ovals.				

Appendix 2: Plans and Drawings

Plans and drawings relied on to determine the Bushfire Attack Level.

