

Bushfire management plan/Statement addressing the Bushfire Protection Criteria coversheet

Site address:

Site visit: Yes No

Date of site visit (if applicable): Day Month Year

Report author or reviewer:

WA BPAD accreditation level (please circle):

Not accredited Level 1 BAL assessor Level 2 practitioner Level 3 practitioner

If accredited please provide the following.

BPAD accreditation number: Accreditation expiry: Month Year

Bushfire management plan version number:

Bushfire management plan date: Day Month Year

Client/business name:

	Yes	No
Has the BAL been calculated by a method other than method 1 as outlined in AS3959 (tick no if AS3959 method 1 has been used to calculate the BAL)?		
Have any of the bushfire protection criteria elements been addressed through the use of a performance principle (tick no if only acceptable solutions have been used to address all of the bushfire protection criteria elements)?		

Is the proposal any of the following (see SPP 3.7 for definitions)?	Yes	No
Unavoidable development (in BAL-40 or BAL-FZ)		
Strategic planning proposal (including rezoning applications)		
High risk land-use		
Vulnerable land-use		

None of the above

Note: Only if one (or more) of the above answers in the tables is yes should the decision maker (e.g. local government or the WAPC) refer the proposal to DFES for comment.

Why has it been given one of the above listed classifications (E.g. Considered vulnerable land-use as the development is for accommodation of the elderly, etc.)?

The information provided within this bushfire management plan to the best of my knowledge is true and correct:

Signature of report author or reviewer



Date



Dan Murphy's and Tavern

Bushfire Management Plan (BMP)



Lot 395 (1) Peony Boulevard, Yanchep

City of Wanneroo

Development Application

25 August 2023

Job Reference No:
230509

BPP GROUP PTY LTD T/A BUSHFIRE PRONE PLANNING

ACN: 39 166 551 784 | ABN: 39 166 551 784

**LEVEL 1, 159-161 JAMES STREET
GUILDFORD WA 6055****PO BOX 388
GUILDFORD WA 6935****08 6477 1144 | admin@bushfireprone.com.au****DOCUMENT CONTROL**

PREPARATION					
Author:	Kathy Nastov (BPAD Level 3 No. 27794)				
Co-Author:	Kyle Calder-Bryan				
VERSION HISTORY					
Version	Status/Details			Date	
1.0	Original			25 August 2023	
1.0	Updated site plans			21 September 2023	
BMP (Master) Template v9.15					
DISTRIBUTION					
Destination		Version	No. Copies	Hard Copy	Electronic Copy
Person	Email				
		1.0		<input type="checkbox"/>	<input checked="" type="checkbox"/>
Adrian Morabito	ADRIAN.MORABITO@FRPCAPITAL.COM.AU	1.1-		<input type="checkbox"/>	<input type="checkbox"/>
<p>Limitations: The protection measures that will be implemented based on information presented in this Bushfire Management Plan are minimum requirements and they do not guarantee that buildings or infrastructure will not be damaged in a bushfire, persons injured, or fatalities occur either on the subject site or off the site while evacuating.</p> <p>This is substantially due to the unpredictable nature and behaviour of fire and fire weather conditions. Additionally, the correct implementation of the required protection measures (including bushfire resistant construction) and any other required or recommended measures, will depend upon, among other things, the ongoing actions of the landowners and/or operators over which Bushfire Prone Planning has no control.</p> <p>All surveys, forecasts, projections and recommendations made in this report associated with the proposed development are made in good faith based on information available to Bushfire Prone Planning at the time. All maps included herein are indicative in nature and are not to be used for accurate calculations.</p> <p>Notwithstanding anything contained therein, Bushfire Prone Planning will not, except as the law may require, be liable for any loss or other consequences whether or not due to the negligence of their consultants, their servants or agents, arising out of the services provided by their consultants.</p> <p>Copyright © 2022 BPP Group Pty Ltd: All intellectual property rights, including copyright, in format and proprietary content contained in documents created by Bushfire Prone Planning, remain the property of BPP Group Pty Ltd. Any use made of such format or content without the prior written approval of Bushfire Prone Planning, will constitute an infringement on the rights of the Company which reserves all legal rights and remedies in respect of any such infringement.</p>					

TABLE OF CONTENTS

SUMMARY STATEMENTS.....	3
1 PROPOSAL DETAILS AND THE BUSHFIRE MANAGEMENT PLAN.....	5
1.1 THE PROPOSED DEVELOPMENT/USE DETAILS, PLANS AND MAPS	5
1.2 THE BUSHFIRE MANAGEMENT PLAN (BMP).....	12
1.2.1 COMMISSIONING AND PURPOSE.....	12
1.2.1 OTHER DOCUMENTS WITH IMPLICATIONS FOR DEVELOPMENT OF THIS BMP.....	12
2 BUSHFIRE PRONE VEGETATION – ENVIRONMENTAL & ASSESSMENT CONSIDERATIONS	13
2.1 ENVIRONMENTAL CONSIDERATIONS – ‘DESKTOP’ ASSESSMENT	13
2.1.1 DECLARED ENVIRONMENTALLY SENSITIVE AREAS (ESA)	15
2.1.2 OTHER PROTECTED VEGETATION ON PUBLIC LAND	16
2.1.3 LOCALLY SIGNIFICANT CONSERVATION AREAS – LOCAL NATURAL AREAS (LNA)	16
2.1.4 RESPONSE OF PROPOSED DEVELOPMENT TO IDENTIFIED ENVIRONMENTAL LIMITATIONS.....	17
2.2 BUSHFIRE ASSESSMENT CONSIDERATIONS.....	18
2.2.1 PLANNED ONSITE VEGETATION LANDSCAPING	18
2.2.2 PLANNED / POTENTIAL OFFSITE REHABILITATION OR RE-VEGETATION	18
2.2.3 IDENTIFIED REQUIREMENT TO MANAGE, MODIFY OR REMOVE ONSITE OR OFFSITE VEGETATION	18
2.2.4 VARIATIONS TO ASSESSED AREAS OF CLASSIFIED VEGETATION TO BE APPLIED	19
3 BUSHFIRE ATTACK LEVEL (BAL) ASSESSMENT	20
3.1 BAL ASSESSMENT SUMMARY (CONTOUR MAP FORMAT)	21
3.1.1 BAL DETERMINATION METHODOLOGY AND LOCATION OF DATA AND RESULTS.....	21
3.1.2 BAL RATINGS DERIVED FROM THE CONTOUR MAP.....	22
3.1.3 SITE ASSESSMENT DATA APPLIED TO CONSTRUCTION OF THE BAL CONTOUR MAP(S).....	23
3.1.4 CLASSIFIED VEGETATION AND TOPOGRAPHY MAP(S)	26
3.1.5 BAL CONTOUR MAP(S).....	27
4 IDENTIFICATION OF BUSHFIRE HAZARD ISSUES	28
5 ASSESSMENT AGAINST THE BUSHFIRE PROTECTION CRITERIA (GUIDELINES V1.4).....	29
5.1 BUSHFIRE PROTECTION CRITERIA ELEMENTS APPLICABLE TO THE PROPOSED DEVELOPMENT/USE	29
5.2 LOCAL GOVERNMENT VARIATIONS TO APPLY.....	29
5.3 ASSESSMENT STATEMENTS FOR ELEMENT 1: LOCATION.....	30
5.4 ASSESSMENT STATEMENTS FOR ELEMENT 2: SITING AND DESIGN.....	31
5.5 ASSESSMENT STATEMENTS FOR ELEMENT 3: VEHICULAR ACCESS.....	34
5.6 ASSESSMENT STATEMENTS FOR ELEMENT 4: WATER	38
6.1 DEVELOPER / LANDOWNER RESPONSIBILITIES – PRIOR TO OPERATION.....	40

6.2	LANDOWNER / OCCUPIER RESPONSIBILITIES – ONGOING MANAGEMENT	41
6.3	LOCAL GOVERNMENT RESPONSIBILITIES – ONGOING MANAGEMENT	42
APPENDIX A: DETAILED BAL ASSESSMENT DATA AND SUPPORTING INFORMATION		43
A1:	BAL ASSESSMENT INPUTS COMMON TO THE METHOD 1 AND METHOD 2 PROCEDURES	43
A1.1:	FIRE DANGER INDICES (FDI/FDI/GFDI)	43
A1.2:	VEGETATION ASSESSMENT AND CLASSIFICATION	43
A1.3:	EFFECTIVE SLOPE.....	49
A1.4:	SEPARATION DISTANCE.....	50
APPENDIX B: ADVICE - ONSITE VEGETATION MANAGEMENT - THE APZ		51
B1:	ASSET PROTECTION ZONE (APZ) DIMENSIONS	51
B1.1:	THE APZ DIMENSIONS REQUIRED TO BE IMPLEMENTED BY THE LANDOWNER	53
B2:	THE STANDARDS FOR THE APZ AS ESTABLISHED BY THE GUIDELINES (DPLH, V1.4).....	55
B3:	THE STANDARDS FOR THE APZ AS ESTABLISHED BY THE LOCAL GOVERNMENT	56
B4:	VEGETATION AND AREAS EXCLUDED FROM CLASSIFICATION - ENSURE CONTINUED EXCLUSION.....	57
APPENDIX C: TECHNICAL REQUIREMENTS FOR VEHICULAR ACCESS.....		58
APPENDIX D: TECHNICAL REQUIREMENTS FOR FIREFIGHTING WATER SUPPLY.....		59
D1:	RETICULATED AREAS – HYDRANT SUPPLY	59

LIST OF FIGURES

Figure 1.1:	Proposed development plan - BWS.....	6
Figure 1.1.1:	Proposed development plan - Tavern.....	7
Figure 1.2:	Proposed development map.....	8
Figure 1.3:	Location map (spatial context).....	9
Figure 1.4:	Extract from Map of Bushfire Prone Areas (Office of Bushfire Risk Management, DFES)	11
Figure 2.1:	Land identified with known environmental, biodiversity and conservation values.....	14
Figure 3.1:	Classified vegetation and topography map.....	26
Figure 3.2:	BAL Contour Map.....	27

SUMMARY STATEMENTS

THIS DOCUMENT – STATEMENT OF PURPOSE

The Bushfire Management Plan (BMP)

The BMP sets out the required package of bushfire protection measures to lessen the risks associated with a bushfire event. It establishes the responsibilities to implement and maintain these measures.

The BMP also identifies the potential for any negative impact on any environmental, biodiversity and conservation values that may result from the application of bushfire protection measures or that may limit their implementation.

Risks Associated with Bushfire Events

The relevant risks are the potential for loss of life, injury, or destroyed or damaged assets which results in personal loss and economic loss. For a given site, the level of that risk to persons and assets (the exposed elements) is a function of the potential threat levels generated by the bushfire hazard, and the level of exposure and vulnerability of the at risk elements to the threats.

Bushfire Protection Measures

The required package of protection measures is established by *State Planning Policy 3.7 Planning in Bushfire Prone Areas (SPP 3.7)*, its associated *Guidelines* and any other relevant guidelines or position statements published by the Department of Planning, Lands and Heritage. These measures are limited to those considered by the WA planning authorities as necessary to be addressed for the purpose of land use planning. They do not encompass all available bushfire protection measures as many are not directly relevant to the planning approval stage. For example:

- Protection measures to reduce the vulnerability of buildings to bushfire threats is primarily dealt with at the building application stage. They are implemented through the process of applying the Building Code of Australia (Volumes 1 and 2 of the national Construction Code) in accordance with WA building legislation and the application of construction requirements based on a building's level of exposure - determined as a Bushfire Attack Level (BAL) rating); or
- Protection measures to reduce the threat levels of consequential fire (ignited by bushfire and involving combustible materials surrounding and within buildings) and measures to reduce the exposure and vulnerability of elements at risk exposed to consequential fire, are not specifically considered.

The package of required bushfire protection measures established by the Guidelines includes:

- The requirements of the bushfire protection criteria which consist of:
 - Element 1: Location (addresses threat levels).
 - Element 2: Siting and Design of Development (addresses exposure levels of buildings).
 - Element 3: Vehicular Access (addresses exposure and vulnerability levels of persons).
 - Element 4: Water (addresses vulnerability levels of buildings).
 - Element 5: Vulnerable Tourism Land Uses (addresses exposure and vulnerability as per Elements 1-4 but in use specific ways and with additional considerations of persons exposure and vulnerability).
- The requirement to develop Bushfire Emergency Plans / Information for 'vulnerable' land uses for persons to prepare, respond and recover from a bushfire event (this addresses vulnerability levels).
- The requirement to assess bushfire risk and incorporate relevant protection measures into the site emergency plans for 'high risk' land uses (this addresses threat, exposure and vulnerability levels).

Compliance of the Proposed Development or Use with SPP 3.7 Requirements

The BMP assesses the capacity of the proposed development or use to implement and maintain the required 'acceptable' solutions and any additionally recommended bushfire protection measures - or its capacity to satisfy the policy intent through the justified application of additional bushfire protection measures as supportable 'alternative' solutions.

THE PROPOSED DEVELOPMENT/USE – BUSHFIRE PLANNING COMPLIANCE SUMMARY		
Environmental Considerations		Assessment Outcome
Will land with identified environmental, biodiversity and conservation values limit the full application of the required bushfire protection measures?		No
Will land with identified environmental, biodiversity and conservation values need to be managed in the implementation and maintenance of the bushfire protection measures - but not limit their application?		No
Required Bushfire Protection Measures The Acceptable Solutions of the Bushfire Protection Criteria (Guidelines)		Assessment Outcome
Element	The Acceptable Solutions	
1: Location	A1.1 Development location	Fully Compliant
2: Siting and Design of Development	A2.1 Asset Protection Zone (APZ)	Fully Compliant
3: Vehicular Access	A3.1 Public roads	Fully Compliant
	A3.2a Multiple access routes	Fully Compliant
	A3.2b Emergency access way	N/A
	A3.3 Through-roads	N/A
	A3.4a Perimeter roads	N/A
	A3.4b Fire service access route	N/A
	A3.5 Battle-axe legs	N/A
	A3.6 Private driveways	Fully Compliant
4: Water	A4.1 Identification of future water supply	N/A
	A4.2 Provision of water for firefighting purposes	Fully Compliant

1 PROPOSAL DETAILS AND THE BUSHFIRE MANAGEMENT PLAN

1.1 The Proposed Development/Use Details, Plans and Maps


The Proposal's Planning Stage For which certain bushfire planning documents are required to accompany the planning application.		Development Application	
The Subject Land/Site		1 Peony Boulevard, Yanchep	
Total Area of Subject Lot/Site		2.6485 hectares	
Number of Additional Lots Created		N/A	
Primary Proposed Construction	Type(s)	Addition(s) to existing building(s)	New Building(s)
	NCC Classification	Class 6 (building for sale of retail goods or supply of services)	Class 6 (building for sale of retail goods or supply of services)
Description of the Proposed Development/Use			
<p>The development includes a new Dan Murphy's as well as a new building that will become a tavern.</p>			



Figure 1.2
Proposed Development

Lot 395 on Plan 062808, Area : 4.6485 ha
 1 Peony Boulevard,
 YANCHEP 6035
CITY OF WANNEROO

- **LEGEND** -----
- Subject Site
 - Other Lots
 - H Hydrant
- Proposed Building**
- New Dan Murphy's
 - Proposed Tavern



----- **LOCALITY** -----



Aerial Imagery : Landgate/SLIP
 Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
 Projection: Universal Transverse Mercator Units: Metre
 Map compiled by: Ian Ross 21/09/2023
 Map updated by: Ian Ross 21/09/2023
 A3 Scale 1:1,500








Figure 1.3
Location Plan

Lot 395 on Plan 062808, Area : 4.6485 ha
1 Peony Boulevard,
YANCHEP 6035
CITY OF WANNEROO

- **LEGEND** -----
- Subject Site
 - Local Government Authority
 - Locality / Suburb
 - Volunteer Fire & Rescue Service
- Reserves**
- Reserves
- Legislated Lands and Waters**
- National Park
 - Section 5(1)(h) Reserve
 - Bush Forever



Aerial Imagery : Landgate/SLIP
Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
Projection: Universal Transverse Mercator Units: Metre
Map compiled by: Ian Ross 21/09/2023
Map updated by: Ian Ross 21/09/2023
A3 Scale 1:25,000

WHERE SPP 3.7 AND THE GUIDELINES ARE TO APPLY – DESIGNATED BUSHFIRE PRONE AREAS

All higher order strategic planning documents, strategic planning proposals, subdivisions and development applications located in designated bushfire prone areas need to address SPP 3.7 and its supporting Guidelines. This also applies where an area is not yet designated as bushfire prone but is proposed to be developed in a way that introduces a bushfire hazard.

For development applications where only part of a lot is designated as bushfire prone and the proposed development footprint is wholly outside of the designated area, the development application will not need to address SPP 3.7 or the Guidelines. (Guidelines DPLH 2021 v1.4, s1.2).

For subdivision applications, if all the proposed lots have a BAL-LOW indicated, a BMP is not required. (Guidelines DPLH 2021 v1.4, s5.3.1).


Figure 1.4
Bushfire Prone Area

Lot 395 on Plan 062808, Area : 4.6485 ha
 1 Peony Boulevard,
 YANCHEP 6035
CITY OF WANNEROO



----- LEGEND -----

- Subject Site
- Other Lots
- Volunteer Fire & Rescue Service
- H Hydrant
- Proposed Building**
- New Dan Murphy's
- Proposed Tavern
- Bush Fire Prone Areas**
- Bushfire Prone Areas (2021)



----- LOCALITY -----



Aerial Imagery : Landgate/SLIP
 Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
 Projection: Universal Transverse Mercator Units: Metre
 Map compiled by: Ian Ross 21/09/2023
 Map updated by: Ian Ross 21/09/2023
 A3 Scale 1:5,000

Disclaimer and Limitation: This map has been prepared for bushfire management planning purposes only. All depicted areas, contours and any dimensions shown are subject to survey. Bushfire Prone Planning does not guarantee that this map is without flaw of any kind and disclaims all liability for any errors, loss or other consequence arising from relying on any information depicted.
 Map Document Path / Name: K:\Projects\Jobs 2023\230509 - Yanchep 3 x DA's (BMP x 3 sites)\230509 - Dan Murphy & Tavern combined\Mapping\MXD\230509_Fig1-4_BPA_Dan Murphy - Tavern.mxd

1.2 The Bushfire Management Plan (BMP)

1.2.1 Commissioning and Purpose

Landowner / proponent:	FRP Capital
Bushfire Prone Planning commissioned to produce the BMP by:	Adrian Morabito
Purpose of the BMP:	To assess the proposal's ability to meet all relevant requirements established by State Planning Policy 3.7: Planning in Bushfire Prone Areas (SPP 3.7), the associated 'Guidelines and any relevant Position Statements; and To satisfy the requirement for the provision of a Bushfire Management Plan to accompany the development application.
BMP to be submitted to:	WA Planning Commission (WAPC) and City of Wanneroo

1.2.1 Other Documents with Implications for Development of this BMP

This section identifies any known assessments, reports or plans that have been conducted and prepared previously, or are being prepared concurrently, and are relevant to the planned proposal for the subject. They potentially have implications for the assessment of bushfire threats and the identification and implementation of the protection measures that are established by this Bushfire Management Plan.

Table 1.4: Other relevant documents that may influence threat assessments and development of protection measures.

RELEVANT DOCUMENTS					
Document	Relevant	Currently Exists	To Be Developed	Copy Provided by Proponent / Developer	Title
Structure Plan	No	No	No	No	-
Bushfire Management Plan	No	No	No	No	-
Bushfire Emergency Plan or Information	No	No	No	No	-
Bushfire Risk Assessment and Management Report	No	No	No	No	-
Environmental Asset or Vegetation Survey	No	No	No	No	-
Landscaping and Revegetation Plan	No	No	No	No	-
Land Management Agreement	No	No	No	No	-

2 BUSHFIRE PRONE VEGETATION – ENVIRONMENTAL & ASSESSMENT CONSIDERATIONS

2.1 Environmental Considerations – ‘Desktop’ Assessment

This ‘desktop’ assessment must not be considered as a replacement for a full Environmental Impact Assessment. It is a summary of potential environmental values at the subject site, inferred from information contained in listed datasets and/or reports, which are only current to the date of last modification.

These data sources must be considered indicative where the subject site has not previously received a site-specific environmental assessment by an appropriate professional.

Many bushfire prone areas also have high biodiversity values. Consideration of environmental priorities within the boundaries of the land being developed can avoid excessive or unnecessary modification or clearing of vegetation. Approval processes (and exemptions) apply at both Commonwealth and State levels.

Any ‘modification’ or ‘clearing’ of vegetation to reduce bushfire risk is considered ‘clearing’ under the **Environmental Protection Act 1986** (EP Act) and requires a clearing permit under the **Environmental Protection (Clearing of Native Vegetation) Regulations 2004** (Clearing Regulations) – unless for an exempt purpose.

Clearing native vegetation is an offence, unless done under a clearing permit or the clearing is for an exempt purpose. Exemptions are contained in the EP Act or are prescribed in the Clearing Regulations (note: these do not apply in environmentally sensitive areas).

The **Department of Water and Environmental Regulation** (DWER) is responsible for issuing ‘clearing’ permits and the framework for the regulation of clearing. Approvals under other legislation, from other agencies, may also be required, dependent on the type of flora or fauna present.

Local Planning Policy or Local Biodiversity Strategy: Natural areas that are not protected by the above Act and Regulation (or any other National or State Acts) may be protected by a local planning policy or local biodiversity strategy. Permission from the local government will be required for any modification or removal of native vegetation in these Local Natural Areas (LNA's). Refer to the relevant local government for detail.



For further Information refer to Guidelines v1.4, the Bushfire and Vegetation Factsheet - WAPC, Dec 2021 and <https://www.der.wa.gov.au/our-work/clearing-permits>

Figure 2.1
Environmental Considerations

Lot 395 on Plan 062808, Area : 4.6485 ha
 1 Peony Boulevard,
 YANCHEP 6035
CITY OF WANNEROO



- **LEGEND** -----
- Subject Site
 - Volunteer Fire & Rescue Service
 - H Hydrant
 - Proposed Building**
 - New Dan Murphy's
 - Proposed Tavern
 - Reserves**
 - Reserves
 - Bush Forever
 - Clearing Regulations



Aerial Imagery : Landgate/SLIP
 Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
 Projection: Universal Transverse Mercator Units: Metre
 Map compiled by: Ian Ross 21/09/2023
 Map updated by: Ian Ross 21/09/2023
 A3 Scale 1:5,000

Disclaimer and Limitation: This map has been prepared for bushfire management planning purposes only. All depicted areas, contours and any dimensions shown are subject to survey. Bushfire Prone Planning does not guarantee that this map is without flaw of any kind and disclaims all liability for any errors, loss or other consequence arising from relying on any information depicted.
 Map Document Path / Name: K:\Projects\Jobs 2023\230509 - Yanchep 3 x DA's (BMP x 3 sites)\230509 - Dan Murphy & Tavern combined\Mapping\MXD\230509_Fig2-1_ENV_Dan Murphy - Tavern.mxd

2.1.1 Declared Environmentally Sensitive Areas (ESA)

IDENTIFICATION OF RELEVANT ENVIRONMENTALLY SENSITIVE AREAS							
ESA Class	Relevant to Proposal	Influence on Bushfire Threat Levels and / or Application of Bushfire Protection Measures	Relevant Dataset	Information Source(s) Applied to Identification of Relevant Vegetation			Further Action Required
				Dataset	Landowner or Developer	Environmental Asset or Vegetation Survey	
Wetlands and their 50m Buffer (Ramsar, conservation category and nationally important)	No	No	DBCA-010 and 011, 019, 040, 043, 044	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None
Bush Forever	No	No	DPLH-022, SPP 2.8	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None
Threatened and Priority Flora + 50m Continuous Buffer	No	No	DBCA-036	Restricted Scale of Data Available (security)	<input type="checkbox"/>	<input type="checkbox"/>	Data not available - confirm with relevant agency
Threatened Ecological Community	No	No	DBCA-038		<input type="checkbox"/>	<input type="checkbox"/>	Data not available - confirm with relevant agency
Heritage Areas National / World	No	No	Relevant register or mapping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None
Environmental Protection (Western Swamp Tortoise) Policy 2002	No	No	DWER-062	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None

DESCRIPTION OF THE IDENTIFIED ENVIRONMENTALLY SENSITIVE AREAS:

The subject site contains data for clearing regulations. The remaining data sets are outside of the subject site, therefore will not impact the proposed developments.

2.1.2 Other Protected Vegetation on Public Land

IDENTIFICATION OF PROTECTED VEGETATION ON PUBLIC LAND							
Land with Environmental, Biodiversity, Conservation and Social Values	Relevant to Proposal	Influence on Bushfire Threat Levels and / or Application of Bushfire Protection Measures	Relevant Dataset	Information Source(s) Applied to Identification of Relevant Vegetation			Further Action Required
				Dataset	Landowner or Developer	Environmental Asset or Vegetation Survey	
Legislated Lands (tenure includes national park/reserve, conservation park, crown reserve and state forest)	No	No	DBCA-011	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None
Conservation Covenants	No	No	DPIRD-023	Only Available to Govt.	<input type="checkbox"/>	<input type="checkbox"/>	Data not available - confirm with relevant agency
National World Heritage Areas	No	No	-	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None
Designated Public Open Space	No	No	-	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	None

DESCRIPTION OF THE IDENTIFIED AREA(S) OF VEGETATION

None required.

2.1.3 Locally Significant Conservation Areas – Local Natural Areas (LNA)

IDENTIFICATION OF LOCALLY SIGNIFICANT CONSERVATION AREAS							
Land with Environmental, Biodiversity and Conservation Values	Relevant to Proposal	Influence on Bushfire Threat Levels and / or Application of Bushfire Protection Measures	Relevant Dataset	Information Source(s) Applied to Identification of Relevant Vegetation			Further Action Required
				Dataset	Landowner or Developer	Environmental Asset or Vegetation Survey	
Native Vegetation / Remnant Vegetation	No	No	Local Government Intramaps	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Confirm with relevant agency
Riparian Zones / Foreshore Areas	No	No		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Confirm with relevant agency
Habitat Vegetation and Wildlife Corridors	No	No		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Confirm with relevant agency

DESCRIPTION OF THE IDENTIFIED AREA(S) OF VEGETATION

Vegetation areas have been checked against the City of Wanneroo Intramaps, no vegetation has been identified as significant, however, it is possible that the local government may have data sets that identify vegetation within the assessment area as significant.

2.1.4 Response of Proposed Development to Identified Environmental Limitations

Consideration of the implications that identified protected areas of vegetation (i.e., those with environmental and subject to conservation) have for the proposed development.

PROPOSED DEVELOPMENT RESPONSE TO IDENTIFIED 'PROTECTED' VEGETATION	
The existence of 'protected' areas of vegetation has implications for the ability of the proposed development to reduce potential bushfire impact through modification or removal of vegetation.	No
Application of Design and/or Construction Responses to Limit Vegetation Modification or Removal	
Modify the development location to reduce exposure by increasing separation distance.	No
Redesign development, structure plan or subdivision.	N/A
Reduction of lot yield where this can increase available separation distances.	N/A
Cluster development to limit modification or removal of vegetation.	N/A
Construct building(s) to the requirements corresponding to higher BAL ratings to reduce required separation distances.	No
Buildings will be placed in area where a BAL-29 can be achieved and buildings will therefore be built to this rating.	

2.2 Bushfire Assessment Considerations

2.2.1 Planned Onsite Vegetation Landscaping

Identification of areas of the subject site planned to be landscaped, creating the potential for increased or decreased bushfire hazard for proposed development.

PLANNED LANDSCAPING	
Relevant to Proposal:	No
N/A.	

2.2.2 Planned / Potential Offsite Rehabilitation or Re-Vegetation

Identification of areas of land adjacent to the subject site on which re-vegetation (as distinct from natural re-generation) will or may occur and is likely to present a greater bushfire hazard for proposed development.

POTENTIAL RE-VEGETATION PROGRAMS		
Land with Environmental, Biodiversity, Conservation and Social Values	Relevant to Proposal	Description
Riparian Zones / Foreshore Areas	No	N/A.
Wetland Buffers	No	N/A.
Legislated Lands	No	N/A.
Public Open Space	No	N/A.
Road Verges	No	N/A.
Other	No	N/A.

2.2.3 Identified Requirement to Manage, Modify or Remove Onsite or Offsite Vegetation

Identification of native vegetation subject to management, modification or removal.

REQUIREMENT TO MANAGE, MODIFY OR REMOVE NATIVE VEGETATION	
Has a requirement been identified to manage, modify or remove onsite native vegetation to establish the required bushfire protection measures on the subject site?	No
Is approval, from relevant state government agencies and/or the local government, to modify or remove onsite native vegetation required? (Note: if 'Yes' evidence of its existence should be provided in this BMP).	No
Has a requirement been identified to manage, modify or remove offsite native vegetation to establish the required bushfire protection measures on the subject site?	No
There is no requirement for management of any offsite vegetation to allow for a BAL-29 to be achieved.	
Is written approval required, from relevant state government agencies and/or the local government, that permits the landowner, or another identified party, to modify or remove offsite	N/A

<p>bushfire prone vegetation and/or conduct other works, to establish an identified bushfire protection measure(s)?</p> <p>If 'Yes', appropriate evidence of the approval or how it is to be established, shall be provided in this BMP as an addendum.</p>	
<p>There is no requirement for management of any offsite vegetation to allow for a BAL-29 to be achieved.</p>	
<p>Is a written management agreement required that states the obligation of the landowner, or another responsible party, to manage defined areas of offsite bushfire prone vegetation, in perpetuity, to ensure the conditions of no fire fuels and/or low threat vegetation and/or vegetation managed in a minimal fuel condition, continue to be met?</p> <p>If 'Yes', appropriate evidence of the agreement or how it is to be established, shall be provided in this BMP as an addendum.</p>	No
<p>There is no requirement for management of any offsite vegetation to allow for a BAL-29 to be achieved.</p>	

2.2.4 Variations to Assessed Areas of Classified Vegetation to be Applied

FOR THE PROPOSED DEVELOPMENT SITUATIONS TO BE ACCOUNTED FOR IN ASSESSING THE POTENTIAL BUSHFIRE IMPACT (BAL)	
<p>Area(s) of land will be subject to future vegetation rehabilitation or re-vegetation that will require a change to a higher threat classification of vegetation on that land to. (Note: this is not regeneration to the mature natural state which is accounted for in the 'existing state' assessment in accordance with AS 3959:2018).</p>	No
<p>Modification of existing area(s) of classified vegetation due to the implementation of the proposed development and/or prior to the site's occupancy or use. This modification will require a change to a lower threat classification (or exclusion from classification) for that area of vegetation.</p>	No
<p>Complete removal of existing area(s) of classified vegetation due to the implementation of the proposed development and/or prior to the site's occupancy or use. This modification will require an exclusion from classification for that area of vegetation.</p>	No

3 BUSHFIRE ATTACK LEVEL (BAL) ASSESSMENT

BUSHFIRE ATTACK LEVELS (BAL) - UNDERSTANDING THE RESULTS

The potential transfer (flux/flow) of radiant heat from the bushfire to a receiving object is measured in kW/m². The AS 3959:2018 BAL determination methodology establishes the ranges of radiant heat flux that correspond to each bushfire attack level. These are identified as BAL-LOW, BAL-12.5, BAL-19, BAL-29, BAL-40 and BAL-FZ.

The bushfire performance requirements for certain classes of buildings are established by the Building Code of Australia (Vol. 1 & 2 of the NCC). The BAL will establish the bushfire resistant construction requirements that are to apply in accordance with AS 3959:2018 - *Construction of buildings in bushfire prone areas* and the NASH Standard – *Steel framed construction in bushfire areas (NS 300 2021)*, whose solutions are deemed to satisfy the NCC bushfire performance requirements.

DETERMINED BAL RATINGS

A BAL Certificate can be issued for a determined BAL. A BAL can only be classed as 'determined' for an existing or future building/structure when:

1. It's final design and position on the lot are known and the stated separation distance from classified bushfire prone vegetation exists and can justifiably be expected to remain in perpetuity; or
2. It will always remain subject to the same BAL regardless of its design or position on the lot after accounting for any regulatory or enforceable building setbacks from lot boundaries as relevant and necessary (e.g., R-codes, restrictive covenants, defined building envelopes) or the retention of any existing classified vegetation either onsite or offsite.

If the BMP derives determined BAL(s), the BAL Certificate(s) required for submission with building applications can be provided, using the BMP as the assessment evidence.

INDICATIVE BAL RATINGS

A BAL Certificate cannot be issued for an indicative BAL. A BAL will be classed as 'indicative' for an existing or future building/structure when the required conditions to derive a determined BAL are not met.

This class of BAL rating indicates what BAL(s) could be achieved and the conditions that need to be met are stated.

Converting the indicative BAL into a determined BAL is conditional upon the currently unconfirmed variable(s) being confirmed by a subsequent assessment and evidential documentation. These variables will include the future building(s) location(s) being established (or changed) and/or classified vegetation being modified or removed to establish the necessary vegetation separation distance. This may also be dependent on receiving approval from the relevant authority for that modification/removal.

BAL RATING APPLICATION – PLANNING APPROVAL VERSUS BUILDING APPROVAL

1. **Planning Approval:** SPP.3.7 establishes that where BAL- LOW to BAL-29 will apply to relevant future construction (or existing structures for proposed uses), the proposed development may be considered for approval (dependent on the other requirements of the relevant policy measures being met). That is, BAL40 or BAL-FZ are not acceptable on planning grounds (except for certain limited exceptions).

Because planning is looking forward at what can be achieved, as well as looking at what may currently exist, both determined and indicative BAL ratings are acceptable assessment outcomes on which planning decisions can be made (including conditional approvals).

2. **Building Approval:** The Building Code of Australia (Vol. 1 & 2 of the NCC) establishes that relevant buildings in bushfire prone areas must be constructed to the bushfire resistant requirements corresponding to the BAL rating that is to apply to that building. Consequently, a determined BAL rating and the BAL Certificate is required for a building permit to be issued - an indicative BAL rating is not acceptable.

3.1 BAL Assessment Summary (Contour Map Format)

INTERPRETATION OF THE BAL CONTOUR MAP

The BAL contour map is a diagrammatic representation of the results of the bushfire attack level assessment.

The map presents different coloured contours extending out from the areas of classified vegetation. Each contour represents a set range of radiant heat flux that potentially will transfer to an exposed element (building, person or other defined element), when it is located within that contour.

Each of the set ranges of radiant heat flux corresponds to a different BAL rating as defined by the AS 3959:2018 BAL determination methodology.

The width of each shaded BAL contour will vary dependant on both the BAL rating and the relevant parameters (calculation inputs) for the subject site. Their width represents the minimum and maximum vegetation separation distances that correspond to each BAL rating (refer to the relevant table below for these distances).

The areas of classified vegetation to be considered in developing the BAL contours, are those that will remain at the intended end state of the subject development once earthworks, clearing and/or landscaping and re-vegetation have been completed. Variations to this statement that may apply include:

- Both pre and post development BAL contour maps are produced; and/or
- Each stage of a development is assessed independently.

3.1.1 BAL Determination Methodology and Location of Data and Results

LOCATION OF DATA & RESULTS					
BAL Determination Methodology		Location of the Site Assessment Data			Location of the Results
AS 3959:2018	Applied to Assessment	Classified Vegetation and Topography Map(s)	Calculation Input Variables		Assessed Bushfire Attack Levels and/or Radiant Heat Levels
			Summary Data	Detailed Data with Explanatory and Supporting Information	
Method 1 (Simplified)	Yes	Figure 3.1	Table 3.2	Appendix A1	Table 3.3 / BAL Contour Map
Method 2 (Detailed)	No	N/A	N/A	N/A	

3.1.2 BAL Ratings Derived from the Contour Map

Table 3.1: Indicative and determined BAL(s) for existing and/or proposed building works.

BUSHFIRE ATTACK LEVEL FOR EXISTING/PLANNED BUILDINGS/STRUCTURE ¹		
Building/Structure Description	Indicative BAL ²	Determined BAL ²
New Dan Murphy's	N/A	BAL-12.5
Proposed Tavern	N/A	BAL-12.5

¹ The assessment data used to derive the BAL ratings is sourced from Table 3.1 and Figure 3.2 'BAL Contour Map'.

² Refer to the start of Section 3 for an explanation of indicative versus determined BAL ratings.

3.1.3 Site Assessment Data Applied to Construction of the BAL Contour Map(s)

RELEVANT CLASSIFIED VEGETATION	
Identification of Classified Vegetation that is Relevant to the Production of the BAL Contour Map(s)	Relevant Vegetation Map
The relevant vegetation will be all areas of classified vegetation that exist at the time of the site assessment – both within the subject site (onsite) and external to the subject site (offsite).	Figure No.3.1
Supporting Assessment Details: There is no requirement to manage onsite vegetation to achieve a BAL-29 or lower for either the proposed Dan Murphy's or for the proposed tavern.	

Table 3.2: The calculation inputs applied to determining the site specific separation distances corresponding to levels of potential radiant heat transfer (including BAL's).

SUMMARY OF CALCULATION INPUT VARIABLES APPLIED TO THE DETERMINATION OF SEPARATION DISTANCES CORRESPONDING TO RADIANT HEAT LEVELS ¹												
Applied BAL Determination Method		METHOD 1 - SIMPLIFIED PROCEDURE (AS 3959:2018 CLAUSE 2.2)										
The Calculation Variables Corresponding to the BAL Determination Method Applied												
Methods 1 and 2		Method 1			Method 2							
Vegetation Classification		FDI	Effective Slope		Site Slope	FFDI or GFDI	Flame Temp.	Elevation of Receiver	Flame Width	Fireline Intensity	Flame Length	Modified View Factor
Area	Class		Applied Range	Measured								
1	(D) Scrub	80	Upslope or flat 0	flat 0	flat 0	-	-	-	-	-	-	-
2	(B) Woodland	80	Upslope or flat 0	flat 0	flat 0	-	-	-	-	-	-	-
3	(G) Grassland	80	Upslope or flat 0	flat 0	flat 0	-	-	-	-	-	-	-
4	(A) Forest	80	Upslope or flat 0	flat 0	flat 0	-	-	-	-	-	-	-
5	(C) Shrubland	80	Upslope or flat 0	flat 0	flat 0	-	-	-	-	-	-	-
6	Excluded cl 2.2.3.2(e & f)	N/A	N/A	N/A	N/A	-	-	-	-	-	-	-

¹ All data and information supporting the determination of the classifications and values stated in this table and any associated justification, is presented in Appendix A. Where the values are stated as 'default' these are either the values stated in AS 3959:2018, Table B1 or the values calculated as intermediate or final outputs through application of the equations of the AS 3959:2018 BAL determination methodology. They are not values derived by the assessor.

Table 3.3: Vegetation separation distances corresponding to the radiant heat levels illustrated as BAL contours in Figure 3.2.


THE CALCULATED VEGETATION SEPARATION DISTANCES CORRESPONDING TO THE STATED LEVEL OF RADIANT HEAT ¹									
Vegetation Classification		Separation Distances Corresponding to Stated Level of Radiant Heat (metres)							
		Bushfire Attack Level						Maximum Radiant Heat Flux	
Area	Class	BAL-FZ	BAL-40	BAL-29	BAL-19	BAL12.5	BAL-LOW	10 kW/m ²	2 kW/m ²
1	(D) Scrub	<10	10-<13	13-<19	19-<27	27-<100	>100	-	-
2	(B) Woodland	<10	10-<14	14-<20	20-<29	29-<100	>100	-	-
3	(G) Grassland	<6	6-<8	8-<12	12-<17	17-<100	>100	-	-
4	(A) Forest	<16	16-<21	21-<31	31-<42	42-<100	>100	-	-
5	(C) Shrubland	<7	7-<9	9-<13	13-<19	19-<100	>100	-	-
6	Excluded cl 2.2.3.2(e & f)	-	-	-	-	-	-	-	-

¹ All calculation input variables are presented in Table 3.2. A copy of radiant heat calculator output for each area of classified vegetation are presented in Appendix A3.

Figure 3.1
Classified Vegetation & Topography
 Lot 395 on Plan 062808, Area : 4.6485 ha
 1 Peony Boulevard,
 YANCHEP 6035
CITY OF WANNEROO



- LEGEND -----
- Subject Site
 - Other Lots
 - ← Photo & Direction
 - H Hydrant
- Proposed Building**
- New Dan Murphy's
 - Proposed Tavern
- 150m Vegetation Assessment Area**
- 150m from Subject Site
- Classified Vegetation**
- Class (A) Forest
 - Class (B) Woodland
 - Class (C) Shrubland
 - Class (D) Scrub
 - Class (G) Grassland
 - Excluded 2.2.3.2



----- LOCALITY -----




Aerial Imagery : Landgate/SLIP
 Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
 Projection: Universal Transverse Mercator Units: Metre
 Map compiled by: Ian Ross 21/09/2023
 Map updated by: Ian Ross 21/09/2023
 A3 Scale 1:1,500


Disclaimer and Limitation: This map has been prepared for bushfire management planning purposes only. All depicted areas, contours and any dimensions shown are subject to survey. Bushfire Prone Planning does not guarantee that this map is without flaw of any kind and disclaims all liability for any errors, loss or other consequence arising from relying on any information depicted.
 Map Document Path / Name: K:\Projects\Jobs 2023\230509 - Yanchep 3 x DA's (BMP x 3 sites)\230509 - Dan Murphy & Tavern combined\Mapping\MXD\230509_Fig3-1_VEG_Dan Murphy - Tavern.mxd

Figure 3.2
BAL Contour Map

Lot 395 on Plan 062808, Area : 4.6485 ha
1 Peony Boulevard,
YANCHEP 6035
CITY OF WANNEROO



- LEGEND -----
- Subject Site
 - Other Lots
 - H Hydrant
 - Proposed Building**
 - New Dan Murphy's
 - Proposed Tavern
 - 100m Vegetation Assessment Area**
 - 100m from Subject Site
 - Indicative Bushfire Attack Levels**
 - BAL FZ
 - BAL 40
 - BAL 29
 - BAL 19
 - BAL 12.5
 - BAL LOW
 - Classified Vegetation Boundary



Aerial Imagery : Landgate/SLIP
Image Date : Feb 2023

Coordinate System: GDA 1994 MGA Zone 50
Projection: Universal Transverse Mercator Units: Metre
Map compiled by: Ian Ross 21/09/2023
Map updated by: Ian Ross 21/09/2023
A3 Scale 1:1,250

4 IDENTIFICATION OF BUSHFIRE HAZARD ISSUES

The Guidelines for Planning in Bushfire Prone Areas (WAPC 2021 v1.4), Appendix 5, establish that the application of this section of the BMP is intended to support **strategic planning** proposals. At the strategic planning stage there will typically be insufficient proposed development detail to enable all required assessments, including the assessment against the bushfire protection criteria.

Strategic Planning Proposals

For strategic planning proposals this section of the BMP will identify:

- Issues associated with the level of the threats presented by any identified bushfire hazard;
- Issues associated with the ability to implement sufficient and effective bushfire protection measures to reduce the exposure and vulnerability levels (of elements exposed to the hazard threats), to a tolerable or acceptable level; and
- Issues that will need to be considered at subsequent planning stages.

All Other Planning Proposals

For all other planning stages, this BMP will address what are effectively the same relevant issues but do it within the following sections:

- Section 2 – Bushfire Prone Vegetation - Environmental and Assessment Considerations: Assess environmental, biodiversity and conservation values;
- Section 3 – Potential Bushfire Impact: Assess the bushfire threats with the focus on flame contact and radiant heat; and
- Section 5 – Assessment Against the Bushfire Protection Criteria (including the guidance provided by the *Position Statement: 'Planning in bushfire prone areas – Demonstrating Element 1: Location and Element 2'*): Assess the ability of the proposed development to apply the required bushfire protection measures thereby enabling it to be considered for planning approval for these factors.

Is the proposed development a strategic planning proposal?

No

5 ASSESSMENT AGAINST THE BUSHFIRE PROTECTION CRITERIA (GUIDELINES V1.4)

5.1 Bushfire Protection Criteria Elements Applicable to the Proposed Development/Use

APPLICATION OF THE CRITERIA, ACCEPTABLE SOLUTIONS AND PERFORMANCE ASSESSMENT

The criteria are divided into five elements – location, siting and design, vehicular access, water and vulnerable tourism land uses. Each element has an intent outlining the desired outcome for the element and reflects identified planning and policy requirements in respect of each issue.

The example acceptable solutions (bushfire protection measures) provide one way of meeting the element's intent. Compliance with these automatically achieves the element's intent and provides a straightforward pathway for assessment and approval.

Where the acceptable solutions cannot be met, the ability to develop design responses (as alternative solutions that meet bushfire performance requirements) is an alternative pathway that is provided by addressing the applicable performance principles (as general statements of how best to achieve the intent of the element).

A merit based assessment is established by the SPP 3.7 and the Guidelines as an additional alternative pathway along with the ability of using discretion in making approval decisions (sections 2.5, 2.6 and 2.7). This is formally applied to certain development (minor and unavoidable – sections 5.4.1 and 5.7). Relevant decisions by the State Administrative Tribunal have also supported this approach more generally.

Elements 1 – 4 should be applied for all strategic planning proposals, subdivision or development applications, except for vulnerable tourism land uses which should refer to Element 5. Element 5 incorporates the bushfire protection criteria in Elements 1 – 4 but caters them specifically to tourism land uses. (Guidelines DPLH 2021v1.4)

The Bushfire Protection Criteria	Applicable to the Proposed Development/Use
Element 1: Location	Yes
Element 2: Siting and Design	Yes
Element 3: Vehicular Access	Yes
Element 4: Water	Yes
Element 5: Vulnerable Tourism Land Uses	No

5.2 Local Government Variations to Apply

Local governments may add to or modify the acceptable solutions to recognise special local or regional circumstances (e.g., topography / vegetation / climate). These are to be endorsed by both the WAPC and DFES before they can be considered in planning assessments. (Guidelines DPLH 2021v1.4).

Do endorsed regional or local variations to the acceptable solutions apply to the assessments against the Bushfire Protection Criteria for the proposed development /use?

No

5.3 Assessment Statements for Element 1: Location

LOCATION	
Element Intent	To ensure that strategic planning proposals, subdivision and development applications are located in areas with the least possible risk of bushfire to facilitate the protection of people, property and infrastructure.
Proposed Development/Use – Relevant Planning Stage	(Do) Development application other than for a single dwelling, ancillary dwelling or minor development
Element Compliance Statement	The proposed development/use achieves the intent of this element by being fully compliant with all applicable acceptable solutions.
Pathway Applied to Provide an Alternative Solution	N/A
Acceptable Solutions - Assessment Statements	
<p>All details of acceptable solution requirements are established in the Guidelines for Planning in Bushfire Prone Areas, DPLH v1.4 (Guidelines) and apply the guidance established by the Position Statement: 'Planning in bushfire prone areas – Demonstrating Element 1: Location and Element 2: Siting and design' (WAPC Nov 2019) and the 'Bushfire Management Plan Guidance for the Dampier Peninsula' (WA Department of Planning, Lands and Heritage, 2021 Rev B) as relevant. These documents are available at https://www.wa.gov.au/government/document-collections/state-planning-policy-37-planning-bushfire-prone-areas.</p>	
Solution Component Check Box Legend	<input checked="" type="checkbox"/> Relevant & met <input checked="" type="checkbox"/> Relevant & not met <input type="checkbox"/> Not relevant
A1.1 Development location	Applicable: Yes Compliant: Yes
ASSESSMENT AGAINST THE REQUIREMENTS ESTABLISHED BY THE GUIDELINES	
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> The development application is located in an area that is or will, on completion, be subject to either a moderate or low bushfire hazard level, or BAL-29 or below.	
Supporting Assessment Details: Both the proposed Dan Murphys's and the proposed tavern area able to be situated within a BAL-29 area.	
ASSESSMENTS APPLYING THE GUIDANCE ESTABLISHED BY THE WAPC ELEMENT 1 & 2 POSITION STATEMENT (2019)	
<p>"Consideration should be given to the site context where 'area' is the land both within and adjoining the subject site. The hazards remaining within the site should not be considered in isolation of the hazards adjoining the site, as the potential impact of a bushfire will be dependent on the wider risk context, including how a bushfire could affect the site and the conditions for a bushfire to occur within the site."</p> <p>Strategic Planning Proposals: Consider the threat levels from any vegetation <u>adjoining</u> and <u>within</u> the subject site for which the potential intensity of a bushfire in that vegetation would result in it being classified as an Extreme Bushfire Hazard Level (BHL). Identify any proposed design strategies to reduce these threats.</p> <p>Structure Plans (lot layout known) and Subdivision Applications: As for strategic planning proposals but <u>within</u> the subject site the relevant threat levels to consider are the radiant heat levels represented by BAL-FZ and BAL-40 ratings.</p>	
<p>The planning proposal is a development application, consequently the referenced position statement is not applicable to the Element 1 assessment.</p>	

5.4 Assessment Statements for Element 2: Siting and Design

SITING AND DESIGN OF DEVELOPMENT	
Element Intent	To ensure that the siting and design of development minimises the level of bushfire impact. (BPP Note: not building/construction design)
Proposed Development/Use – Relevant Planning Stage	(Do) Development application other than for a single dwelling, ancillary dwelling or minor development
Element Compliance Statement	The proposed development/use achieves the intent of this element by being fully compliant with all applicable acceptable solutions.
Pathway Applied to Provide an Alternative Solution	N/A
Acceptable Solutions - Assessment Statements	
<p>All details of acceptable solution requirements are established in the Guidelines for Planning in Bushfire Prone Areas, DPLH v1.4 (Guidelines) and apply the guidance established by the Position Statement: 'Planning in bushfire prone areas – Demonstrating Element 1: Location and Element 2: Siting and design' (WAPC Nov 2019) and the 'Bushfire Management Plan Guidance for the Dampier Peninsula' (WA Department of Planning, Lands and Heritage, 2021 Rev B) as relevant. These documents are available at https://www.wa.gov.au/government/document-collections/state-planning-policy-37-planning-bushfire-prone-areas.</p>	
<p>Solution Component Check Box Legend <input checked="" type="checkbox"/> Relevant & met <input checked="" type="checkbox"/> Relevant & not met <input type="checkbox"/> Not relevant</p>	
A2.1 Asset Protection Zone (APZ)	<p>Applicable: Yes Compliant: Yes</p>
APZ DIMENSIONS – DIFFERENCES IN REQUIREMENTS FOR PLANNING ASSESSMENTS COMPARED TO IMPLEMENTATION	
<p>A key required bushfire protection measure is to reduce the exposure of buildings/infrastructure (as exposed vulnerable elements at risk), to the direct bushfire threats of flame contact, radiant heat and embers and the indirect threat of consequential fires that result from the subsequent ignition of other combustible materials that may be constructed, stored or accumulate in the area surrounding these structures. This reduces the associated risks of damage or loss.</p> <p>This is achieved by separating buildings (and consequential fire fuels as necessary) from areas of classified bushfire prone vegetation. This area of separation surrounding buildings is identified as the Asset Protection Zone (APZ) and consists of no vegetation and/or low threat vegetation or vegetation continually managed to a minimal fuel condition. The required separation distances will vary according to the site specific conditions and local government requirements.</p> <p>The APZ dimensions stated and/or illustrated in this Report can vary dependent on the purpose for which they are being identified.</p> <div style="border: 1px solid black; padding: 10px; margin: 10px 0;"> <p><i>Note: Appendix B 'Onsite Vegetation Management' provides further information regarding the different APZ dimensions that can be referenced, their purpose and the specifications of the APZ that are to be established and maintained on the subject lot.</i></p> </div>	
THE 'PLANNING BAL-29' APZ DIMENSIONS	
<p>Purpose: To provide evidence of the development or use proposal's ability to achieve minimum vegetation separation distances. To achieve 'acceptable solution' planning approval for this factor, it must be demonstrated that the minimum separation distances corresponding to a maximum level of radiant transfer to a building of 29 kW/m², either exist or can be implemented (with certain exceptions). These separation distances are the 'Planning BAL-29' APZ dimensions.</p> <p><i>The 'Planning BAL-29' APZ is not necessarily the size of the APZ that must be physically implemented and maintained by a landowner. Rather, its sole purpose is to identify if an acceptable solution for planning approval can be met.</i></p>	

THE 'REQUIRED' APZ DIMENSIONS

Purpose: Establishes the dimensions of the APZ to be physically implemented by the landowner on their lot: These will be the minimum required separation distances from the subject building(s) to surrounding bushfire prone vegetation (identified by type and associated ground slope). These are established by:

- A. The 'BAL Rating APZ' of the subject building(s) when distances are greater than 'B' below (except when 'B' establishes a maximum distance); or
- B. The 'Local Government' APZ' derived from the Firebreak/Hazard Reduction Notice when distances are greater than 'A' above, other than when a maximum distance is established, in which case this will apply; or
- C. A combination of 'A' and 'B'.

Within this Report/Plan it is the 'Planning BAL-29' APZ that will be identified on maps, diagrams and in tables as necessary – unless otherwise stated.

The 'Required' APZ dimension information will be presented in Appendix B1.1 and on the Property Bushfire Management Statement, when required to be included for a development application.

ASSESSMENT AGAINST THE REQUIREMENTS ESTABLISHED BY THE GUIDELINES

APZ Width: The proposed (or a future) habitable building(s) on the lot(s) of the proposed development - or an existing building for a proposed change of use – can be (or is) located within the developable portion of the lot and be surrounded by a 'Planning BAL-29' APZ of the required dimensions (measured from any external wall or supporting post or column to the edge of the classified vegetation), that will ensure their exposure to the potential radiant heat impact of a bushfire does not exceed 29 kW/m².

Restriction on Building Location: It has been identified that the current developable portion of a lot(s) provides for the proposed future (or a future) building/structure location that will result in that building/structure being subject to a BA-40 or BAL-FZ rating. Consequently, it may be considered necessary to impose the condition that a restrictive covenant to the benefit of the local government pursuant to section 129BA of the Transfer of Land Act 1893, is to be placed on the certificate(s) of title of the proposed lot(s) advising of the existence of a restriction on the use of that portion of land (refer to Code F3 of Model Subdivision Conditions Schedule, WAPC June 2021 and Guidelines s5.3.2).

APZ Location: The required dimensions for a 'Planning BAL-29' APZ can be contained solely within the boundaries of the lot(s) on which the proposed (or a future) habitable building(s) - or an existing building(s) for a proposed change of use – is situated.

APZ Location: The required dimensions for a 'Planning BAL-29' APZ can be partly established within the boundaries of the lot(s) on which the proposed (or a future) habitable building(s) - or an existing building(s) for a proposed change of use – is situated. The balance of the APZ would exist on adjoining land that satisfies the exclusion requirements of AS 3959:2018 cl 2.2.3.2 for non-vegetated areas and/or low threat vegetation and/or vegetation managed in a minimal fuel condition.

APZ Location: It can be justified that any adjoining (offsite) land forming part of a 'Planning BAL-29' APZ will:

- If non-vegetated, remain in this condition in perpetuity; and/or
- If vegetated, be low threat vegetation or vegetation managed in a minimal fuel condition in perpetuity.

APZ Management: The area of land (within each lot boundary), that is to make up the required 'Landowner' APZ dimensions (refer to Appendix B, Part B1), can and will be managed in accordance with

the requirements of the Guidelines Schedule 1 'Standards for Asset Protection Zones' (refer to Appendix B).

Subdivision Staging: There are undeveloped future stages of subdivision, containing bushfire prone vegetation, that have been taken into consideration for their potentially 'temporary' impact on the ability to establish a 'Planning BAL-29' APZ on adjoining developed lots. A staging plan is developed to manage this.

Firebreak/Hazard Reduction Notice: Any additional requirements established by the relevant local government's annual notice to install firebreaks and manage fuel loads (issued under s33 of the Bushfires Act 1954), can and will be complied with.

Supporting Assessment Details: The BAL-29 APZ will consist of excludable areas under AS 3959:2018 cl 2.2.3.2, both within the lot and within the adjoining the lot. The excludable areas in the adjoining lot will be made up unvegetated areas, including footpaths, public roads and bike lanes.

ASSESSMENTS APPLYING THE GUIDANCE ESTABLISHED BY THE WAPC ELEMENT 1 & 2 POSITION STATEMENT (2019)

Strategic Planning Proposals: "At this planning level there may not be enough detail to demonstrate compliance with this element. The decision-maker may consider this element is satisfied where A1.1 is met."

Structure Plans (lot layout known) and Subdivision Applications: "Provided that Element 1 is satisfied, the decision-maker may consider approving lot(s) containing BAL-40 or BAL-FZ under the following scenarios.

The planning proposal is a development application, consequently the referenced position statement is not applicable to the proposed development.

5.5 Assessment Statements for Element 3: Vehicular Access

VEHICULAR ACCESS	
Element Intent	To ensure that the vehicular access serving a subdivision/development is available and safe during a bushfire event.
Proposed Development/Use – Relevant Planning Stage	(Do) Development application other than for a single dwelling, ancillary dwelling or minor development
Element Compliance Statement	The proposed development/use achieves the intent of this element by being fully compliant with all applicable acceptable solutions.
Pathway Applied to Provide an Alternative Solution	N/A
Acceptable Solutions - Assessment Statements	
<p>All details of acceptable solution requirements are established in the Guidelines for Planning in Bushfire Prone Areas, DPLH v1.4 (Guidelines) and apply the guidance established by the Position Statement: 'Planning in bushfire prone areas – Demonstrating Element 1: Location and Element 2: Siting and design' (WAPC Nov 2019) and the 'Bushfire Management Plan Guidance for the Dampier Peninsula' (WA Department of Planning, Lands and Heritage, 2021 Rev B) as relevant. These documents are available at https://www.wa.gov.au/government/document-collections/state-planning-policy-37-planning-bushfire-prone-areas.</p> <p>The technical construction requirements for access types and components, and for each firefighting water supply component, are also presented in Appendices 2 and 3. The local government will advise the proponent where different requirements are to apply and when any additional specifications such as those for signage and gates are to apply (these are included in the relevant appendix if requested by the local government).</p>	
Solution Component Check Box Legend	<input checked="" type="checkbox"/> Relevant & met <input checked="" type="checkbox"/> Relevant & not met <input type="checkbox"/> Not relevant
A3.1 Public roads	Applicable: Yes Compliant: Yes
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<p>The technical construction requirements of vertical clearance and weight capacity (Guidelines, Table 6) can and will be complied with (Refer also to Appendix C in this BMP).</p>
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<p>All other applicable technical requirements of trafficable width, gradients and curves, are required to be in "accordance with the class of road as specified in the IPWEA Subdivision Guidelines, Liveable Neighbourhoods, Ausroad Standards and/or any applicable standard in the local government area" (Guidelines, Table 6 and E3.1. Refer also to Appendix C in this BMP).</p> <p>The assessment conducted for the bushfire management plan indicates that it is likely that the proposed development can and will comply with the requirements.</p> <p>The applicable class(s) of road and technical requirements have been confirmed with the relevant local government/Main Roads WA. These can and will be complied with.</p>
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	A traversable verge is available adjacent to classified vegetation (Guidelines, E3.1), as recommended.
Supporting Assessment Details: None required.	

A3.2a Multiple access routes	Applicable:	Yes	Compliant:	Yes
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> For each lot, two-way public road access is provided in two different directions to at least two different suitable destinations with an all-weather surface.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The two-way access <u>is</u> available at an intersection no greater than 200m from the relevant boundary of each lot, via a no-through road.				
<p>The two-way access is <u>not</u> available at an intersection within 200m from the relevant boundary of each lot. However, the available no-through road satisfies the established exemption for the length limitation in every case. These requirements are:</p> <p><input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <ul style="list-style-type: none"> Demonstration of no alternative access (refer to A3.3 below); The no-through road travels towards a suitable destination; and The balance of the no-through road that is greater than 200m from the relevant lot boundary is within a residential built-out area or is potentially subject to radiant heat levels from adjacent bushfire prone vegetation that correspond to the BAL-LOW rating (<12.5 kW/m²). </p>				
Supporting Assessment Details: The development sits on Peony Boulevard which has two access to Marmion Avenue and Kakadu Road. Both roads also provide two access onto other adjoining roads.				
A3.2b Emergency access way	Applicable:	No	Compliant:	N/A
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The proposed or existing EAW provides a through connection to a public road.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The proposed or existing EAW is less than 500m in length and will be signposted and gated (remaining unlocked) to the specifications stated in the Guidelines and/or required by the relevant local government.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The technical construction requirements for widths, clearances, capacity, gradients and curves (Guidelines, Table 6 and E3.2b. Refer also to Appendix C in this BMP), can and will be complied with.				
Supporting Assessment Details: N/A.				
A3.3 Through-roads	Applicable:	No	Compliant:	No
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> A no-through public road is necessary as no alternative road layout exists due to site constraints.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The no-through public road length does not exceed the established maximum of 200m to an intersection providing two-way access (Guidelines, E3.3).				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The no-through public road exceeds 200m but satisfies the exemption provisions of A3.2a as demonstrated in A3.2a above.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The public road technical construction requirements (Guidelines, Table 6 and E3.1. Refer also to Appendix C in this BMP), can and will be complied with as established in A3.1 above.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> The turnaround area requirements (Guidelines, Figure 24) can and will be complied with.				
Supporting Assessment Details: N/A.				

A3.4a Perimeter roads	Applicable:	No	Compliant:	No
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The proposed greenfield or infill development consists of 10 or more lots (including those that are part of a staged subdivision) and therefore should have a perimeter road. This is planned to be installed.				
<p>The proposed greenfield or infill development consists of 10 or more lots (including those that are part of a staged subdivision). However, it is not required on the established basis of:</p> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> <ul style="list-style-type: none"> • The vegetation adjoining the proposed lots is classified Class G Grassland; • Lots are zoned rural living or equivalent; • It is demonstrated that it cannot be provided due to site constraints; or • All lots have existing frontage to a public road. 				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The technical construction requirements of widths, clearances, capacity, gradients and curves (Guidelines, Table 6 and E3.4a) can and will be complied with.				
Supporting Assessment Details: N/A.				
A3.4b Fire service access route	Applicable:	No	Compliant:	No
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The FSAR can be installed as a through-route with no dead ends, linked to the internal road system every 500m and is no further than 500m from a public road.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The technical construction requirements of widths, clearances, capacity, gradients and curves (Guidelines, Table 6 and E3.4b. Refer also to Appendix C in this BMP), can and will be complied with.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The FSAR can and will be signposted. Where gates are required by the relevant local government, the specifications can be complied with.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> Turnaround areas (to accommodate type 3.4 fire appliances) can and will be installed every 500m on the FSAR.				
Supporting Assessment Details: N/A.				
A3.5 Battle-axe access legs	Applicable:	No	Compliant:	No
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> A battle-axe leg cannot be avoided due to site constraints.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The proposed development is in a reticulated area and the battle-axe access leg length from a public road is no greater than 50m. No technical requirements need to be met.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> The proposed development is not in a reticulated area. The technical construction requirements for widths, clearances, capacity, gradients and curves (Guidelines, Table 6 and E3.5. Refer also to Appendix C in this BMP), can and will be complied with.				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="radio"/> Passing bays can and will be installed every 200m with a minimum length of 20m and a minimum additional trafficable width of 2m.				
Supporting Assessment Details: N/A.				
Ensure bridge weight capacity is considered when relevant.				

A3.6 Private driveways	Applicable:	Yes	Compliant:	Yes
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <p>The private driveway to the most distant external part of the development site is within a lot serviced by reticulated water, is accessed via a public road with a speed limit of 70 km/hr or less and has a length is no greater than 70m (measured as a hose lay). No technical requirements need to be met.</p>				
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <p>The technical construction requirements for widths, clearances, capacity, gradients and curves (Guidelines, Table 6 and E3.6. Refer also to Appendix C in this BMP), can and will be complied with.</p>				
<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <p>Passing bays can and will be installed every 200m with a minimum length of 20m and a minimum additional trafficable width of 2m.</p>				
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <p>The turnaround area requirements (Guidelines, Figure 28, and within 30m of the habitable building) can and will be complied with.</p>				
<p>Supporting Assessment Details: The proposed Dan Murphy's is approximately 30 metres away from the current access point onto Peony Boulevard, while the Tavern is approximately 15 metres away to Peony Boulevard.</p>				

5.6 Assessment Statements for Element 4: Water

FIREFIGHTING WATER	
Element Intent	To ensure water is available to enable people, property and infrastructure to be defended from bushfire.
Proposed Development/Use – Relevant Planning Stage	(Do) Development application other than for a single dwelling, ancillary dwelling or minor development
Element Compliance Statement	The proposed development/use achieves the intent of this element by being fully compliant with all applicable acceptable solutions.
Pathway Applied to Provide an Alternative Solution	N/A
Acceptable Solutions - Assessment Statements	
<p>All details of acceptable solution requirements are established in the Guidelines for Planning in Bushfire Prone Areas, DPLH v1.4 (Guidelines) and apply the guidance established by the Position Statement: 'Planning in bushfire prone areas – Demonstrating Element 1: Location and Element 2: Siting and design' (WAPC Nov 2019) and the 'Bushfire Management Plan Guidance for the Dampier Peninsula' (WA Department of Planning, Lands and Heritage, 2021 Rev B) as relevant. These documents are available at https://www.wa.gov.au/government/document-collections/state-planning-policy-37-planning-bushfire-prone-areas.</p> <p>The technical construction requirements for access types and components, and for each firefighting water supply component, are also presented in Appendices 2 and 3. The local government will advise the proponent where different requirements are to apply and when any additional specifications such as those for signage and gates are to apply (these are included in the relevant appendix if requested by the local government).</p>	
Solution Component Check Box Legend	<input checked="" type="checkbox"/> Relevant & met <input checked="" type="checkbox"/> Relevant & not met <input type="checkbox"/> Not relevant
A4.1 Identification of future firefighting water supply	Applicable: No Compliant: No
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> It can be demonstrated that reticulated or sufficient non-reticulated water for firefighting can be provided at the subdivision and/or development application stage in accordance with the specifications of the relevant water supply authority or the requirements of Schedule 2.	
Supporting Assessment Details: N/A,	
A4.2 Provision of water for firefighting purposes	Applicable: Yes Compliant: Yes
<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> A reticulated water supply is available to the proposed development. The existing hydrant connection(s) are provided in accordance with the specifications of the relevant water supply authority.	
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> A reticulated water supply will be available to the proposed development. Hydrant connection(s) can and will be provided in accordance with the specifications of the relevant water supply authority.	
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> A static water supply (tank) for firefighting purposes will be installed on the lot that is additional to any water supply that is required for drinking and other domestic purposes. The proposed subdivision will retain an existing habitable building for which the same standard of water supply will be provided.	
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> A strategic water supply (tank or tanks) for firefighting purposes will be installed within or adjacent to the proposed development that is additional to any water supply that is required for drinking and other domestic purposes. The required land will be ceded free of cost to the local government and the lot or road reserve where the tank is to be located will be identified on the plan of subdivision.	

The strategic static water supply (tank or tanks) will be located no more than 10 minutes travel time from a subject site (at legal road speeds).

The technical requirements (location, number of tanks, volumes, design, construction materials, pipes and fittings), as established by the Guidelines (A4.2, E4 and Schedule 2) and/or the relevant local government, can and will be complied with.

Supporting Assessment Details: The proposed development is within a reticulated area and therefore will not need to comply with any other technical water requirements. The closest hydrant is located on Peony Boulevard approximately 60 metres away.

Refer to information contained in Appendix D for the firefighting water supply specifications and technical requirements.

6 BUSHFIRE PROTECTION MEASURES - RESPONSIBILITY FOR IMPLEMENTATION CHECKLIST

6.1 Developer / Landowner Responsibilities – Prior to Operation

DEVELOPER/LANDOWNER RESPONSIBILITIES – PRIOR OPERATION	
No.	Implementation Actions
1	<p>Prior to relevant building work, inform the builder of the existence of this approved Bushfire Management Plan (BMP). The plan identifies that the development site is within a designated bushfire prone area and states the indicative (or determined) BAL rating(s) that may (or will) be applied to buildings/structures. A BAL assessment report may be required to confirm determined ratings and will be required when ratings are indicative. BAL certificates will need to be issued to accompany building applications.</p> <p>The BMP may also establish, as an additional bushfire protection measure, that construction requirements to be applied will be those corresponding to a specified higher BAL rating.</p> <p>Compliance with the Building Code of Australia (Volumes 1 and 2 of the National Construction Code), will require certain bushfire resistant construction requirements be applied to residential buildings in bushfire prone areas (i.e., Class 1, 2 and 3 and associated Class 10a buildings and decks). Other classes of buildings may also be required to comply with these construction when established by the relevant authority or if identified as an additional bushfire protection measure within the BMP.</p> <p>The deemed to satisfy solutions that will meet the relevant bushfire performance requirements are found in AS 3959 – Construction of Building in Bushfire Prone Areas (as amended) and the NASH Standard - Steel Framed Construction in Bushfire Areas (as amended).</p>
2	<p>Prior to occupancy/operation establish the 'Required' Asset Protection Zone (APZ) around habitable buildings (and other structures as required) to satisfy:</p> <ul style="list-style-type: none"> • The minimum required dimensions established in Appendix B1; and • The standards established by the Guidelines DPLH, 2021 v1.4, Schedule 1, or as varied by the local government through their annually issued firebreak / hazard reduction notice when the variations have been endorsed by the WAPC and DFES as per s4.5.3 of the Guidelines. <p>If native vegetation is required to be modified or removed, ensure that approval has been received from the relevant authority (refer to the applicable local government for advice).</p>

6.2 Landowner / Occupier Responsibilities – Ongoing Management

LANDOWNER/OCCUPIER – ONGOING MANAGEMENT	
No.	Management Actions
1	<p>Maintain the 'Required' Asset Protection Zone (APZ) around habitable buildings (and other structures as required) to satisfy:</p> <ul style="list-style-type: none"> • The minimum required dimensions established in Appendix B1; and • The standards established by the Guidelines DPLH, 2021 v1.4, Schedule 1, or as varied by the local government through their annually issued firebreak / hazard reduction notice when the variations have been endorsed by the WAPC and DFES as per s4.5.3 of the Guidelines.
2	<p>Comply with the City of Wanneroo Fire Mitigation Notice issued under s33 of the Bush Fires Act 1954. Check the notice annually for any changes.</p>
3	<p>Maintain vehicular access routes within the lot to comply with the technical requirements referenced in the BMP and the relevant local government's annual firebreak / hazard reduction notice.</p>
4	<p>Ensure that builders engaged to construct dwellings/additions and/or other relevant structures on the lot, are aware of the existence of this approved Bushfire Management Plan (BMP). The plan identifies that the development site is within a designated bushfire prone area and states the indicative (or determined) BAL rating(s) that may (or will) be applied to buildings/structures.</p> <p>A BAL assessment report may be required to confirm determined ratings and will be required when ratings are indicative. BAL certificates will need to be issued to accompany building applications.</p> <p>Compliance with the Building Code of Australia (Volumes 1 and 2 of the National Construction Code), will require certain bushfire resistant construction requirements be applied to residential buildings in bushfire prone areas (i.e., Class 1, 2 and 3 and associated Class 10a buildings and decks). The deemed to satisfy solutions that will meet the relevant bushfire performance requirements are found in AS 3959 – Construction of Building in Bushfire Prone Areas (as amended) and the NASH Standard - Steel Framed Construction in Bushfire Areas (as amended).</p> <p>As an additional bushfire protection measure, other classes of buildings may also be required to comply with these construction requirements when established by the relevant authority or if identified as an additional bushfire protection measure within the BMP. The BMP may also establish that construction requirements to be applied will be those corresponding to a specified higher BAL rating. When applicable, these requirements will be identified in Section 5.7.</p>
5	<p>Ensure all future buildings the landowner has responsibility for, are designed and constructed in full compliance with:</p> <ul style="list-style-type: none"> • The bushfire resistant construction requirements of the Building Code of Australia (Volumes 1 and 2 of the National Construction Code), as established by the Building Regulations 2012 (WA Building Act 2011); and • Any additional bushfire protection measures this Bushfire Management Plan has established are to be implemented.

6.3 Local Government Responsibilities – Ongoing Management

LOCAL GOVERNMENT – ONGOING MANAGEMENT	
No.	Management Actions
1	<p>Monitor landowner compliance with the annual City of Wanneroo Fire Mitigation Notice and with any bushfire protection measures that are:</p> <ul style="list-style-type: none"> • Established by this BMP; • Are required to be maintained by the landowner/occupier; and • Are relevant to local government operations.

APPENDIX A: DETAILED BAL ASSESSMENT DATA AND SUPPORTING INFORMATION

A1: BAL Assessment Inputs Common to the Method 1 and Method 2 Procedures

A1.1: FIRE DANGER INDICES (FDI/FDI/GFDI)

When using Method 1 the relevant FDI value required to be applied for each state and region is established by AS 3959:2018, Table 2.1. Each FDI value applied in Tables 2.4 – 2.7 represents both the Forest Fire Danger Index (FFDI) and a deemed equivalent for the Grassland Fire Danger Index (GFDI), as per Table B2 in Appendix B. When using Method 2, the relevant FFDI and GFDI are applied.

The values may be able to be refined within a jurisdiction, where sufficient climatological data is available and in consultation with the relevant authority.

Relevant Jurisdiction:	WA	Region:	Whole State	Method 1	Applied FDI:	80
				Method 2	Applied FFDI:	N/A
					Applied GFDI:	N/A

A1.2: VEGETATION ASSESSMENT AND CLASSIFICATION

Vegetation Types and Classification

In accordance with AS 3959:2018 clauses 2.2.3 and C2.2.3.1, all vegetation types within 100 metres of the 'site' (defined as "the part of the allotment of land on which a building stands or is to be erected"), are identified and classified. Any vegetation more than 100 metres from the site that has influenced the classification of vegetation within 100 metres of the site, is identified and noted. The maximum excess distance is established by AS 3959: 2018 cl 2.2.3.2 and is an additional 100 metres.

Classification is also guided by the Visual Guide for Bushfire Risk Assessment in WA (WA Department of Planning February 2016) and any relevant FPA Australia practice notes.

Modified Vegetation





The vegetation types have been assessed as they will be in their natural mature states, rather than what might be observed on the day. Vegetation destroyed or damaged by a bushfire or other natural disaster has been assessed on its expected re-generated mature state. Modified areas of vegetation can be excluded from classification if they consist of low threat vegetation or vegetation managed in a minimal fuel condition, satisfying AS 3959:2018 s2.2.3.2(f), and there is sufficient justification to reasonable expect that this modified state will exist in perpetuity.


The Influence of Ground Slope


Where significant variation in effective slope exists under a consistent vegetation type, these will be delineated as separate vegetation areas to account for the difference in potential bushfire behaviour, in accordance with AS 3959:2018 clauses 2.2.5 and C2.2.5.




THE INFLUENCE OF VEGETATION GREATER THAN 100 METRES FROM THE SUBJECT SITE



Vegetation area(s) within 100m of the site whose classification has been influenced by the existence of bushfire prone vegetation from 100m – 200m from the site:	None
Assessment Statement:	No vegetation types exist close enough, or to a sufficient extent, within the relevant area to influence classification of vegetation within 100 metres of the subject site.

VEGETATION AREA 1					
Classification	D. SCRUB				
Types Identified	Open scrub D-14		Sown pasture G-26		
Effective Slope	Measured	flat 0 degrees	Applied Range (Method 1)	Upslope or flat 0 degrees	
Foliage Cover (all layers)	10-30%	Shrub/Heath Height	Up to 4m	Tree Height	N/A
Dominant & Sub-Dominant Layers (species as relevant)	Dominant vegetation type includes scrub of heights up to 4 metres. Vegetation area also includes unmanaged grass, vegetation areas does not show signs of a recent management.				
Post Development Assumptions:	Only scrub vegetation within the subject site can be managed by the landowner.				
 <p>DIRECTION 342 deg(T) 31.54870°S ACCURACY 5 m 115.63776°E DATUM WGS84</p> <p>230303 2023-08-15 10:27:13+08:00</p>			 <p>DIRECTION 36 deg(T) 31.54852°S ACCURACY 4 m 115.63716°E DATUM WGS84</p> <p>230303 2023-08-15 11:13:03+08:00</p>		
PHOTO ID: 1			PHOTO ID: 2		
 <p>DIRECTION 213 deg(T) 31.54834°S ACCURACY 5 m 115.63788°E DATUM WGS84</p> <p>230303 2023-08-15 11:08:46+08:00</p>			 <p>DIRECTION 341 deg(T) 31.54860°S ACCURACY 5 m 115.63894°E DATUM WGS84</p> <p>230303 2023-08-15 10:34:16+08:00</p>		
PHOTO ID: 3			PHOTO ID: 4		

VEGETATION AREA 2						
Classification	B. WOODLAND					
Types Identified	Woodland B-05		Low shrubland C-12			
Effective Slope	Measured	flat 0 degrees	Applied Range (Method 1)		Upslope or flat 0 degrees	
Foliage Cover (all layers)	10-30%	Shrub/Heath Height	<1m	Tree Height	Up to 12m	
Dominant & Sub-Dominant Layers (species as relevant)	Vegetation area has been classified as woodland due to the dominant vegetation type being mature native trees. Native trees have formed a line with an understory of small bushes rather than scrub, while the Yanchep Sports Club area immediately to the north of the woodland is in a managed state, suggesting that the woodland area has been recently cleared.					
Post Development Assumptions:	The woodland area is not within the subject site, therefore the landowner cannot manage the vegetation.					
						
PHOTO ID: 5			PHOTO ID: -			

VEGETATION AREA 3						
Classification	G. GRASSLAND					
Types Identified	Sown pasture G-26					
Effective Slope	Measured	flat 0 degrees	Applied Range (Method 1)		Upslope or flat 0 degrees	
Foliage Cover (all layers)	N/A	Shrub/Heath Height	N/A	Tree Height	N/A	
Dominant & Sub-Dominant Layers (species as relevant)	Grassland areas have formed where there has previously been clearing of trees and/or scrub vegetation. Grass has shown accelerated growth due to recent winter rain, has been classified as there is no evidence of recent management.					
Post Development Assumptions:	The grassland area is not within the subject site, therefore the landowner cannot manage the vegetation.					
						
PHOTO ID: 6			PHOTO ID: -			

VEGETATION AREA 4					
Classification	A. FOREST				
Types Identified	Open forest A-03				
Effective Slope	Measured	flat 0 degrees	Applied Range (Method 1)	Upslope or flat 0 degrees	
Foliage Cover (all layers)	30-70%	Shrub/Heath Height	<2m	Tree Height	Up to 5m
Dominant & Sub-Dominant Layers (species as relevant)	Forest vegetation consists primarily of mature native trees with subdominant vegetation types of bushes and grasses, creating a tiered structure. No evidence of recent management.				
Post Development Assumptions:	The forest area is not within the subject site, therefore the landowner cannot manage the vegetation.				
					
PHOTO ID: 7			PHOTO ID: 8		
					
PHOTO ID: 9			PHOTO ID: -		

VEGETATION AREA 5					
Classification	C. SHRUBLAND				
Types Identified	Closed (low) heath C-10				
Effective Slope	Measured	flat 0 degrees	Applied Range (Method 1)	Upslope or flat 0 degrees	
Foliage Cover (all layers)	10-30%	Shrub/Heath Height	1-2m	Tree Height	N/A
Dominant & Sub-Dominant Layers (species as relevant)	Shrubland area consists primarily of vegetation between 1 and 2 metres in height, in an area previously cleared. Since clearing, there has been no management or maintenance carried out and vegetation area cannot be considered for exclusion.				
Post Development Assumptions:	The shrubland area is not within the subject site, therefore the landowner cannot manage the vegetation.				
 <p>DIRECTION 131 deg(T) 31.54867°S 115.64014°E ACCURACY 5 m DATUM WGS84</p> <p>230303 2023-08-15 10:50:40+08:00</p>			 <p>DIRECTION 127 deg(T) 31.54897°S 115.64006°E ACCURACY 4 m DATUM WGS84</p> <p>230303 2023-08-15 10:50:03+08:00</p>		
PHOTO ID: 10			PHOTO ID: 11		



VEGETATION AREA 6					
Exclusion Clause	2.2.3.2 (e) non-vegetated areas and (f) vegetation managed in a minimal fuel condition.				
Effective Slope	Measured	N/A	Applied Range (Method 1)	N/A	
Foliage Cover (all layers)	N/A	Shrub/Heath Height	N/A	Tree Height	N/A
Dominant & Sub-Dominant Layers (species as relevant)	Excluded areas consist of low threat vegetation such as that shown within (PHOTO ID: 12), where there is only winter growth of weeds and the managed grassed areas within the Yanchep Sports Club (PHOTO ID: 16). Excluded areas also consists of non-vegetated areas such as public car parks and roads, existing buildings and areas of development.				
Post Development Assumptions:	N/A.				
 <p>DIRECTION 287 deg(T) 31.54876°S 115.63840°E ACCURACY 21 m DATUM WGS84</p> <p>230303 2023-08-15 10:32:06+08:00</p>			 <p>DIRECTION 129 deg(T) 31.54895°S 115.63794°E ACCURACY 4 m DATUM WGS84</p> <p>230303 2023-08-15 10:26:43+08:00</p>		
PHOTO ID: 12			PHOTO ID: 13		



PHOTO ID: 14



PHOTO ID: 15



PHOTO ID: 16

PHOTO ID: -

A1.3: EFFECTIVE SLOPE

Measuring

Effective slope refers to the slope “under the classified vegetation which most significantly influences bushfire behaviour (AS 3959:2018, clause B4, CB4). It is not the average slope.

It is described as upslope, flat or downslope when viewed from the exposed element (e.g., building) looking towards the vegetation – and measured in degrees. Ground slope has a direct and significant influence on a bushfire's rate of spread and intensity, which increases when travelling up a slope.

The slope under the vegetation in closest proximity to the exposed element(s), over the distance that will most likely carry the entire depth of the flaming front, will be a significant consideration in the determination of the effective slope. This distance is determined as a function of the potential quasi-steady rate of spread and expected residence time (i.e., the flaming combustion period at a single point on the ground), of a bushfire in the specific vegetation type/landscape scenario.

Slope Variation Within Areas of Vegetation

Where a significant variation in effective slope exists under a consistent vegetation type, these will be delineated as separate vegetation areas to account for the difference in potential bushfire behaviour, in accordance with AS 3959:2018 clauses 2.2.5 and C2.2.5.

Slope Variation Due to Multiple Development Sites

When the effective slope, under a given area of bushfire prone vegetation, will vary significantly relative to multiple proposed development sites (exposed elements), then the effective slopes corresponding to each of the different locations, are separately identified.

The relevant (worst case) effective slope is determined in the direction corresponding to the potential directions of fire spread towards the subject building(s).

Differences in Application of Effective Slope - AS 3959:2018 Method 1 versus Method 2 Procedures

The Method 1 procedure provides five different slope ranges from flat (including all upslopes) to 20 degrees downslope to define the effective slope and bushfire behaviour model calculations apply the highest value in each range (i.e., 0°, 5°, 10°, 15° or 20°).

The Method 2 procedure requires an actual slope (up or down in degrees) to be determined. AS 3959:2018, clause B1 limits the effective slope that can be applied to 30 degrees downslope and 15 degrees upslope. Where any upslope is greater than 15 degrees, then 15 degrees is to be used.

SITE ASSESSMENT DETAILS - EXPLANATION & JUSTIFICATION

The effective slopes determined from the site assessment are recorded in Table 3.2 of this Bushfire Management Plan. When their derivation requires additional explanation and justification, this is provided below.

A1.4: SEPARATION DISTANCE

Measuring

The separation distance is the distance in the horizontal plane between the receiver (building/structure or area of land being considered) and the edge of the classified vegetation (AS 3959:2018, clause 2.2.4)

The relevant parts of a building/structure from which the measurement is taken is the nearest part of an external wall or where a wall does not exist, the supporting posts or columns. Certain parts of buildings are excluded including eaves and roof overhangs.

The edge of the vegetation, for forests and woodlands, will be determined by the unmanaged understorey rather than either the canopy (drip line) or the trunk (AS 3959:2018, clause C2.2.5).

Measured Separation Distance as a Calculation Input

If a separation distance can be measured because the location of the building/structure relative to the edge of the relevant classified vegetation is known, this figure can be entered into the BAL calculation. The result is a determined BAL rating.

Assumed Separation Distance as a Calculation Input

When the building/structure location within the lot is not known, an assumed building location may be applied that would establish the closest positioning of the building/structure relative to the relevant area of vegetation.

The assumed location would be based on a factor that puts a restriction on a building location such as:

- An established setback from the boundary of a lot, such as a residential design code setback or a restrictive covenant; or
- Within an established building envelope.

The resultant BAL rating would be indicative and require later confirmation (via a Compliance Report) of the building/structure actual location relative to the vegetation to establish the determined BAL rating.

Separation Distance as a Calculation Output

With the necessary site specific assessment inputs and using the AS 3959:2018 bushfire modelling equations, the range of separation distances that will correspond to each BAL rating (each of which represents a range of radiant heat flux), can be calculated. This has application for bushfire planning scenarios such as:

- When the separation distance cannot be measured because the exact location of the exposed element (i.e., the building, structure or area), relative to classified vegetation, is yet to be determined.

In this scenario, the required information is the identification of building locations onsite that will correspond to each BAL rating. That is, indicative BAL ratings can be derived for a variety of potential building/structure locations; or

- The separation distance is known for a given building, structure or area (and a determined BAL rating can be derived), but additional information is required regarding the exposure levels (to the transfer of radiant heat from a bushfire), of buildings or persons, that will exist at different points within the subject site.

The calculated range of separation distances corresponding to each BAL rating can be presented in a table and/or illustrated as a BAL Contour Map – whichever is determined to best fit the purpose of the assessment.

For additional information refer to the information boxes in Section 3 'Bushfire Attack Levels (BAL) - Understanding the Results and Section 3.2. 'Interpretation of the BAL Contour Map'.

SITE ASSESSMENT DETAILS - EXPLANATION & JUSTIFICATION

For the subject development/use the applicable separation distances values are derived from calculations applying the assessed site data. They are an output value, not an input value and therefore are not presented or justified in this appendix.

The derived values are presented in Section 3, Table 3.1 and illustrated as a BAL contour map in Figure 3.2.

APPENDIX B: ADVICE - ONSITE VEGETATION MANAGEMENT - THE APZ

THE ASSET PROTECTION ZONE (APZ) - DESCRIPTION

This is an area surrounding a habitable building containing low threat fire fuel fuels (including vegetation), or vegetation managed in a minimal fuel condition, no fire fuels or any combination. The primary objectives include:

- To ensure the building is sufficiently separated from the bushfire hazard to limit the impact of its direct attack mechanisms. That is, the dimensions of the APZ will, for most site scenarios, remove the potential for direct flame contact on the building, reduce the level of radiant heat to which the building is exposed and ensure some reduction in the level of ember attack (with the level of reduction being dependent on the vegetation types of present);
- To ensure any vegetation retained within the APZ is low threat and/or is managed in a minimum fuel condition and prevents surface fire spreading to the building;
- To ensure other combustible materials that can result in consequential fire (typically ignited by embers) within both the APZ and parts of the building, are eliminated, minimised and/or appropriately located or protected. (Note: The explanatory notes in the Guidelines provide some guidance for achieving this objective and other sources are available. Research shows that consequential fire, ignited by embers, is the primary cause of building loss in past bushfire events); and
- To provide a defensible space for firefighting activities.

B1: Asset Protection Zone (APZ) Dimensions

APZ DIMENSIONS – DIFFERENCES IN REQUIREMENTS FOR PLANNING ASSESSMENTS COMPARED TO IMPLEMENTATION

THE 'PLANNING BAL-29' APZ DIMENSIONS

The 'Planning BAL-29' APZ is not necessarily the size of the APZ that must be physically implemented and maintained by a landowner. Rather, its purpose is to identify if an acceptable solution for planning approval can be met i.e., can a specified minimum separation distance from bushfire prone vegetation exist.

An assessment against the Bushfire Protection Criteria is conducted for planning approval purposes. To satisfy 'A2.1: Asset Protection Zone', it must be demonstrated that certain minimum separation distances between the relevant building/structure and different classes of bushfire prone vegetation, either exist or can be created and will remain in perpetuity. These minimum separation distances determine the 'Planning BAL-29' APZ dimensions.

Dimensions: The minimum dimensions are those that will ensure the potential radiant heat impact on subject buildings does not exceed 29 kW/m². These dimensions will vary dependent on the vegetation classification, the slope of the land they are growing on and certain other factors specific to the subject site.

Note: For certain purposes associated with vulnerable land uses, the 'Planning BAL-29' APZ may be replaced with dimensions corresponding to radiant heat impact levels of 10 kW/m² and 2 kW/m² and calculated using 1200K flame temperature.

Location: The identified 'Planning BAL-29' APZ must not extend past lot boundaries onto land the landowner has no control over either now or potentially at some point in the future. Limited exceptions include:

- When adjoining land is not vegetated (e.g., built out, roads, carparks, drainage, rock, water body etc.);
- When adjoining land currently or, will in the short term, contain low threat vegetation and or vegetation managed in a minimal fuel condition as per AS 3959:2018 cl. 2.2.3.2. It must be reasonable (justifiable) to expect this low threat vegetation and/or level of management will continue to exist or be conducted in perpetuity and require no action from the owner of the subject lot.

Such areas of land include formally managed areas of vegetation (e.g., public open space / recreation areas / services installed in a common section of land). For specific scenarios, evidence of the formal

commitment to manage these areas to a certain standard may be required and would be included in the BMP.

These areas of land can also be part of the required APZ on a neighbouring lot for which the owner of that lot has a recognised responsibility to establish and maintain; and

- When there is a formalised and enforceable capability and responsibility created for the subject lot owner, or any other third party, to manage vegetation on land they do not own in perpetuity. This would be rare, and evidence of the formal authority would be included in the BMP.

The bushfire consultant's 'Supporting Assessment Detail', that is presented in the assessment against the acceptable solution A2.1, will identify and justify how any adjoining land within the 'Planning BAL-29 APZ will meet the APZ standards. Or otherwise, explain how this condition cannot be met.

THE 'BAL RATING' APZ DIMENSIONS

The applicable BAL rating will have been stated in the BAL Assessment Data section of the BAL Assessment Report or BMP (as relevant). The BAL rating can be assessed as 'determined' or 'indicative' or be 'conditional', dependent of the specific conditions associated with the site and the stage of assessment or planning. It is the eventual assessment of the 'Determined' BAL that will establish both the BAL rating that is to apply and its corresponding 'BAL Rating' APZ dimensions.

Dimensions: The minimum dimensions of the 'BAL Rating' APZ to be established and maintained will be those that correspond to the determined BAL rating for the subject building/structure that has accounted for surrounding vegetation types, the slope of the land they are growing on and certain other factors specific to the subject site and surrounding land.

Establishing the 'BAL Rating' APZ will ensure that the potential radiant heat exposure of the building/structure will be limited to the level that the applied construction requirements are designed to resist when that building/structure is required to be constructed to the standard corresponding to the Determined BAL.

Note: For certain purposes associated with vulnerable land uses, the 'BAL Rating' APZ dimensions may be replaced with dimensions corresponding to the specific radiant heat impact levels of 10 kW/m² and 2 kW/m² and calculated using 1200K flame temperature.

Location: The same conditions will apply as for the 'Planning BAL-29' APZ.

THE 'LOCAL GOVERNMENT' APZ DIMENSIONS

Some Local Government's establish the dimensions of the APZ that must be established surrounding buildings in their annual Firebreak/Hazard Reduction Notice. Or for a specific site they may establish a maximum allowable dimension (typically that corresponding to BAL-29). When established, the landowner will need to be comply with these.

THE 'REQUIRED' APZ DIMENSIONS

This is the APZ that is to be established and maintained by the landowner within the subject lot and surrounding the subject building(s). It will be identified on the Property Bushfire Management Statement when it is required to be included in this Report/Plan.

Dimensions: The 'Required APZ' dimensions are the minimum (or maximum when relevant) distances away from the subject building(s) that the APZ must extend. These distances will not necessarily be the same all around the building(s). They can vary and are dependent on the different vegetation types (and their associated ground slope) that can exist around the building(s), and specific local government requirements. The dimensions to implement are determined by:

- A. The 'BAL Rating APZ' of the subject building(s) when distances are greater than 'B' below (except when 'B' establishes a maximum distance); or
- B. The 'Local Government' APZ' derived from the Firebreak/Hazard Reduction Notice when distances are greater than 'A' above, other than when a maximum distance is established, in which case this will apply; or
- C. A combination of 'A' and 'B'.

Location: The same conditions will apply as for the 'Planning BAL-29' APZ.

B1.1: THE APZ DIMENSIONS REQUIRED TO BE IMPLEMENTED BY THE LANDOWNER

DETERMINATION OF THE 'REQUIRED' APZ DIMENSIONS TO BE IMPLEMENTED AND MAINTAINED BY LANDOWNER WITHIN THEIR LOT											
Relevant Buildings(s)	Vegetation Classification [Refer to Fig 3.1]		Minimum Required Separation Distances from Building to Vegetation (metres)							The 'Required' APZ Dimensions [see note]	
			Established by the 'BAL Rating' APZ Dimension				Established by the "Local Government" APZ Dimension		N/A		
			Determined Radiant Heat Impact	Stated 'Indicative' or 'Conditional' BAL				Firebreak / Hazard Reduction Notice			Maximum Allowed
				BAL-29	BAL-19	BAL-12.5	BAL-LOW				
Area	Class										
Proposed Dan Murphy's	1	(D) Scrub	BAL-12.5	13-<19	19-<27	27-<100	100<	20	N/A	20	
	2	(B) Woodland		14-<20	20-<29	29-<100	100<	20	N/A	20	
	3	(G) Grassland		8-<12	12-<17	17-<50	50<	20	N/A	20	
	4	(A) Forest		21-<31	31-<42	42-<100	100<	20	N/A	21	
	5	(C) Shrubland		9-<13	13-<19	19-<100	100<	20	N/A	20	
	6	Excluded cl 2.2.3.2(e & f)		-	-	-	-	-	-	-	-
Proposed Tavern	1	(D) Scrub	BAL-12.5	13-<19	19-<27	27-<100	100<	20	N/A	20	
	2	(B) Woodland		14-<20	20-<29	29-<100	100<	20	N/A	20	
	3	(G) Grassland		8-<12	12-<17	17-<50	50<	20	N/A	20	
	4	(A) Forest		21-<31	31-<42	42-<100	100<	20	N/A	21	
	5	(C) Shrubland		9-<13	13-<19	19-<100	100<	20	N/A	20	
	6	Excluded cl 2.2.3.2(e & f)		-	-	-	-	-	-	-	-

Note: The 'Required' APZ Dimension corresponding to each area of vegetation is the greater of the 'BAL Rating' or the 'Firebreak/Hazard Reduction Notice' APZ dimensions - unless a local government maximum distance(s) is established as a result of their environmental assessment of the subject site. The area of the APZ will also be limited to the subject lot boundary unless otherwise justified in this Report/Plan. Final determination of the dimensions will require that any indicative or conditional BAL becomes a 'Determined' BAL.

Comments: A 3-metre-wide firebreak is to be installed and maintained from 1st of November until the 30th of April every year. If it is not possible to install and maintain a firebreak, then all buildings are required to be a minimum of 5 metres from the external boundaries. The City of Wanneroo Firebreak Mitigation Notice also states that "Additional mitigation work may be required by a Fire Control Officer to maintain a 20-metre asset protection zone around buildings".

B2: The Standards for the APZ as Established by the Guidelines (DPLH, v1.4)

Within the Guidelines (source: <https://www.wa.gov.au/government/document-collections/state-planning-policy-37-planning-bushfire-prone-areas>), the management Standards are established by:

- Schedule 1: Standards for Asset Protection Zones (see extract below) established by the Guidelines; and
- The associated explanatory notes (Guidelines E2) that address (a) managing an asset protection zone (APZ) to a low threat state (b) landscaping and design of an asset protection zone and (c) plant flammability.

Guidelines for
Planning in
Bushfire
Prone Areas


71

ELEMENT 2: SITING AND DESIGN OF DEVELOPMENT

SCHEDULE 1: STANDARDS FOR ASSET PROTECTION ZONES

OBJECT	REQUIREMENT
Fences within the APZ	<ul style="list-style-type: none"> • Should be constructed from non-combustible materials (for example, iron, brick, limestone, metal post and wire, or bushfire-resisting timber referenced in Appendix F of AS 3959).
Fine fuel load (Combustible, dead vegetation matter <6 millimetres in thickness)	<ul style="list-style-type: none"> • Should be managed and removed on a regular basis to maintain a low threat state. • Should be maintained at <2 tonnes per hectare (on average). • Mulches should be non-combustible such as stone, gravel or crushed mineral earth or wood mulch >6 millimetres in thickness.
Trees* (>6 metres in height)	<ul style="list-style-type: none"> • Trunks at maturity should be a minimum distance of six metres from all elevations of the building. • Branches at maturity should not touch or overhang a building or powerline. • Lower branches and loose bark should be removed to a height of two metres above the ground and/or surface vegetation. • Canopy cover within the APZ should be <15 per cent of the total APZ area. • Tree canopies at maturity should be at least five metres apart to avoid forming a continuous canopy. Stands of existing mature trees with interlocking canopies may be treated as an individual canopy provided that the total canopy cover within the APZ will not exceed 15 per cent and are not connected to the tree canopy outside the APZ.

Figure 19: Tree canopy cover – ranging from 15 to 70 per cent at maturity



<p>Shrub* and scrub* (0.5 metres to six metres in height). Shrub and scrub >6 metres in height are to be treated as trees.</p>	<ul style="list-style-type: none"> • Should not be located under trees or within three metres of buildings. • Should not be planted in clumps >5 square metres in area. • Clumps should be separated from each other and any exposed window or door by at least 10 metres.
<p>Ground covers* (<0.5 metres in height. Ground covers >0.5 metres in height are to be treated as shrubs)</p>	<ul style="list-style-type: none"> • Can be planted under trees but must be maintained to remove dead plant material, as prescribed in 'Fine fuel load' above. • Can be located within two metres of a structure, but three metres from windows or doors if >100 millimetres in height.
<p>Grass</p>	<ul style="list-style-type: none"> • Grass should be maintained at a height of 100 millimetres or less, at all times. • Wherever possible, perennial grasses should be used and well-hydrated with regular application of wetting agents and efficient irrigation.
<p>Defendable space</p>	<ul style="list-style-type: none"> • Within three metres of each wall or supporting post of a habitable building, the area is kept free from vegetation, but can include ground covers, grass and non-combustible mulches as prescribed above.
<p>LP Gas Cylinders</p>	<ul style="list-style-type: none"> • Should be located on the side of a building furthest from the likely direction of a bushfire or on the side of a building where surrounding classified vegetation is upslope, at least one metre from vulnerable parts of a building. • The pressure relief valve should point away from the house. • No flammable material within six metres from the front of the valve. • Must sit on a firm, level and non-combustible base and be secured to a solid structure.

* Plant flammability, landscaping design and maintenance should be considered – refer to explanatory notes

B3: The Standards for the APZ as Established by the Local Government

Refer to the firebreak / hazard reduction notice issued annually (under s33 of the Bushfires Act 1954) by the relevant local government. It may state Standards that vary from those established by the Guidelines and that have been endorsed by the WAPC and DFES as per Section 4.5.3 of the Guidelines.

A copy of the applicable notice is not included here as they are subject to being reviewed and modified prior to issuing each year. Refer to ratepayers notices and/or the local government's website for the current version.

B4: Vegetation and Areas Excluded from Classification - Ensure Continued Exclusion

AS 3959:2018 establishes the methodology for determining a bushfire attack level (BAL). The methodology includes the classification of the subject site's surrounding vegetation according to their 'type' and the application of the corresponding relevant bushfire behaviour models to determine the BAL.

Certain vegetation can be considered as low threat or managed in a minimal fuel condition and can be excluded from classification. Where this has occurred in assessing the site, the extract from AS3959:2018 below states the requirements that must continue to exist for the vegetation on those areas of land to be excluded from classification (including the size of the vegetation area if relevant to the assessment).

15

AS 3959:2018

2.2.3.2 Exclusions—Low threat vegetation and non-vegetated areas

The following vegetation shall be excluded from a BAL assessment:

- (a) Vegetation of any type that is more than 100 m from the site.
- (b) Single areas of vegetation less than 1 ha in area and not within 100 m of other areas of vegetation being classified vegetation.
- (c) Multiple areas of vegetation less than 0.25 ha in area and not within 20 m of the site, or each other or of other areas of vegetation being classified vegetation.
- (d) Strips of vegetation less than 20 m in width (measured perpendicular to the elevation exposed to the strip of vegetation) regardless of length and not within 20 m of the site or each other, or other areas of vegetation being classified vegetation.
- (e) Non-vegetated areas, that is, areas permanently cleared of vegetation, including waterways, exposed beaches, roads, footpaths, buildings and rocky outcrops.
- (f) Vegetation regarded as low threat due to factors such as flammability, moisture content or fuel load. This includes grassland managed in a minimal fuel condition, mangroves and other saline wetlands, maintained lawns, golf courses (such as playing areas and fairways), maintained public reserves and parklands, sporting fields, vineyards, orchards, banana plantations, market gardens (and other non-curing crops), cultivated gardens, commercial nurseries, nature strips and windbreaks.

NOTES:

- 1 Minimal fuel condition means there is insufficient fuel available to significantly increase the severity of the bushfire attack (recognizable as short-cropped grass for example, to a nominal height of 100 mm).
- 2 A windbreak is considered a single row of trees used as a screen or to reduce the effect of wind on the leeward side of the trees.


APPENDIX C: TECHNICAL REQUIREMENTS FOR VEHICULAR ACCESS

The design/layout requirements for access are established by the acceptable solutions of the Guidelines (DPLH, 2021 v1.4) Element 3 and vary dependent on the access component, the land use and the presence of 'vulnerable' persons. Consequently, the best reference source are the Guidelines. The technical requirements that are fixed for all components and uses are presented in this appendix.

GUIDELINES TABLE 6, EXPLANATORY NOTES E3.3 & E3.6 AND RELEVANT ACCEPTABLE SOLUTIONS

Technical Component	Vehicular Access Types / Components			
	Public Roads	Emergency Access Way ¹	Fire Service Access Route ¹	Battle-axe and Private Driveways ²
Minimum trafficable surface (m)	In accordance with A3.1	6	6	4
Minimum Horizontal clearance (m)	N/A	6	6	6
Minimum Vertical clearance (m)	4.5			
Minimum weight capacity (t)	15			
Maximum Grade Unsealed Road ³	As outlined in the IPWEA Subdivision Guidelines	1:10 (10%)		
Maximum Grade Sealed Road ³		1:7 (14.3%)		
Maximum Average Grade Sealed Road		1:10 (10%)		
Minimum Inner Radius of Road Curves (m)		8.5		

Turnaround Area Dimensions for No-through Road, Battle-axe Legs and Private Driveways ⁴



Passing Bay Requirements for Battle-axe leg and Private Driveway

When the access component length is greater than the stated maximum, passing bays are required every 200m with a minimum length of 20m and a minimum additional trafficable width of 2m (i.e. the combined trafficable width of the passing bay and constructed private driveway to be a minimum 6m).

Emergency Access Way – Additional Requirements

Provide a through connection to a public road, be no more than 500m in length, must be signposted and if gated, gates must be open the whole trafficable width and remain unlocked.

¹ To have crossfalls between 3 and 6%.

² Where driveways and battle-axe legs are not required to comply with the widths in A3.5 or A3.6, they are to comply with the Residential Design Codes and Development Control Policy 2.2 Residential Subdivision.

³ Dips must have no more than a 1 in 8 (12.5% or 7.1 degree) entry and exit angle.

⁴ The turnaround area should be within 30m of the main habitable building.

APPENDIX D: TECHNICAL REQUIREMENTS FOR FIREFIGHTING WATER SUPPLY

D1: Reticulated Areas – Hydrant Supply

The Guidelines state "where a reticulated water supply is existing or proposed, hydrant connection(s) should be provided in accordance with the specifications of the relevant water supply authority."

The main scheme water suppliers / authorities in WA are The Water Corporation, AqWest – Bunbury Water Corporation and Busselton Water Corporation. Various local authority exists in other non-scheme and regional areas. However, most existing fire hydrants are connected to Water Corporation water mains.

Consequently, the hydrant location specifications from The Water Corporation's 'No 63 Water Reticulation Standard' (Ver 3 Rev 15) are provided in the extract below with the key distances relevant to bushfire planning assessments being highlighted. This Standard is deemed to be the baseline criteria for developments and should be applied unless different local water supply authority conditions apply. Other applicable specification will be found in the Standard.

Note: The maximum distance from a hydrant to the rear of a lot/building is generally interpreted as not applicable to large lot sizes where the maximum distance becomes an impractical limitation i.e., typically rural residential areas.

Design Standard DS 63
Water Reticulation Standard



2.2.1.5 Appurtenances

c. Hydrants

Hydrants shall be screw-down hydrant with built-in isolation valve and installed only on DN100 or larger pipes. Hydrants shall be located:

- so that the maximum distance between a hydrant and the rear of a building envelope, (or in the absence of a building envelope the rear of the lot) shall be 120m;
- so that spacing (as measured by hose-run) between hydrants in non-residential or mixed use areas shall be maximized and no greater than 100m;
- so that spacing (as measured by hose-run) between hydrants in residential areas with lots per dwelling <10,000m² shall be maximized and no greater than 200m;
- so that spacing between hydrants (as measured by hose-run) in rural residential areas where minimum lots per dwelling is >10,000 m² (1ha) shall be maximized and no greater than 400m;
- centrally along the frontage of a lot to avoid being under driveways, unless the lot features a frontage 6m or less, in which case it shall be placed to the side opposite the driveway;
- at lots that have the widest frontage in the local area;
- where appropriate at the truncation of road junctions or intersections so that they can serve more than one street and can be readily located;
- on both sides of the major roads at staggered intervals where there are mains on both sides of the road;
- at major intersections on dual multi-lane roads, where two hydrants are to be sited on diagonally opposite corners;
- hydrants should be located at least 20m from traffic calming devices i.e., median slow points or chokers, chicanes, mini traffic circles, and intersection 'pop-outs' to ensure traffic is not impeded;
- in a position not less than 10m from any high voltage main electrical distribution equipment such as transformers and distribution boards, liquefied petroleum gas or other combustible storage;
- directly on top of the main using a tee unless proved to be impractical.