

Fire Management Plan



Rezoning / Subdivision Proposal
Special Residential to Residential
Balance of Title Lots 9164 & 9175
Banksia Grove
City of Wanneroo
June 2015
Version 3

Rezoning / Subdivision Proposal - Special Residential to Residential
Balance of Title Lots 9164 & 9175
Banksia Grove
CITY OF WANNEROO

Front Cover Photo: Aerial photograph of development site (source: nearmap.com)

Report prepared by:

Rohan Carboon B. App. Sci. G. Cert. (Bushfire Protection)
Managing Director
Bushfire Safety Consulting Pty Ltd
P O Box 84
STONEVILLE WA 6081

Mobile: 0429 949 262
Email: enquiries@bushfiresafety.net
Website: www.bushfiresafety.net

June 2015
Version 3

Disclaimer

This report has been prepared in good faith, and is derived from sources believed to be reliable and accurate at the time of publication. Nevertheless, this publication is distributed on the terms and understanding that the author is not responsible for results of any actions taken based on information in this publication or for any error in or omission from this publication

Table of Contents

Executive Summary	1
1. Introduction	2
1.1 The Proposal	3
1.2 Objectives	3
2. Statutory and Policy Framework	4
2.1 Bush Fires Act	4
2.2 State Planning Policy No. 3.4 Natural Hazards and Disasters	4
2.3 Planning for Bush Fire Protection Guidelines (2010)	4
3. Description of the Area	5
3.1 Description of the Subject Land	5
3.2 Fire Climate	5
3.3 Bushfire Fuels	7
3.4 Assets	7
3.5 Access	8
3.6 Water Supply	8
3.7 Bushfire History	8
4. Bushfire Hazard Assessment	9
4.1 Vegetation Type and Class	9
4.2 Slope	10
4.3 The Bushfire Hazard Assessment Levels	11
5. Fire Mitigation Strategies	11
5.1 Element: Location of the Development	12
5.2 Element: Vehicular Access	12
5.3 Element: Water	13
5.4 Element: Siting of the Development	14
5.4.1 Building Siting and Predicted Bushfire Attack Levels	15
5.4.2 Landscaping Considerations	17
5.5 Design of the Development	18
5.6 Public Education and Community Awareness	18
5.7 Community Fire Refuges and Fire Safer Areas	19
6. Conclusion	20

6.1 Compliance Checklist for Performance Criteria and Acceptable Solutions	20
7. Implementing the Fire Management Plan	23
7.1 Developer's Responsibilities	23
7.2 Property Owners' Responsibilities	24
7.3 City of Wanneroo's Responsibilities	24
7.4 FESA's Responsibilities	24
8. References	26
9. Appendices	28
Appendix A: Site location Plan	
Appendix B: Site Plan	
Appendix C: Local Structure Plan	
Appendix D: Subdivision Concept Plan	
Appendix E: Vegetation Classification - existing conditions	
Appendix F: Bushfire Hazard Rating - existing conditions	
Appendix G: Vehicular Access	
Appendix H: Building Siting and BPZ	
Appendix I: Maximum Indicative BAL Ratings	

Executive Summary

This Fire Management Plan has been prepared to support the proposed rezoning and future subdivision of land between proposed Moort Rise and Pinjar Road, Banksia Grove. These lots are the subject of WAPC subdivision approvals WAPC 147352 & 146580. A Fire Management Plan produced by Bushfire Safety Consulting Pty Ltd was approved to clear development conditions for both of these previous subdivision approvals.

The development site has been re-assessed for vegetation class and bushfire hazard rating levels. It has been determined that all proposed buildings will fall within the acceptable level of risk. Bushfire Attack Level BAL-29 is not exceeded for any of the 38 proposed dwellings that form part of the subdivision concept plan. All dwellings will be sited a minimum of 20 metres from permanent classified vegetation and bushfire hazard.

This Plan includes a table on page 20 showing responses to the Performance Criteria outlined in the Planning for Bushfire Protection Guidelines - Edition 2 (WAPC et al. 2010).

Currently, the site's bushfire hazard level is rated as extreme, but as the development occurs, vegetation will be removed and managed and hazard levels will become lower. Residual hazard will remain in the adjoining property to the west of the site. Areas of hazard south of the development have been approved for subdivision so existing hazard is temporary and will be removed.

Access and egress from all the proposed 38 lots will adequately service the development.

Water is adequate for residential needs and for a water supply during fire emergencies by the provision of fire hydrants on Pinjar and Redheart Roads and Moort Rise.

Both the City of Wanneroo and FESA have a public education program to raise the community's awareness to its responsibilities regarding preparing homes from a bushfire attack and what to do if an event happens.

If there is a bushfire within or near the site, implementing this Fire Management Plan will reduce the threat to residents and firefighters.

1. Introduction

The site subject to this Fire Management Plan (FMP) is the balance of title lots 9164 & 9175 in Banksia Grove in the City of Wanneroo. The site includes a strip of land 5.9984ha in size which is currently undeveloped. It is located in Banksia Grove which is located 30 kilometres north of Perth and 5 kilometres north-east of the Wanneroo Townsite (Appendix A). The site is currently undeveloped except for some clearing to accommodate Moort Rise. The site contains Banksia woodland vegetation (Appendix B). Banksia Grove residential development when complete will be home to approximately 12,000 residents, housed in 4,000 dwellings as outlined in the Banksia Grove Structure Plan (Appendix C).

Banksia Grove is an urban development initiative involving the Western Australian Government through the Department of Housing, partnering with the Walker Corporation and PRM Property Group Pty Ltd.

The site is zoned "Special Residential" under the City of Wanneroo's District Planning Scheme No. 2. An application is now lodged to rezone the site from special residential to residential to allow further subdivision.

As part any future subdivision application for the land, the Department of Fire and Emergency Services (DFES) is expected to request the previous approved Fire Management Plans over the site are updated prior to determination.

This FMP has been prepared to satisfy this anticipated condition. This Plan provides responses to the performance criteria that fulfil the intent of the bushfire hazard management issues outlined in the Planning for Bushfire Protection Guidelines - Edition 2 (WAPC et al. 2010).

Community bushfire safety is a shared responsibility between governments, fire agencies, communities and individuals. The planning and building controls outlined in this Plan, if fully implement, will mitigate the risk to people and property; however, it will not remove the risk. How people interpret the risk, prepare and maintain the property and buildings and what decisions and actions they take (i.e. evacuate early or stay and defend or other) greatly influence the outcome of a bushfire.

1.1 The Proposal

The proposed Special Residential Subdivision Concept Plan (Appendix D) outlines 38 proposed lots will be created, which will average each 1578m² in size.

It is a linear shaped development extending north south sandwiched between the existing urban environment in the east and the woodland vegetated rural residential or horticultural lots in Carramar to the west.

The project management team, which commenced work in December 2005, will develop the entire Banksia Grove Project over a 10 to 12 year period.

1.2 Objectives

The purpose of this FMP is to address bushfire management issues within the proposed development. If there is a bushfire within or near the site, implementing the FMP will reduce the threat to residents and firefighters.

Achievable and measurable goals of this Plan include ensuring:

- The development is located in an area where the bushfire hazard does not present an unreasonable level of risk to life and property
- Vehicular access to the development is safe, if there is a bushfire occurring
- Water is available to the development so that life and property can be defended from bushfire
- The development is sited to minimise the effects of a bushfire, and
- The development design will minimise the effects of a bushfire.

This document sets out the roles and responsibilities of the developer, residents, the City of Wanneroo and the Fire and Emergency Services Authority (FESA). It is important that the measures and procedures outlined in this FMP are reviewed as necessary.

This FMP includes:

- A description of the site, the surrounding area, fire climate and bushfire history
- A summary of research into the related effects of a bushfire
- A bushfire hazard assessment
- Addressing vehicular access
- Siting buildings to include building protection zones
- Water supply, and
- Maps and plans of fire reduction measures.

2. Statutory and Policy Framework

Relevant key legislation, policy and guidelines include the following:

2.1 Bush Fires Act

The Act sets out provision to diminish the dangers resulting from bushfires, prevent, control and extinguish bushfires and for other purposes. The Act addresses various matters including prohibited burning times, enabling Local Government to require land owners/occupiers to plough or clear firebreaks, to control and extinguish bushfires and establish and maintain Bush Fire Brigades.

2.2 State Planning Policy No. 3.4 Natural Hazards and Disasters

The objectives of this Policy are to:

- Include planning for natural disasters as a fundamental element when preparing all statutory and non-statutory planning documents, specifically town planning schemes and amendments, and local planning strategies, and
- Use these planning instruments to minimise the adverse effects of natural disasters on communities, the economy and the environment.

The Policy determines those areas that are most vulnerable to bushfire and where development is appropriate and not appropriate. The provisions and requirements contained in Planning for Bush Fire Protection Guidelines - Edition 2 (WAPC et al. 2010) were used in this determination.

2.3 Planning for Bush Fire Protection Guidelines (2010)

These Guidelines were prepared by FESA, the Western Australian Planning Commission (WAPC) and the Department of Planning. The document is the foundation for fire risk management planning on private land in Western Australia.

The document addresses important fire risk management and planning issues and sets out performance criteria and acceptable solutions to minimise the risk of bushfires in new subdivisions and developments. It addresses management issues including the location, design and siting of the development, vehicular access and water.

3. Description of the Area

Banksia Grove is a relatively new suburb located within the City of Wanneroo. When complete, Banksia Grove will be home to 4 schools, restaurants, cafes and retail outlets. The project will create over 4000 home sites and approximately 12,000 residents will call it home by 2020. Banksia Grove had a population of 4718 at the 2011 census.

The subject land is bounded by urban development to the north and east and rural residential bush blocks and horticultural land in Carramar to the west.

3.1 Description of the Subject Land

The subject land is 5.9984 ha in size, being approximately 75m wide and 928m long. The linear shape of the development site will allow 38 “Special Residential” lots to be created.

This FMP focuses on the subject land and immediate surrounding area (Appendix B).

In summary this land is:

- Undeveloped and generally vegetated in low woodland with an understorey of open heath
- Gently sloping, downhill to the west
- Surrounded to the north and east by residential development and low woodland to the south and west.

3.2 Fire Climate

The behaviour of bushfires is significantly affected by weather conditions and they burn more aggressively when high temperatures combine with low humidity and strong winds.

In Perth and surrounding coastal areas, the fire risk is greatest from summer through autumn, when the moisture content in vegetation is low. Summer and autumn days with high temperatures, low humidity and strong winds are particularly conducive to the spread of fire. This threat is enhanced if thunderstorms develop accompanied by lightning and little or no rain.

Research indicates that virtually all house losses occur during severe, extreme or catastrophic conditions (i.e when the Fire Danger Index is over 50) (Blanchi et al. 2010).

The Bureau of Meteorology website (www.bom.gov.au/weather/wa/sevwx/perth/bushfires.shtml) states that extreme fire weather conditions in the Perth region typically occur with strong easterlies or north easterly winds associated with a strong high to the south of the state and a trough offshore. Easterly winds represent about 60 per cent of extreme fire weather days (events) compared to less than 5 per cent associated with southerly winds. About 15 per cent of Perth events occurred in a westerly flow following the passage of a trough. Very dangerous fire weather conditions often follow a sequence of hot days and easterly winds that culminate when the trough deepens near the coast and moves inland. Winds can change from easterly to northerly and then to westerly during this sequence of climatic events.

Data from the Bureau of Meteorology weather station at Swanbourne (28 km south of the study site) indicate the area experiences warm dry summers and cool wet winters (Figure 1), and is classified as a Mediterranean climate. Mean maximum temperatures vary from 31 degrees Celsius in February to 18 degrees Celsius in July.




Figure 1: Mean maximum recorded temperatures and mean rainfall for Swanbourne Meteorology Station between 1993 and 2010

The site is 7.5 kms from the coast and is significantly influenced by land and sea breezes. These are created by the daily heating and cooling of the land surface next to the ocean. The sea breeze occurs when the air over the land heats up and becomes more buoyant and rises, denser moist air over the ocean then flows inland. Sea breezes can strengthen prevailing wind, reduce it or even reverse it, depending on the strength and direction of the two airstreams (Cheney and Sullivan 2008).

Data from the Bureau of Meteorology weather station at Swanbourne indicate that the predominant winds in the summer months at 3 pm near the study site are south-

westerlies (Figure 2). Wind strength, direction and frequency of the south-west wind is clearly dominant and occurs 70-80 per cent of the time. Winds from the west and south occur < 10 per cent of the time.




Figure 2: Rose of wind direction and wind speed in km/hr for December, January and February between 1993 and 2010 at the Swanbourne Bureau of Meteorology Station

Interpreting Figure 2 - Wind speed Vs Direction Plot

Wind roses summarise the occurrence of winds at a location, showing their strength, direction and frequency. The percentage of calm conditions is represented by the size of the centre circle - the bigger the circle, the higher is the frequency of calm conditions. Each branch of the rose represents wind coming from that direction, with north to the top of the diagram. Eight directions are used. The branches are divided into segments of different thickness and colour, which represent wind speed ranges in that direction. Speed ranges of 10 km/hr are used. The length of each segment within a branch is proportional to the frequency of winds blowing within corresponding range of speeds from that direction (BOM 2010).

3.3 Bushfire Fuels

The study site is vegetated in low woodland comprised of predominantly banksia and sheoak species. An intact heath understorey (open shrubland) exists under the low woodland canopy. In the north east corner, scrub vegetation exists and canopy foliage cover is less than 10%. Bushfire fuels will be significantly reduced on the site when building envelopes and building protection zones are established.

3.4 Assets

When the site is fully developed it will contain 38 new lots that will occupy the transitional zone between urban lots to the east and rural residential lots to the west.

There are dwellings and development east and north of this site that are and will be within 100 metres of classified vegetation. These dwellings are also at risk of bushfire attack.

3.5 Access

The subdivision will be serviced by Moort Rise (a 14 metre wide road reserve) on the western boundary. Access onto individual lots will be via driveways from Moort Rise. Pinjar Road does not provide access to the lots but immediately adjoins the eastern boundary. Moort Rise and Donia Way provide through access and two access ways for residents and emergency services at all times. The residential development east and north of the site provide numerous access options.

3.6 Water Supply

Reticulated water is provided to the entire development. Several fire hydrants exist on Pinjar Road and one on Redheart Road. Three fire hydrants are proposed in Moort Rise. This will adequately supply the small subdivision.

3.7 Bushfire History

A recent study has concluded that bushfires may have been in the Australian Landscape for 50 million years longer than previously thought. The adaption of eucalypts that allows them to recover from bushfires has been traced back more than 60 million years (Crisp et al. 2011), indicating fire has been in the Australian landscape since that time.

Anthropological and historical evidence suggests that much of the Swan Coastal Plain was regularly burnt by the Aborigines until the middle of the nineteenth century (Hallam 1975, Abbott 2003).

Bushfires are common in the City of Wanneroo, in the 2009-2010 financial year, the volunteer fire brigades attended to 132 fires (City of Wanneroo 2010). More recent bushfire history includes:

- 10 January 2010, a fire started near Neaves Road and old Yanchep Road. A bushfire “Advice” was issued for people in Banksia Grove. No properties were threatened and the “All Clear” was issued at the 4.30pm on the same day.

- 15 January 2015, a fire started near Bullsbrook and travelled on strong easterly winds crossing Neaves Road and pushing north of the Banksia Grove estate. Two derelict homes were destroyed and over 7000 hectares burnt.

Areas of native vegetation surrounded by residential estates are susceptible to frequent bushfires due to the high risk of arson and great potential for accidental ignitions (Walker 1981, Burrows and Abbott 2003).

4. Bushfire Hazard Assessment

Assessing bushfire hazards at a strategic level takes into account the predominant class of vegetation on the site and surrounding area for a minimum of 100 metres. The vegetation class map for the site and surrounding area for a minimum of 100 m is shown in Appendix E. Fuel layers in a typical forest environment can be broken down into 5 obvious segments (Figure 3). These defined fuel layers are used in the following descriptions regarding vegetation types, fuel structure and bushfire hazard levels.




Figure 3 : The five obvious fuel layers in a forest environment that could be associated with fire behaviour (Gould et al. 2007)

4.1 Vegetation Type and Class

The site assessment undertaken for this study identified two vegetation classes as identified and mapped in Appendix E. The site is 90% covered in a low woodland with canopy heights in the range of 5 - 10m. The dominant genus are Banksia, Eucalyptus and Allocasuarina species (Figure 4). Some trees have poor canopy health. The low

woodland supports a healthy and intact open heath (shrubland) elevated vegetation layer and near surface fuels such as Hibbertia species.

A small area in the north east corner of the site contains scrub vegetation. The dominant genus is Leptospermum (Tea tree) and Adenanthos (Wollybush) which grows in clumps 2-3 metres high (Figure 5).

The low woodland vegetation type extends south of the site and into the adjoining rural residential properties to the west.

There is no vegetation north or east of the site as these areas have been cleared and developed.

Managed vegetation is also located in small areas surrounding existing dwellings on the rural residential lots west of the site. Residents have established gardens and irrigated lawns surrounding their homes.

Vegetation will be removed to create the building envelope on each lot and an overlapping building protection zone will reduce fuel loads across most of the site. The development will also reduce overall bushfire hazard on the site.



Figures 4 & 5: Low woodland vegetation with an open shrubland elevated layer (left) and scrub vegetation dominated by tea tree species (right)

4.2 Slope

The site slopes downslope to the west at an average gradient of 3-4 degrees. This is consistent across the entire site. Contour lines with intervals of 1 metre can be seen in the plan in Appendix H.

4.3 The Bushfire Hazard Assessment Levels

The vegetation class map (Appendix E) outlines the dominant vegetation types on the study site and surrounding area for a minimum of 100 m. Descriptions of the vegetation class structure and dominant species are outlined in section 5.1 Vegetation Type and Class. The bushfire hazard assessment levels were determined using Appendix 1 of the Planning for Bushfire Protection Guidelines - Edition 2 (WAPC et al. 2010).

The study site has a bushfire hazard rating of extreme due to the extent of low woodland and scrub vegetation. Low bushfire hazard occurs in areas of managed vegetation such as irrigated lawns, market garden, roads and residential areas.

As the site develops, building envelopes and building protection zones will be established and vegetation will be removed. This will lead to a reduction in the bushfire hazard. Long-term hazard will remain in the adjoining rural residential properties to the west.

The bushfire hazard rating map for the site and surrounding area is shown in Appendix F.

5. Fire Mitigation Strategies

This report adopts an acceptable solution and performance-based system of control for each bushfire hazard management issue. It is consistent with Appendix 2 of the Planning for Bushfire Protection Guidelines - Edition 2 (WAPC et al. 2010). The management issues are:

- Location of the development
- Vehicular Access
- Water
- Siting of the development, and
- Design of the development.

Acceptable solutions are provided for four out of the five management issues and each illustrates one example of satisfactorily meeting the corresponding performance criteria. A performance-based approach is provided for one management issue.

5.1 Element: Location of the Development

Intent

To ensure that development/intensification of land use is located in areas where bush fire hazard does not present an unreasonable level of risk to life and property.

Acceptable Solution

Bushfire hazard levels are rated as extreme on the development site due to the predominant vegetation being low woodland. Low bushfire hazard occurs where managed vegetation exists surrounding dwellings, unvegetated areas and the urban environment.

The maximum Bushfire Attack Level (BAL) is predicted to be BAL-29 for any dwelling. All dwellings achieve a minimum 20 metre separation from the low woodland west of the site.

Hazard Separation Zones (HSZ's) exist to reduce fire intensity on dwellings. Construction standards will be increased to align with the appropriate Bushfire Attack Level (BAL) to offset the requirement for a HSZ because the small lot sizes do not permit their inclusion.

The site will be provided with an adequate water supply and access to fight fires and all exposed dwellings will be constructed to AS 3959 standards.

5.2 Element: Vehicular Access

Intent

To ensure vehicular access serving a subdivision development is safe if a bushfire occurs.

Background

The development site is located adjacent to an urban area with a substantial network of public roads in a low bushfire hazard environment. Pinjar Road borders the eastern boundary of the entire site and is a two-lane public road providing two access routes.

The western perimeter road (Moort Rise) provides access to all lots. The public road network surrounds the entire site and is outlined in Appendix G.

This proposal complies with the performance criteria by applying the following acceptable solutions:

Acceptable Solution A2.1: Two Access Routes

All 38 lots within the subdivision have direct driveway access to Moort Rise on the western boundary of each lot. This road provides two access routes from all lot driveways because Moort Rise is a through road. This complies with the requirements for two access routes.

Acceptable Solution A2.2: Public Roads

Pinjar Road and the western boundary road reserve will comply with minimum standards for public roads. The following public road standards for Moort Rise and Donia Way apply:

- Minimum trafficable surface: 6 m
- Horizontal clearance: 6 m
- Vertical clearance: 4 m
- Maximum grades: 1 in 8
- Maximum grades over 50 m: 1 in 5
- Maximum average grade: 1 in 7
- Minimum weight capacity: 15 tonnes
- Maximum crossfall: 1 in 33
- Minimum inner radius of curves: 12 m

5.3 Element: Water

Intent

To ensure water is available to the development to enable life and property to be defended from bushfire.

Acceptable Solution

The development is provided with a reticulated water supply, together with fire hydrants, that meet the specifications of the Water Corporation and FESA.

Residential dwellings (Class 1a) require fire hydrants to be sited within (or every) 200 m in land zoned residential. Three fire hydrants currently exist on adjacent public roads, two are located on Pinjar Road and a further hydrant is located on Redheart Road north of the site. They are located within 200m of each other and no additional hydrants are required to service the development.

A number of fire hydrants will also be located on Moort Rise. Fire services require ready access to an adequate water supply during fire emergencies.

5.4 Element: Siting of the Development

Intent

To ensure the siting of the development minimises the level of bushfire impact.

Acceptable Solution: Building Protection Zone (BPZ)

One of the most important fire protection measures influencing the safety of people and property is to create a BPZ around buildings. The building protection zone is a low fuel area immediately surrounding a building. Non-flammable features such as driveways, roads, road reserves, footpaths, lawn or landscaped gardens (including deciduous trees) can form parts of a BPZ.

World first research into land management and house loss during the Black Saturday Victorian bushfires concluded that the action of private landholders, who managed fuel loads close to their houses, was the single most important factor to determine house survival when compared with other land management practices, such as broad scale fuel reduction burning remote from residential areas (Gibbons et al. 2012).

Creating a BPZ will ensure vegetation and fuels, within close proximity to dwellings, are managed to reduce predicted radiant heat flux levels and improve the survival of buildings.

Managing vegetation in the BPZ has two main purposes:

- To reduce direct flame contact and radiant heat from igniting the building during the passage of a fire front, and
- To reduce ember attack and provide a safer space for people to defend (if required) before, during and after a fire front.

A permanent BPZ will be established for 20m minimum to the east of all dwellings. The internal BPZ will be 15 metres wide west of the dwellings and this will be in addition to the 14 metre wide Moort Road reserve providing a total 29 metre BPZ west of the dwellings. The BPZ will overlap between lots creating a break in the fuel loads and protection for dwellings from an approaching fire front west of the site.

The lots are 20-24 metres wide meaning an internal 20m BPZ cannot be accommodated within each individual lot. This is resolved by having an overlapping BPZ that will connect lots north and south throughout the subdivision.

A strip of remnant vegetation could be retained on the eastern perimeter boundary of all lots to screen dwellings from Pinjar Road beyond the 20m BPZ, however this will be dependent on required site works. The width of this vegetation strip will vary between 10-13.5 metres depending on the depth of individual lots. The overlapping BPZ and building envelope is outlined in Appendix H.

The BPZ must be established by the developer and maintained by future land owners to the following standards:

- Width: 20 m minimum to the west and east of all dwellings and including Moort Rise reserve as indicated in Appendix H
- Fuel load: reduced to and maintained at 2 tonnes per hectare
- All tree crowns are a minimum of 10 m apart
- All trees to have lower branches pruned to a height of 2 m
- All tall shrubs or trees are not to be located within 2 m of a building (including windows)
- No tree crowns or foliage is to be within 2 m of any building, this includes existing trees and shrubs and new plantings
- All fences and sheds are constructed with non-combustible materials (i.e. colorbond, brick or limestone)
- All shrubs to contain no dead material within the plant
- No tall shrubs are to be in clumps within 3 m of the building
- No trees are to contain dead material in the crown or on the bole.

By achieving these standards, it will be possible to construct dwellings to an appropriate standard (i.e. BAL-29 or less) under the Australian Standard (AS 3959-2009) Construction of buildings in bushfire-prone areas. A Hazard Separation Zone is not able to be included in the design due to the small lot sizes. The removal of this design feature is offset by an increase in construction standards and compliance with AS 3959 and BAL-29 is not exceeded.

5.4.1 Building Siting and Predicted Bushfire Attack Levels

The following Bushfire Attack Level (BAL) assessment demonstrates that the fuel management surrounding dwellings achieves acceptable levels of risk.

The AS 3959-2009 has six categories of Bushfire Attack Level, namely BAL-LOW, BAL-12.5, BAL-19, BAL-29, BAL-40 and BAL-FZ. These categories are based on heat flux exposure thresholds.

The method for determining the BAL involves a site assessment of vegetation and local topography. The assumed Fire Danger Index (FDI) for Western Australia is 80. The BAL identifies the appropriate construction standard that applies as a minimum standard in Construction of buildings in bushfire-prone areas (AS 3959-2009).

Methodology and Assumptions

The following BAL examples were determined using the methodology in Appendix A of AS 3959-2009. This methodology is also outlined in the Planning for Bush Fire Protection Guidelines. Example BAL assessments were undertaken in six representative locations adjacent to bushfire hazard (Appendix H). The results of these assessments are shown in Table 1.

The criteria to determine the BAL is outlined as follows:

Designated FDI : 80
 Flame Temperature : 1090
 Slope : Flat & Downslope 3 - 4 degrees (See Table 1)
 Vegetation Class : Woodland
 Setback distances : See Table 1

Area of Classified Vegetation	Vegetation Classification	Setback Distance	Effective Slope (degrees)	BAL Rating
West of the site	Woodland	29-<35 metres	Downslope 3-4	BAL-19
		35-<100 metres	Downslope 3-4	BAL-12.5
South of the site	Woodland	16-<20 metres	Flat	BAL-29
	Woodland	20-<29 metres	Flat	BAL-19
	Woodland	29-<100	Flat	BAL-12.5

Table 1: Bushfire Attack Level (BAL) Assessment for the site (See Appendix H for site details)

A dwelling with a 16m setback between woodland vegetation with no effective slope will achieve a BAL rating of BAL-29. A dwelling with a setback distance between 29m and 35m with downslope 3-4 degrees will achieve a BAL rating of BAL-19. A dwelling with a setback greater than 35 metres will achieve a BAL rating of BAL-12.5. All

provide acceptable solutions because construction standards will be increased to mitigate the increased exposure consistent with AS3959 (Table 1).

A Bushfire Attack Level of BAL-12.5 means the risk is considered to be low. The construction elements are expected to be exposed to a radiant heat flux not greater than 12.5kW/m^2 . There is a risk of ember attack and burning debris ignited by windborne embers and a likelihood of exposure to radiant heat (Standards Australia 2009). The recommended construction sections are 3 and 5 in AS 3959-2009.

A Bushfire Attack Level of BAL-19 means the risk is considered to be moderate. The construction elements are expected to be exposed to a radiant heat flux not greater than 19kW/m^2 . There is a risk of ember attack and burning debris ignited by windborne embers and a likelihood of exposure to radiant heat (Standards Australia 2009). The recommended construction sections are 3 and 6 in AS 3959-2009.

A Bushfire Attack Level of BAL-29 means the risk is considered to be high. The construction elements are expected to be exposed to a radiant heat flux not greater than 29kW/m^2 . There is an increased risk of ember attack and burning debris ignited by windborne embers and a likelihood of exposure to an increased level of radiant heat (Standards Australia 2009). The recommended construction sections are 3 and 7 in AS 3959-2009.

This example assessment demonstrates that all proposed buildings will fall within the acceptable level of risk (i.e. BAL-29 and lower) and will have construction standards increased to meet AS 3959 requirements. All lots require a BAL assessment at building licence application stage to confirm accurate construction standard requirements as the exact location of the dwelling is required in order to confirm BAL ratings.

5.4.2 Landscaping Considerations

Landscaping can both assist in the survival of the building and be a determining measure in its destruction. Landscaping can protect buildings by forming a barrier or deflector for windborne debris and radiant heat. It can also bring the fire directly to the building so a degree of care needs to be exercised when selecting and locating landscaping.

All plants will burn under the right conditions and plants do not achieve a “fire resistance level” to meet the Building Code of Australia (BCA). Placing plants too close to a building, under timber decks or next to windows will provide a direct threat

to the building. Having a clearance around the building will achieve the desired effect of creating a break between the vegetation and the building. A pathway around the building may be one way to achieve this requirement. The landscaping can then be provided further out from the building.

Bark chips and combustible mulch near a building is not recommended and is a particular problem when the windows have low sill heights. The FESA document titled “Plant Guide within the Building Protection Zone” provides a useful list of species and spacing requirements to achieve compliance with vegetation within a building protection zone in the Swan Coastal Plain. It can provide guidance for appropriate revegetation of the site.

Work from Ramsay and Rudolf (2003) has identified 14 major plant attributes that assist people to determine suitable plant species for gardens surrounding buildings (i.e. in the building protection zone). This is a useful reference book for residents to plan their garden design and select suitable plant species.

5.5 Design of the Development

Performance Criteria

The design of the development is appropriate to the level of bushfire hazard that applies to the site.

Acceptable Solution

All on site development is to comply with the performance criteria or acceptable solutions 1 - 4 in “Planning for Bushfire Protection” Guidelines. The buildings are to comply with AS 3959-2009 Construction of buildings in bushfire-prone areas and the City of Wanneroo has the responsibility to ensure dwellings meet this standard.

The predicted highest BAL level for any dwelling is BAL-29 which will be mitigated by compliance with the Australian Standard AS3959.

5.6 Public Education and Community Awareness

Community bushfire safety is a shared responsibility between individuals, the community, government and fire agencies. FESA has an extensive Community Bushfire Education Program including a range of publications, a website and Bushfire Ready Groups. The 30 page booklet Prepare, Act, Survive provides excellent advice

on preparing for and surviving the bushfire season. Other downloadable brochures include 'Fire Danger Ratings and what they mean for you' and 'Bushfire Warnings and what you should do'.

The City of Wanneroo's website and local bushfire brigades provide bushfire safety advice to residents. The website provides links to the downloadable brochure 'Protect Your home and Property from Bushfires' (found at: http://www.wanneroo.wa.gov.au/Residents/Fire_Services). It also provides details on how to become a volunteer for the local Bush Fire Brigade.

Banksia Grove residents are eligible for membership in the Wanneroo Bush Fire Brigade. Professional, qualified consultants also offer bushfire safety advice and relevant services to residents and businesses in high risk areas.

5.7 Community Fire Refuges and Fire Safer Areas

There are no designated Community Fire Refuges in the City of Wanneroo. However, at the time of an emergency, the relevant authorities can select an evacuation centre and FESA, the City and Police will provide this information to residents.

A predetermined centre cannot be nominated because there are no purpose built structures (such as bunkers) designed to withstand the impacts of a bushfire. This means the location of an evacuation centre is not determined until the position of the fire and the characteristics of a specific event are considered by authorities. There would be nothing more dangerous than sending residents to a centre which is in the direct path of a fire.

The safest place to be during a bushfire is away from it. Where to go is an important element when people are relocating during a time of emergency (NSW Rural Fire Service 2004). The preferred option for residents is to designate a destination that is not in a bushfire-prone area and will be safe to travel to before a bushfire attack.

Those who find themselves threatened by a bushfire need options (VBRC 2009). This may be because their plan to leave is no longer possible because they cannot reach a place away from the fire front, or their plan to defend their property fails. Residents may also be caught away from their home when a bushfire threatens.

The concept of a "Neighbourhood Safer Place" and Neighbourhood Safer Precincts" has arisen from recommendations by the Victorian Bushfire Royal Commission into the Black Saturday bushfires.

There are many areas within the City of Wanneroo including urban areas within Banksia Grove that are not bushfire-prone, but they have not been declared. Obviously a non-bushfire-prone area can provide a safe location for people during a bushfire, but there is no official criteria in Western Australia to determine these areas. As there is no specific criteria to guide this process, FESA's general advice is for residents, when their household bushfire survival plans have failed, is to go to a safer place such as a local open space or building where people may go to seek shelter from a bushfire (FESA 2010).

6. Conclusion

This plan provides acceptable solutions and responses to the performance criteria that fulfil the intent of the bushfire hazard management issues outlined in Planning for Bushfire Protection Guidelines - Edition 2 (WAPC et al. 2010). However, community bushfire safety is a shared responsibility between governments, fire agencies, communities and individuals.

The planning and building controls outlined in this plan will reduce the risk of bushfire to people and property, it will not remove all risk. How people interpret the risk, prepare and maintain their properties and buildings and what decisions and actions they take (i.e. evacuate early or stay and defend or other) greatly influence their personal safety. Residents need to be self reliant, and not expect warnings or assistance from emergency services.

6.1 Compliance Checklist for Performance Criteria and Acceptable Solutions

Element	Question	Answer
1: Location	Does the proposal comply with the performance criteria by applying acceptable solution A1.1?	Yes
2: Vehicular access	Does the proposal comply with the performance criteria by applying acceptable solution A2.1?	Yes

Element	Question	Answer
2: Vehicular access	Does the proposal comply with the performance criteria by applying acceptable solution A2.2?	Yes
	Does the proposal comply with the performance criteria by applying acceptable solution A2.3?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.4?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.5?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.6?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.7?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.8?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A2.9?	N/A
3: Water	Does the proposal comply with the performance criteria by applying acceptable solution A2.10?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A3.1?	Yes
	Does the proposal comply with the performance criteria by applying acceptable solution A3.2?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A3.3?	N/A

Element	Question	Answer
4: Siting of the Development	Does the proposal comply with the performance criteria by applying acceptable solution A4.1?	Yes - Construction standards are increased to align with site bushfire attack level.
	Does the proposal comply with the performance criteria by applying acceptable solution A4.2?	N/A
	Does the proposal comply with the performance criteria by applying acceptable solution A4.3?	Yes
	Does the proposal comply with the performance criteria by applying acceptable solution A4.4?	No - However the proposal does satisfactorily comply with performance criterion P4 because building construction standards are to be increased to comply with AS 3959-2009 to offset the removed Hazard Separation Zone. Construction standards will achieve a maximum of BAL-29.
	Does the proposal comply with the performance criteria by applying acceptable solution A4.5?	Yes - Shielding might be applicable as individual dwellings may have shielded walls not exposed to the direct impact of radiant heat.

Element	Question	Answer
5: Design of the Development	Does the proposal comply with the performance criteria by applying acceptable solution A5.1?	No - However the proposal does comply with the performance criterion P5 because building construction standards will be increased to comply with AS 3959-2009 to offset the requirement for a HSZ. BAL-29 is not exceeded.
	Does the proposal comply with the performance criteria by applying acceptable solution A5.2?	Yes - The proposal complies as the development will meet the performance criteria because of compliance with AS 3959 and BAL-29 is not exceeded.

7. Implementing the Fire Management Plan

7.1 Developer's Responsibilities

To maintain a reduced level of risk from bushfire, the developer's responsibilities are to:

- Install the public road to standards outlined in Element 6.2 Vehicular Access
- Install water supply and hydrant to comply with standards outlined in Element 6.3 Water
- Install the Building Protection Zone across the entire site and maintain until each individual lot is sold
- Lodge a Section 70A Notification on each Certificate of Title exposed to AS 3959 construction standards, proposed by this subdivision. The notification shall alert purchasers and successors in title, to these exposed lots, of the responsibilities of the Fire Management Plan and bush fire building construction requirements
- Comply with the City of Wanneroo's Fire Control Notice as published, on all vacant land, and
- Supply a copy of this Fire Management Plan and The Homeowners Bush Fire Survival Manual, Prepare, Act, Survive (or similar suitable documentation) and the City of Wanneroo's Fire Break Notice to each lot owner subject to AS 3959 construction standards.

7.2 Property Owners' Responsibilities

The owners/occupiers of the site, as created by this proposal, are to maintain a reduced level of risk from bushfire, and will be responsible for undertaking, complying and implementing measures to protect their own assets (and people under their care) from the threat and risk of bushfire. The owners' will be responsible for:

- Complying with the City of Wanneroo's annual Firebreak Notice
- Ensuring that vacant lots comply with the City of Wanneroo's Fire Control Notice
- Ensuring construction of dwellings complies with AS 3959, and
- Establishing and maintaining the BPZ at the property owner's/occupier's own cost.

As part of the building license application, the property owner or the City of Wanneroo (at the property owner's expense) shall have the proposed dwelling re-assessed for Bushfire Attack Level (at the time of construction) with results to be submitted as part of the building licence application.

7.3 City of Wanneroo's Responsibilities

The responsibility for compliance with the law rests with individual property owners and occupiers and the following conditions are not intended to unnecessarily transfer some of the responsibilities to the City of Wanneroo.

The City of Wanneroo shall be responsible for:

- Providing fire prevention and preparedness advice to landowners upon request
- Monitoring bush fuel loads in all areas of public open space, road reserve sites and liaising with relevant stakeholders to maintain fuel loads at safe levels
- Maintaining public roads to appropriate standards and ensuring compliance with the City of Wanneroo's Fire Control Notice
- Ensuring dwellings are constructed to AS 3959 where applicable, and
- Endorsing a section 70A notification on each title affected by this Fire Management Plan.

7.4 FESA's Responsibilities

FESA is required to maintain district fire fighting capabilities for structural and bush fires.

Applicant Declaration

I declare that the information provided is true and correct to the best of my knowledge.

Full name: Rohan Carboon

Applicant signature: 

Date: 16 June, 2015

8. References

- Abbott, I. (2003). Aboriginal fire regimes in south-west Western Australia: evidence from historical documents. Pages 119-146 in I. Abbott and N. Burrows, editors. Fire in ecosystems of south-west Western Australia: impacts and management. Backhuys, Leiden, The Netherlands.
- Blanchi, R. Lucas, C. Leonard, J and Finkele K. (2010) Meteorological conditions and wildfire -related house loss in Australia. CSIRO Publishing, Melbourne
- Burrows, N., and I. Abbott. 2003. Fire in south-west Western Australia: synthesis of current knowledge, management implications and new research directions. Pages 437-452 in N. Burrows and I. Abbott, editors. Fire in ecosystems of south-west Western Australia: impacts and management. Backhuys, Leiden, The Netherlands.
- Cheney P & Sullivan P (2008) Grassfires. Fuel, Weather and Fire Behaviour. 2nd edition CSIRO Publishing.
- Crisp M. D, Burrows G. E, Cook L. G, Thornhil A. HI & Bowman D (2011) Flammable biomes dominated by eucalypts originated at the Cretaceous–Palaeogene boundary. In Nature Communications 2. Article No 193.
- FESA (2010) PREPARE. ACT. SURVIVE. Your guide to preparing for and surviving the bushfire season booklet
- Gibbons P, van Bommel L, Gill AM, Cary GJ, Driscoll DA, et al. (2012) Land Management Practices Associated with House Loss in Wildfires. PLoS ONE 7(1): e29212. doi:10.1371/journal.pone.0029212
- Gould J. S, McCaw W. L, Cheeney N. P, Ellis P. F, Knight I. K, and Sullivan A. L (2007) Project Vesta - Fire in Dry Eucalypt Forest: Fuel Structure, fuel dynamics and fire behaviour. Ensis-CSIRO, Canberra ACT, and Department of Environment and Conservation, Perth WA.
- Hallam, S. J. 1975. Fire and Hearth: A study of Aboriginal usage and European surpation in south-western Australia. Australian Institute of Aboriginal Studies, Canberra, Australia.
- NSW Rural Fire Service (2004) Bushfire Evacuation Plans (see: www.rfs.nsw.gov.au)

Ramsay C, and Rudolf L (2003) Landscape and Building Design for Bushfire Areas. CSIRO Publishing, Collingwood. Australia.

Risk Frontiers, Bushfire CRC and RMIT University (2008). 100 Years of Australian civilian bushfire fatalities: exploring the trends in relation to the 'stay or go policy' Report for the Bushfire CRC http://www.bushfirecrc.com/research/downloads/Fatality-Report_final_new.pdf

Standards Australia. (2009) Australian Standard AS 3959-2009 Construction of buildings in bushfire-prone areas.

Victorian Bushfires Royal Commission (VBRC) Interim Report (2009). Government Printer for the State of Victoria.

Victorian Bushfires Royal Commission (VBRC) Final Report (2010). Government Printer for the State of Victoria.

Western Australian Planning Commission (WAPC), FESA and Department of Planning and Infrastructure (2010), Planning for Bush Fire Protection - Edition 2. Western Australian Planning Commission, Perth.

Walker, J. 1981. Fuel dynamics in Australian vegetation. Pages 101-127 in A. M. Gill, R. H. Groves, and I. R. Noble, editors. Fire and the Australian biota. Australian Academy of Science, Canberra, Australia.



APPENDIX A: SITE LOCATION PLAN

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND:

SUBJECT LAND.....



NORTH

0 100 200 300m

SCALE 1:15 000 @ A4

DATE: MAY 2015

Base mapping supplied by Nearmap & Google Maps

Bushfire Safety
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 940 262
www.bushfiresafety.net



APPENDIX B
Site Plan

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



NORTH

0 25 50 75 100 125 150m

SCALE 1:3500 @ A3
DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire  **Safety**
CONSULTING

BUSHFIRE SAFETY CONSULTING


PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net



Appendix C

All road carriageway detail depicted on this subdivision plan including road pavements, road treatments, medians or parking, are for illustrative purposes only and are subject to final engineering design and separate approval processes. The detail reflects the preferred urban design intent for the road network standards.

All dimensions and areas depicted on this plan are subject to pre-col and final survey and will vary from the figures shown. This plan remains the property of CLE.



APPENDIX D

DRAFT




CONCEPT PLAN - SPECIAL RESIDENTIAL
Lots 4000-4008, 4010-4012 Moort Rise
City of Wanneroo






plan no: 981-438-01
scale: 1:4000 @ A4
date: 20.11.2014

T: (+618) 9382 1233 F: (+618) 9382 1127
E: admin@cleplan.com.au
www.cleplan.com.au
L2-38 ROWLAND STREET SUBIACO WA 6008
PO BOX 796 SUBIACO WA 6904



LEGEND

	LOW WOODLAND
	SCRUB
	MINERAL EARTH OR MANAGED VEGETATION (Low threat)

APPENDIX E

VEGETATION CLASSIFICATION EXISTING CONDITION

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



NORTH

0 25 50 75 100 125 150m


SCALE 1:3500 @ A3
DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire Safety
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net



APPENDIX F

BUSHFIRE HAZARD RATING EXISTING CONDITION

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



NORTH

0 25 50 75 100 125 150m


SCALE 1:3500 @ A3
DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire  **Safety**
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net



APPENDIX G VEHICULAR ACCESS

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



0 25 50 75 100 125 150m


SCALE 1:3500 @ A3
DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire Safety
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net



APPENDIX H BUILDING SITING AND BPZ

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



NORTH

0 25 50 75 100 125 150m


SCALE 1:3500 @ A3
DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire Safety
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net



APPENDIX I MAXIMUM INDICATIVE BAL RATINGS

MOORT RISE
BANKSIA GROVE
City of Wanneroo

LEGEND

SUBJECT LAND.....



SOURCE:
PHOTOGRAPHY FROM NEARMAP



NORTH

0 25 50 75 100 125 150m

SCALE 1:3500 @ A3

DATE: MAY 2015

Base mapping supplied by CLE Town Planning + Design

Bushfire Safety
CONSULTING

BUSHFIRE SAFETY CONSULTING

PO BOX 84 STONEVILLE WA 6081
Mbl: 0429 949 262
www.bushfiresafety.net